

CITY OF COLORADO SPRINGS PRE-APPROVED CONCRETE AND CLSM MIX DESIGNS
 The concrete and CLSM mix designs listed below are preapproved for use on projects project in the City.

12-Jan-24

Expiration Date	Mix Design Identification	Description	Design Water/Cement Ratio
BURNCO (FKA ACTION) READY MIX			
4/30/2024	40E4C1C2M	Machine - Low Slump 4000 psi	0.45
4/30/2024	40E4C1C4C	Hand Set 4000 psi	0.45
4/30/2024	40E401C4C	Hand Set 4000 psi	0.45
4/30/2024	40G4C1C2M	Machine - Low Slump 4000 psi	0.45
4/30/2024	45EC1C4C	CDOT DBP 4,500 psi	0.45
4/30/2024	01HB01B6F	100 PSI Flowfill	NA
SRM (SMYRNA READY MIX) CONCRETE			
4/30/2024	40022	4000 PSI CS Curb	0.45
4/30/2024	40020	4000 PSI CS FLATWORK	0.45
4/30/2024	40220	4000 PSI CS Median Cover	0.45
4/30/2024	926	Colorado Springs Flow Fill	NA
HOLCIM (FKA TRANSIT MIX) CONCRETE			
4/30/2024	T14082110	City Mix w/ 100% Cement (IL)	0.45
4/30/2024	T14062110	City Curb Machine w/ 100% Cement	0.44
4/30/2024	CLSMCITY	CLSMCITY - City Flow-Fill	NA
4/30/2024	3408211020	NWC City Exterior Mix	0.45
4/30/2024	T34062110	City Mix (Curb Machine) w 20% FA	0.45
4/30/2024	2200CITY	Accerelated FlowFill (CLSM)	NA
PETE LIEN & SONS			
4/30/2024	90CG51	Fast Track	0.41
4/30/2024	40CG50	Hand Set	0.45
4/30/2024	40DG50	Hand Set- 4000 psi w/ FA	0.45
4/30/2024	05CA02	CLSM	
LUCKY DOG			
12/31/2024	0138FFCS	CLSM Flow Fill (Colorado Springs)	NA
12/31/2024	015767FFCS	CLSM Flow Fill (Colorado Springs)	NA
On Demand			
12/31/2024	CSFF100C	CLSM FlowFill	NA
PATE CONSTRUCTION			
12/31/2024	CS150FF	CLSM (Flowfill)	NA
HCD			
12/31/2024	COHDCSSFF71023	CLSM (Flowfill)	NA
A-C CONCRETE			
4/30/2024	AC-220-006	CSU-COS Structural CLSM (Utility Only)	NA