



**Present Fire Board of Appeals Board Members (6):**

David Hewett, Chair  
Ron Honn, Vice Chair  
Vince Colarelli  
Mike Riggs  
Jannic Ekornes  
Laurie Olsen

**Industry Represented:**

Small Business  
Citizen At-Large  
Building  
Architecture  
Fire Suppression  
Insurance

**Not Present (0):**

**Industry Represented:**

**Vacant Position (1):**

-

**Industry Represented:**

Large Business

**Present Fire Board of Appeals Secretary**

Brett T. Lacey, Fire Marshal

**Representing:**

Colorado Springs Fire Department

**Additional Attendee(s):**

Desirae Tucker, Administrative Assistant Senior  
Mellisa Wutzke, Administrative Assistant Senior  
Captain Richard Valdez, Deputy Fire Marshal  
Connie Manning, Compliance Coordinator  
Roland Peterson, Senior Fire Inspector  
Phil Valdez, Senior Fire Inspector  
Jacob Watson, Fire Protection Engineer I  
Michael Starke, Fire Inspector II  
Sarah DaCosta, Administrative Assistant II  
Kris Cooper, Deputy Fire Marshal  
Katie Claar, Engineer II  
Keith Buckmiller, Citizen  
Randy Purvis, Homeowner  
Robin Purvis, Homeowner  
Scott Hente, Builder  
Nelson Daily, Citizen

**Representing:**

Colorado Springs Fire Department  
Colorado Springs Fire Department  
Colorado Springs Fire Department  
Colorado Springs Fire Department  
Colorado Springs Fire Department  
Colorado Springs Fire Department  
Colorado Springs Fire Department  
Colorado Springs Fire Department  
Colorado Springs Fire Department  
Colorado Springs Fire Department  
Colorado Springs Fire Department  
Colorado Springs Utilities  
400 Dahlia Street  
400 Dahlia Street  
400 Dahlia Street  
Robert Scott General Contractors, Inc.  
Observer

**CALL TO ORDER**

1. Board Chair Hewett called the meeting to order at 8:28 A.M. and promptly conducted a roll call.

**ADMINISTRATIVE**

1. Approval of Meeting Minutes

Board Member Colarelli motioned to approve the meeting minutes.  
Board Member Olsen seconded the motion.

**The motion passed unanimously.**

**2. Contractor Licensing**

**A. Fire Alarm Contractor B**

- i. Business Name:** APEX Integrated Systems, LLC  
**Applicant:** Mikel Foster  
**RME:** Mikel Foster

Fire Marshal Lacey stated applicant meets the requirements and recommended approval.

**Board Member Colarelli motioned to approve the application.  
Board Member Honn seconded the motion.  
The motion passed unanimously.**

**3. Appeal**

- A. Request by Builder Scott Hente of Robert Scott General Contractors, Inc., on behalf of homeowners Randy and Robin Purvis, requests relief from Colorado Springs City Ordinance 18-50, *Fire Prevention Code and Standards Appendix B, Fire-Flow Requirements for Buildings, Section B105.1* located at 400 Dahlia St., Colorado Springs, CO 80904**

Fire Marshal Lacey provided a background of the Colorado Springs Fire Department (CSFD) working with Builder Scott Hente on behalf of homeowners, Randy and Robin Purvis on the construction of a new home located at 400 Dahlia Street, Colorado Springs, Colorado. Due to the size of the home, the water flow available does not meet the fire flow code requirements. The water flow in this area is one of the remaining areas in Colorado Springs that are below the fire flow requirements. Fire Marshal Lacey introduced Katie Claar, Engineer II from the Water Infrastructure Planning at Colorado Springs Utilities (CSU) and she has been working with CSFD's Fire Protection Engineer, Dee Withee. For several months, discussions transpired to try and come up with a resolution to the water supply for the Purvises. Fire Protection Engineer Withee offered the appellants two resolutions. One was to install a residential sprinkler system or, two, to install a monitored alarm system. The intent for the monitored alarm system is if the CSFD could get early notification and rapid response, the fire could be kept to a minimal size. The appellants agreed to the monitored alarm system and the permit was issued. The appellants have since changed their minds and decided to appeal to the Fire Board of Appeals.

Fire Marshal Lacey introduced Roland Peterson, Senior Fire Inspector, CSFD.

Senior Fire Inspector Peterson provided information concerning the proposed residence at 400 Dahlia Street. The structure is a 5B building of 4938 square feet requiring a fire flow of 2000 gallons per minute (gpm). There is a theoretical fire flow of 800 gpm as well as an actual fire flow on 8/24/22 of 1388 gpm and a simultaneous fire flow on 10/4/22 of 1563 gpm. This is significantly short of the required fire flow. A compromise was made to allow a monitored alarm system in lieu of a fire sprinkler system

Chair Hewett asked for clarification that the initial expectation was a fire (sprinkler) system and the CSFD agreed to a fire alarm (monitoring system).

Senior Fire Inspector Peterson confirmed Chair Hewett's statement.

Fire Marshal Lacey clarified that the requirement is to have the required fire flow for the size of the house requested. There was further discussion between the appellant and the CSFD and the two options were offered. Upon further deliberation, it was decided that the CSFD would be ok with the alarm (monitoring) system.

Senior Fire Inspector Peterson stated there is an amendment in the fire code that allows a 50% reduction in fire flow requirement if the structure is sprinklered but have no less than 1500 gpm requirement at any given time for any given structure.

Chair Hewett asked if there were any other questions from the board for the CSFD.

Chair Hewett asked Builder Scott Hente to the podium.

Builder Scott Hente shared a presentation.  
(All supplemental documents follow these minutes).

Scott Hente stated they are requesting relief from the fire flow requirement specifically for the monitored alarm system for the house under construction at 400 Dahlia Street. There are several reasons they are asking for this request. They are replacing an older structure with a new home constructed to the current fire code requirements which is the 2018 Wildland Urban Interface (WUI) fire code requirements. This neighborhood has never been advised that fire flow is an issue, and he believes there is sufficient fire flow for firefighting purposes. He referenced a map in his presentation of the neighborhood where 400 Dahlia Street is located that he received from CSU. He highlighted the location of 400 Dahlia Street and the two nearest fire hydrants. Fire hydrant 768C is 25 feet from the property line of the new house. He used this map as a basis to define the neighborhood. The previous map showed 25 separate single-family residences in addition to other structures such as sheds and detached garages. With one exception, the ages of the homes range from 33 to 119 years old. To the best of his knowledge, with one exception, no home in the neighborhood has a sprinkler system or a monitored alarm system. 400 Dahlia Street will be the only home built on the referenced map built to current fire codes and will be held to a higher standard of fire flow than any of the other houses, some of that are over 100 years old. The previous structure at 400 Dahlia Street was a dilapidated art studio that was built 60 years ago. It was a fire hazard and not in compliance with anything. If his customers had not purchased the lot, this structure would still be there today and present a hazard to the neighborhood. His customers have replaced this with a structure that is in compliance with modern fire codes, recent city ordinances, and 2018 WUI requirements. The Purvises are 32-year residents of this neighborhood. Their current residence is three doors from 400 Dahlia Street. None of the residences have ever been told this is an issue, and if it is an issue, why have there been no improvements to the overall system? Scott Hente confirmed that they have been in communication for many months with the CSFD before and after they pulled the permit. During this time, he asked CSU why they have not fixed the water issue. He was told it came down to money. The house they are building is being held to a higher standard and a higher fire code. They (appellants) believe there is sufficient flow. The appellants waited until after they pulled the permit to ask for this waiver because they started asking questions of others, including fire flow professionals, and former firefighters if this is really an issue. There are two hydrants that are on a double loop and if you use one of the hydrants shown on the map, it can handle multiple handlines that are available to the fire department. There are also the banks of the preconnected hoses that are on the fire trucks. Thus, the appellants feel there is sufficient flow, especially concerning a house that is being built to modern standards with materials such as ignition-free exterior surfaces. Since they are building to

the newest, most current standards, they are asking the requirement for the monitored alarm system to be waived.

Chair Hewett asked if there are any questions from the board members.

Board Member Colarelli asked Scott Hente about the change of the 400 square feet in the house compared to what was originally submitted.

Scott Hente replied he is not sure what he is referring to as the plans submitted to the building department have been submitted and approved.

Board Member Colarelli stated okay, and that the remainder of his questions are for the CSFD.

Board Member Riggs stated Scott Hente referenced hazards to existing residences and asked if he knows the size of the existing residences.

Scott Hente replied he has a list of all of them and they run the gamut ranging in size from very small to a couple that are bigger than what they are building.

Board Member Riggs stated when the appellant received the permit, they made some decisions that were revised on the permit in November, and it was agreed that a fire alarm system would be installed.

Scott Hente stated all of those were agreed to before the issuing of the permit, there have been no changes since the permit was issued.

Board Member Riggs asked if it was agreed to in the permit.

Scott Hente replied yes, and they agreed to that. He further stated that Fire Marshal Lacey is correct in that the process to get this home approved took more than a year. There were several factors contributing to this including the waiver of replat with the city, supply chain issues, and increasing costs. There was a desire to get the project going and they agreed to install a monitored fire alarm system when the permit was issued. It was after this that the appellant started to consult with fire professionals which led to additional conversations with Fire Marshal Lacey. The appellant has been working on this for several months and almost initiated this request at the time they pulled the permit.

Board Member Ekornes asked if he knew if there are plans for CSU to improve the water lines in the area.

Scott Hente stated that he would let CSU answer that question, but every time he has talked to them, he has been told that it is going to cost a lot of money and they can't get to it. Because CSU cannot improve their infrastructure, they are asking one homeowner to bear the cost of that failure of not improving their infrastructure and he feels that is unfair.

Chair Hewett stated that Scott Hente commented that he is building a newer home and everything else in the area is not being required to upgrade.

Scott Hente stated there is one other possible exception in the map.

Chair Hewett stated he understood, but what it is important to understand is the Fire Board of Appeals (FBA) does not have the authority or the right to go back to an existing home and require they bring it up to standard unless something is being done. The rest of the



neighborhood can be referenced, but there is no enforcement ability to an existing structure unless they intend to make changes to that existing structure.

Scott Hente agrees but this is a hindrance for anyone that wants to make improvements if they know that they are going to have these increased costs.

Chair Hewett responded that he understood, but wants to make sure he understands Scott Hente's point of contention which is the rest of the homeowners do not have to abide by this because of their age.

Scott Hente is not trying to suggest automatically enforcing that, what he is saying is there is now one house that is held to this higher standard when the rest are not. If the desire is to fight a fire and protect the neighborhood, is that being done? He is not sure that it is.

Board Member Colarelli stated this has become an increasingly common problem. He knows from the commercial side he has had to take extraordinary measures to provide fire flow in buildings that would otherwise not require them because of a decrease in fire flow or decrease in water pressure in the CSU system. He can site 5 buildings in the last 18 months where he has had to do that.

Scott Hente stated he is not a fire professional but has someone in attendance who is and would like him to speak if the board will allow it.

Chair Hewett said absolutely.

Keith Buckmiller introduced himself. He has been in the fire service since 1980 with 35 years at the CSFD. He referenced a slide from Scott Hente's presentation that shows a 1300-gallon fire hydrant that would provide that much flow. That provides 5, 2 ½ inch lines that would provide 265 gpm. That is a lot of water. Also at 212 degrees, one cubic foot of water will expand 1600 times and that is what will be putting the fire out. Although the CSFD's numbers state what is generated is less than what is applicable, a lot of fire can be put out with that hydrant, he has done it before and is still doing it today. That is a lot of water. With the ISO (Insurance Service Office) rating, continuous water flow in Colorado Springs, the training of the CSFD firefighters, and the water system that gives a high ISO rating, a lot of work can be done with that much water. He thinks there is a lot of overkill in the numbers presented. If there was a conflagration in the area like the Marshall Fire, that hydrant will be relied upon for all the other houses, and it is not going to be there. The Purvises house will have a 1-hour rating on the inside and outside, so fire coming from the outside will take 1 hour to get in, and fire on the inside will take 1 hour to get out. In that process, the whole neighborhood is going to go up in flames, and firefighters will be put in there with an inadequate water system, to be able to catch those hydrants to do a pump and run to fight the fires. The system is bad, CSU should be put on notice that it is bad, and the neighborhood should be notified that it is bad. To put \$16,000-\$20,000 into the house on Dahlia, he does not see the reasoning behind that. He reiterated that there is a lot of water and that if the house caught on fire, he would put it out.

Chair Hewett asked if there were any questions from the board.

Scott Hente stated Mr. Purvis, the property owner, would like to address the board.

Property owner, Randy Purvis wanted to address the square footage issue. To his understanding, when the plans were first submitted, the architect added up the square footage in the garage, main floor, basement, the front and back porch and came to that figure. The CSFD stated that was a nice starting point, but additional measurements are

required to include the eave overhang and the area underneath the deck. That is how they got the additional 300 to 400 square feet which is what pushed the house up to a significantly higher category.

Board Member Colarelli thanked Mr. Purvis.

Chair Hewett asked if there were any additional questions or comments from the board.

Board Member Colarelli asked Chair Hewett if the board could ask CSFD staff questions.

Chair Hewett responded certainly.

Board Member Colarelli asked Senior Fire Protection Engineer Peterson if he had any historical data on what the fire flows have been in the area and if they have changed.

Fire Marshal Lacey stated that Katie Claar, CSU engineer, should speak to that.

Board Member Colarelli responded that he would table that question for a minute. He stated that in the write-up, the building's allowable square footage is described like a commercial building as opposed to a residential building. There is approximately 1700 square feet on the lower level of this building, presuming that there was a drywall assembly under the joist and the door was a fire-rated door that goes up. Is there a strategy that the homeowner might be able to consider allowing for fire separation between the upper and lower level to reduce the allowable square footage?

Senior Fire Inspector Peterson replied that the requirements to separate a building for fire flow purposes require a 2-hour unpenetrated fire wall. To create two separate dwelling units with that 2-hour horizontal assembly with no penetrations is the only way, per the adopted fire code, that it could be accomplished.

Board Member Colarelli stated technically, there is a solution available if the appellant is willing to consider it.

Senior Fire Inspector Peterson responded yes.

Board Member Colarelli asked in the plans as approved, would there have been a requirement for smoke detectors in the house regardless of the monitored fire alarm system.

Senior Fire Inspector Peterson replied that the smoke detectors, being 120 volt tied together with a battery backup are a requirement of the building code.

Board Member Colarelli clarified that the additional requirement from a technical standpoint, is the addition of the monitoring to that system.

Senior Fire Inspector Peterson stated that the technical requirement would be an NFPA (National Fire Protection Association) 72 compliant system that dials out to dispatch.

Board Member Colarelli clarified it is a monitored system with a dialer as compared to a traditional smoke detector system.

Senior Fire Inspector Peterson stated the traditional smoke alarms required from the building code sound individually and based on how they are wired, will sound all together.

A smoke detector goes to a central panel with a dialer that calls a monitoring company that calls dispatch.

Board Member Colarelli thanked him.

Board Member Riggs asked about fire flow reduction for fire sprinklers which is outlined in (NFPA)1142. In the IFC (International Fire Code) there is a provision for the fire marshal to potentially decrease fire flow and fire duration. Has he looked at that or has this been applicable in the past? Is there a pathway forward? The code could be read to imply rural communities as a part of that passage in (IFC)103.1.

Fire Marshal Lacey responded that Colorado Springs is not considered rural as it has a water distribution system. In rural fire departments, there is hard suction you can draft from static water sources or portable tanks. None of the CSFD apparatus have hard suction because of the robust distribution system. The only reasonable approach to deal with the lack of water was the mechanisms proposed by Fire Protection Engineer Withee. The fire suppression system is an active measure to address the fire in its incipient stage. With that proposal, there could be a tradeoff for insurance with possible payback for that system. The next alternative at a lower cost, is the monitored fire alarm system because if the CSFD gets early notification fast response, there would be less fire to use the water available to extinguish the fire in a way that former Chief Buckmiller spoke to.

Board Member Riggs asked how the fire flow gpm can be utilized for different size buildings and how the relationship between gpm increases and building square footage increases going tandem. Are there differences in how that availability affects how a fire is fought?

Fire Marshal Lacey provided a history of fire flow testing, research, and standards and how those standards from 1914 are utilized today. However, materials of today, like plastics and resins, burn vastly differently than materials from 1914. The relative conversion of the amount of water required to quench a fire based on steam conversion given the amount of fuel load per square foot, determines the amount of flow we are comfortable with to control the fire assuming maximum probable loss or involvement of that fire.

Board Member Riggs thanked Fire Marshal Lacey for his perspective.

Board Chair Hewett stated part of that comment is fires of today are going to burn faster and hotter than what the numbers dictated in the calculations.

Fire Marshal Lacey responded affirmatively, but continued research is comfortable to honor the tables as provided. Given the current application, the resources available such as technical equipment, and the way fire equipment is utilized.

Board Chair Hewett stated he understood and asked if there were any questions.

Board Member Colarelli asked about the statement about the CSFD's ability to fight a fire with limited water based on certain gpm and handline available. Will he comment on the CSFD's ability to fight a fire in this location given the limited amount of water flow?

Fire Marshal Lacey responded the CSFD will do the best job they can with the limited fire flow available. The only thing he can guarantee is that fire is unpredictable and the CSFD does an exceptional job. The only thing he is comfortable with as the fire code official is

looking at the square footage, the type of construction, and the fire code with the tables of fire flow.

Board Chair Hewett stated this comes back to the issue of response time and the potential of unnoticed burning. If the home was unoccupied at the time of a fire, the alarm that was agreed upon is the key element, is that correct?

Fire Marshal Lacey agreed and explained that it is the CSFD's premise behind the consideration of the reduced fire flow that this would be acceptable due to the early notification and response.

Fire Marshal Lacey had Senior Fire Inspector Peterson return to the podium.

Senior Fire Inspector Peterson provided additional information about construction in the neighborhood. 411 Columbia Road, a property that touches 400 Dahlia, was a 2017 tear-down/rebuild of a home and was equipped with a residential fire sprinkler system. A home at 613 Columbia Court just received a certificate of occupancy and has a fire alarm system provided by Westerns States Fire Protection. 606 and 696 Columbia, and 516 Laurel Street have monitored fire alarm systems. 969 Columbia Court has both a fire alarm and a fire sprinkler system. These are five examples of homes in the area with systems one which is directly adjacent to 400 Dahlia Street.

Board Chair Hewett asked if these are all remodeled or built in a recent time period.

Senior Fire Inspector Peterson responded affirmatively with 969 Columbia Court being the oldest which was permitted in 2001.

Board Chair Hewett thanked Senior Fire Inspector Peterson.

Board Member Ekornes asked if a neighbor wanted to remodel their house, would they have to install a sprinkler system or alarm system?

Senior Fire Inspector Peterson responded it is based on the increase in square footage. He gave the example at 7 Swallow Drive which is a current remodel/addition that is across from 400 Dahlia Street. The addition did not increase the fire flow requirement for that structure.

Fire Marshal Lacey addressed the board and stated Sarah (DaCosta) was handing out the Staff Summary Report which was not included in the packet provided to the board and the appellants. It is a summary of the CSFD's staff opinion. He apologized for the omission and stated it would not happen again. (All supplemental documents follow these minutes).

Board Chair Hewett asked about the remodels Senior Fire Inspector Peterson mentioned. What are the square footages of these houses? He also stated 400 Dahlia Street is at 4938 square feet.

Senior Fire Inspector Peterson replied 613 Columbia Court is slightly smaller than 400 Dahlia Street being in the 3000 to 4000 square foot range. 411 Columbia Road is a comparable size, but he does not know the exact square footage. He is not familiar with the square footage of the others but believes they are roughly in the 3000 to 4000 square feet range.

Board Chair Hewett stated this neighborhood is going through a renaissance in other homes in the recent time period and asked if the appellant agree with that statement.

Scott Hente stated it varies house by house, some are remodels, and some are modernizing.

Board Chair Hewett stated that there is activity in the neighborhood.

Scott Hente replied that there is activity, and some do not change in square footage. He asked to address Board Member Colarelli's question.

Board Chair Hewett confirmed he could.

Scott Hente stated this is the first time he is seeing this document (referencing the Staff Summary Report).

Board Chair Hewett affirmed this is the case for the board as well,

Scott Hente stated Board Member Colarelli asked about the separation between the lower floor and the upper floor. Per the current fire code, he has to drywall the lid of the basement or if it is an unfinished area, he has to apply a fire retardant and has to provide a certificate at the time of the final building inspection. Thus, there is a separation between floors. There are other things they have done to decrease the fire risk at this home such as arc fault circuit protectors, the drywall is better, and other things required in the building code that help protect the structure even more than the structure that was there previously. He does not want the board to think he misled them. He used the homes in the map he was provided by CSU and the homes Senior Fire Inspector Peterson referenced were outside that map.

Board Chair Hewett stated he understood nor did he think that was the neighborhood and thanked Scott Hente.

Fire Marshal Lacey apologized for the omission of the Staff Summary Report, it is his responsibility that the packet is complete. The Staff Summary Report is provided to everyone as to why the recommendation was given. He offered everyone to take time to read it. The summary goes along with the recommendation that has been verbalized in testimony.

Board Chair Hewett appreciates Fire Marshal Lacey's comments and for everyone to take time to read the Staff Summary Report.

Scott Hente asked if CSU to come up to address the board.

Board Chair Hewett stated the job of the board is to review everything, but this board is not in control of CSU. He does want to hear the information and asked Katie Claar to the podium.

Katie Claar, CSU Engineer II provided information on the water flow in this neighborhood. The fire flow is low in this area because of aged infrastructure, the area is provided water from a single feed and has 6-inch pipelines. Eventually, these will be replaced with eight-inch water mains but there is no telling when the budget will be available. They have a finished water linear asset program where they have a risk model that considers the size, material, condition, and criticality of all the water mains and prioritizes all the water mains throughout the city that need to be replaced. Eventually, these water mains will fall under that. They have had a lot of fire studies for vulnerable areas within the city. They have

some recommendations to improve the fire flows in this area, but it depends on when the budget becomes available to do projects in this area.

Board Member Colarelli asked if it is her opinion that the fire flow has decreased over time in this area.

Engineer II Claar thinks they have decreased marginally because of aging infrastructure and as the pipe degrades, fire flows decrease. Due to the size of the pipes and the location she believes the flow was low at the time of construction.

Board Member Colarelli stated there was an actual fire flow of 1388(gpm). What would have been expected 20 years ago?

Engineer II Claar is not sure how much higher it would have been 20 years ago but does not think it would have been that much higher.

Board Member Colarelli asked if it would likely have been 2000(gpm).

Engineer II Claar responded no.

Board Member Colarelli asked if it would likely have been 1500(gpm).

Engineer II Claar replied yes.

Board Member Colarelli inquired if the aging infrastructure would cause this to decrease by 10%.

Engineer II Claar replied approximately.

Board Member Colarelli stated to be clear, the aging infrastructure is wear and tear on the inside face of the pipes.

Engineer II Claar responded with a confirmation.

Board Member Colarelli asked if this would increase friction loss and reduce flow.

Engineer II Claar responded with a confirmation.

Fire Marshal Lacey stated the material found in aging infrastructure such as cast iron, tuberculates, and corrodes causing the pipe diameter to shrink and reduce water flow. Current materials have eradicated this problem.

Board Chair Hewett asked if there are additional comments or questions from the board members or the appellant.

Appellant Randy Purvis stated per a map from CSU, there is a line coming west on Pikes Peak Avenue that turns north up Columbia and there is a second line coming down from Mesa that enters at the end of Columbia Road. It is a bi-fed neighborhood.

Board Member Colarelli stated that the CSFD has asked the appellant to install a monitored fire detection and fire alarm system as compared to the fire alarm and detection system that they would have to install under the code. What is their aversion to installing the system?

Appellant Randy Purvis responded there are three steps in the fire alarm system as he understands it. One is the code bare minimum, where there are alarms at various points throughout the house that are tied together that alarms only inside the building. The other end of the extreme, which is what they are being asked to do, is the alarm is all wired together to a central panel and the central panel buys a cell phone line. This neighborhood does not have good cell service, which brings additional concerns. The in-between option is a fire alarm/burglar alarm system that is monitored by an external agency. He thinks the bare minimum cost of this is about \$500 to \$600 and asked (Scott Hente) for confirmation.

Scott Hente does not think it costs that much but does not think of this as an additional cost as that is part of the building code, and it is built into the cost of the house.

Board Chair Hewett stated that he (Randy Purvis) is talking about the additional cost for the monitored alarm system.

Scott Hente stated he knows that cost.

Board Chair Hewett stated that is what Randy Purvis is trying to resolve.

Scott Hente stated that he knows that cost.

Board Chair Hewett asked what the cost is.

Scott Hente stated it is in the \$16,000 to \$20,000 range.

Randy Purvis stated he estimates the in-between option cost is \$1000 to \$2000.

Board Chair Hewett asked Board Member Colarelli if this answers his question.

Board Member Colarelli questioned if the compelling reason for the variance is to avert the additional cost.

Randy Purvis stated, in his point of view, it is the additional expense for a benefit that cannot be rationalized by the cost of the benefit. He can rationalize the in-between option where an alert is sent to an outside company.

Board Member Colarelli thanked him.

Board Chair Hewett asked if there were any additional questions or comments from the appellant.

Scott Hente responded no.

Board Chair Hewett asked if Fire Marshal Lacey had any additional comments.

Fire Marshal Lacey responded no.

Board Chair Hewett explained the process in the voting procedure.

Board Chair Hewett stated he has heard no further comments from the board, the appellant, or the fire marshal. He requested a motion to approve or deny from the board.

**Board Member Riggs motioned to deny the request for relief from Colorado Springs City Ordinance 18-50, *Fire Prevention Code and Standards***

**Appendix B, Fire-Flow Requirements for Buildings, Section B105.1 located at 400 Dahlia St., Colorado Springs, CO 80904.**

**Ekornes seconded the motion.**

**The motion passes unanimously.**

Board Chair Hewett explained he will ask each board member individually for their vote and the reason for their vote.

Board Member Olsen denied the request stating when it comes down to it, the fire department's ammunition is water supply, despite all the equipment, training efficiency, the firefighters and adequate water supply for this type of home is critical and plays the most important role in saving lives and property. She agrees the monitored fire alarm system is reasonable.

Board Member Riggs voted to disapprove the appeal. The intent of the code is incremental improvement to improve not only your own structure but for the benefit and safety of those surrounding the facility. The code is pretty prescriptive but also provides options for what you can do in certain locations and guidelines whether that is a cap on square footage based on known elements, or through fire sprinkler systems, or through alternative means and methods. One of the alternative means and methods that the fire marshal has within his authority is to allow a monitored fire alarm system. Between those options, there are things that are available that could be employed and thinks this is a reasonable element to be employed.

Board Member Colarelli voted to deny and could not have said it better than Mr. Riggs.

Board Member Ekornes agrees with the motion. He stated that the national building code requires sprinkler systems in all buildings, but the CSFD has not adopted that. He thinks it is reasonable that they have allowed the appellant to do a monitored alarm system and also, it was agreed to in a meeting before the permit was approved that it would be supplied.

Board Vice Chair Honn votes with the group and sticking with the code and enforcing the code. He believes it is a reasonable accommodation.

Board Chair Hewett votes to deny. His reasoning is the appellant is in a situation where it is a changing neighborhood and, in his mind, is asking to keep what is in the neighborhood, unfortunately, the reality of where we live today, we have to have these codes. We have seen two egregious fires in our city in the last ten to twelve years. It is our job to protect our city and that is a job for every citizen here. We each get different ways we have to do that whether it be in a remodeling instance or a rebuilding instance. It does seem harsh at times, it doesn't always seem fair, but we don't have the legal ability to go back to every house and say you are coming up to today's code. But we do have the ability in the system that we live in to say that something new has to come within code or something is being remodeled. And so, we do the best we can. So, at this point, based on our vote today, your appeal is denied.

Board Chair Hewett asked if there are any other questions or comments.

**ADJOURN**

**Board Member Colarelli motioned to adjourn.**


**Board Member Olsen seconded the motion.**

**The motion passed unanimously.**



**The meeting adjourned at 9:34 A.M.**

Respectfully submitted by,

A handwritten signature in black ink, appearing to read "Brett T. Lacey". The signature is fluid and cursive, with a large, sweeping flourish at the end.

Brett T. Lacey  
Fire Marshal and Secretary to the Fire Board of Appeal

BTL/cm

**From:** [City of Colorado Springs](#)  
**To:** [Manning, Connie S](#)  
**Subject:** Fire Board of Appeals Application  
**Date:** Thursday, May 18, 2023 1:26:53 PM

---

<p>Submitted on Thursday, May 18, 2023 - 1:26 pm<br>

Submitted by user: Visitor<br>

Submitted values are:<br>

Date of Request: 2023-05-18

Project/Facility Information

-----  
Name: Robin Purvis, Randall Purvis (Owners) Robert Scott General Contractors, Inc. (Builder)

Address/Location:

400 Dahlia St.

Colorado Springs, Colorado. 80904

United States

Applicant Information

-----  
Name: Scott Hente

Title: Builder

Organization: Robert Scott General Contractors, Inc.

Mailing Address:

9850 Highland Glen Place

Colorado Springs, Colorado. 80920

United States

Phone Number: 719-499-6752

Email: scotthente75@gmail.com

Which code requirement do you disagree with? (include code section and inspection report number):

Hydrant Flow of 2,000 gpm requirement based on Table B105.1(2) from the International Fire Code

Why do you believe the code should not be followed? How does your solution address the intent of the code?:

A. Equity

1. Existing buildings do not have these requirements

What good is a monitor in the home if the CSFD cannot put out a fire in neighboring homes

2. Existing buildings have not had fire flow / mitigation requirements imposed on building permits

3. Imposes a "fix" randomly on new construction for water department failures

As water customers we are paying for a service that is not being provided

Why isn't fire flow adequate?

Age of pipes

Valves not reset from prior tests, fires elsewhere on the system

4. Cost of Compliance is disproportionately large.

\$16,000 +/- to install alarm system

Monthly operating expense: Unknown

Cost Information was not communicated to the builder or the homeowner prior to imposing the requirement.

B. Does not solve the problem

1. If fire flow is an issue – it is a City problem
  - Is it on the CSU capital improvements budget radar?
  - Any CSU plans to replace basic, 100-year old infrastructure?
  - How does this meet City goals of encouraging in-fill
2. If fire flow is insufficient, it affects all buildings in the vicinity
  - To provide fire protection for existing homes
  - To prevent spread of fire between existing homes
  - To prevent rapid spread of fire within existing homes
    - Built to older versions of building codes
    - Built before adoption of any building codes

C. Is it really needed?

1. Flow Requirements

Fire Flow per simultaneous test conducted 10-04-2022: 1675  
(Hydrants 768-C and 1297-C)

Sq Ft per plans: 4687      Fire flow requirement: 1750  
Sq Ft per submittal: 4938      Fire flow requirement: 2000

2. Fire flow is in fact adequate

Use of 2-inch hose to fight fire

The measured flows would supply:

- 5 lines @ 265 GPM with 1&1/8" tip @ 50 psi
- 4 lines @ 325GPM with 1&1/4" tip @ 50 psi
- 3 lines @ 400 GPM with 1&3/8" tip @ 50 psi

Adequate for fire fighting

3. As new construction, the home will meet existing codes have greater safety

Class A roof

Double Paned Windows

Greater fire blocking that meets current Building Codes

Exterior clad fire rated materials per Colorado Springs requirements for the Wildland Urban Interface (WUI)

4. CSFD has a very good ISO rating: 3 of 10

Additional Information

Discussed with Fire Marshal Rep.?: Yes

If so, with whom?: Fire Marshall Lacey and Deputy Fire Marshall Valdez

Alternative Solutions?: Yes

What is your proposed solution through alternate means or methods? (Be specific):

Construct a home to modern codes and Colorado Springs Current fire rated requirements and remove requirement stated on PPRBD Approved plans for an "Installed Monitored Fire Alarm System Per Code Requirements." (Approved PPRBD plan set, page 4.)

If yes, why were they unacceptable?:

An additional alternative discussed was a Sprinkler system

Unacceptable for the same reasons; even more expensive.

</p>

<hr>

<p>The results of this submission may be viewed at:<br>



**Colorado Springs Utilities**  
It's how we're all connected

*Water Services Division  
Operations Department*

## *Fire Flow Test Report*

<b>DATE:</b>	10/20/2022		
<b>WORK ORDER #:</b>	3913729		
<b>REQUESTER NAME:</b>	Elena Hepworth LGA Studios	Requester #1	Requester #2
<b>FAX #/Email:</b>	elenah@LGASudios.com		
<b>PHONE #:</b>	719-635-0880 ext 104		
<b>LOCATION:</b>	400 Dahlia St		
<b>FLOWING HYDRANT #:</b>	767-C		
<b>NOZZLE SIZE:</b>	2.5		
<b>WATER MAIN SIZE:</b>			
<b>FLOW HYDRANT STATIC PSI:</b>	115		
<b>PITOT (PSI):</b>	36		
<b>FLOW (GPM):</b>	1007		
<b>RESIDUAL HYDRANT #:</b>	768-C		
<b>RESIDUAL HYD STATIC PSI:</b>	132		
<b>WATER MAIN SIZE:</b>			
<b>RESIDUAL PRESSURE (PSI):</b>	62		
<b>FIRE DEPT REVIEW PLAN #:</b>			
<b>FIRE INSPECTOR:</b>			
<b>CSFD REQUIRED FLOW (GPM):</b>			
<b>CALCULATED FLOW @ 20 PSI</b>	1298		
<b>RESIDUAL (GPM):</b>	Contact Fire Inspector to obtain Official Final Fire Flow Calculations.		

**COMMENTS:**

*Please call with questions or comments.  
Thank You  
Sean Higbee, Water Distribution Supervisor  
Distribution: Fire Prevention (CSFD 385-7334)*

**404 W. FONTANERO ST. BUILDING 457  
P.O. BOX 1103, MAIL CODE 1210  
COLORADO SPRINGS, CO 80947-1210  
PHONE 719-668-4595, FAX 719-668-2890, shigbee@csu.org, http://www.csu.org**



**Colorado Springs Utilities**  
It's how we're all connected

*Water Services Division  
Operations Department*


## *Fire Flow Test Report*

<b>DATE:</b>	10/20/2022		
<b>WORK ORDER #:</b>	3913729		
<b>REQUESTER NAME:</b>	Elena Hepworth LGA Studios	Requester #1	Requester #2
<b>FAX #/Email:</b>	elenah@LGASTudios.com		
<b>PHONE #:</b>	719-635-0880 ext 104		
<b>LOCATION:</b>	400 Dahlia St		
<b>FLOWING HYDRANT #:</b>	1297-C		
<b>NOZZLE SIZE:</b>	2.5		
<b>WATER MAIN SIZE:</b>			
<b>FLOW HYDRANT STATIC PSI:</b>	130		
<b>PITOT (PSI):</b>	60		
<b>FLOW (GPM):</b>	1300		
<b>RESIDUAL HYDRANT #:</b>	<b>768-C</b>		
<b>RESIDUAL HYD STATIC PSI:</b>	132		
<b>WATER MAIN SIZE:</b>			
<b>RESIDUAL PRESSURE (PSI):</b>	62		
<b>FIRE DEPT REVIEW PLAN #:</b>			
<b>FIRE INSPECTOR:</b>			
<b>CSFD REQUIRED FLOW (GPM):</b>			
<b>CALCULATED FLOW @ 20 PSI</b>	<b>1675</b>		
<b>RESIDUAL (GPM):</b>	Contact Fire Inspector to obtain Official Final Fire Flow Calculations.		

**COMMENTS:**

*Please call with questions or comments.  
Thank You  
Sean Higbee, Water Distribution Supervisor  
Distribution: Fire Prevention (CSFD 385-7334)*

**404 W. FONTANERO ST. BUILDING 457  
P.O. BOX 1103, MAIL CODE 1210  
COLORADO SPRINGS, CO 80947-1210  
PHONE 719-668-4595, FAX 719-668-2890, shigbee@csu.org, <http://www.csu.org>**



COLORADO SPRINGS FIRE PREVENTION  
PLAN REVIEW REPORT

May 22, 202

Tax Id: 7403204014

DSN:

**Project Description:** PURVIS RESIDENCE - 400 DAHLIA ST - NEW WUIO HOME HARDENED STRUCTURE REQUIRED

SYSTEMS: monitored fire alarm in lieu of fire flow - reference variance tab

CN:Code: IRC - 15 IFC - 15 PPRBC 17 /Class: R3 / Const: 5B /Stories: 2 /Size: 4938 /OL: 1

FH:Required Flow: 2000gpm /# Hydrants 2 /On site flow: 1688 PER ACTUAL 8/24/22 see PR comment for update 10.20.22

DV: NONE

Additional Comments:

**Business Name:** PURVIS RESIDENCE

**Address:** 00400 DAHLIA ST #400,

**Plan Id:** 20221410-HS-1

**Plan Description:** NEW RES DEV/HILSID

**Plan Status:** Approved

**Contractor:** LGA STUDIOS

**Review Status:** DISAPPROVED

**Plan Reviewer:** Trimble, James Charles

**Review Date:** 9/16/2022

**Comment**

FY1

\*\*\*\*\* (STANDARD COMMENT) This project is: PURVIS RESIDENCE - 400 DAHLIA ST - NEW WUIO HOME HARDENED STRUCTURE REQUIRED

This plan review is based on the requirements found within the adopted Editions of the International Building Code, International Fire Code and the related Standards.

Disapproved

(DISAPPROVED) INSUFFICIENT WATER/HYDRANTS

The available fire flows and/or number of hydrants at this location, do not meet the fire code requirements.

You have several options:

- 1) Reduce the Square Footage
- 2) Install a fire sprinkler system. (You can get a 50% reduction in required fire flows if you install an approved fire sprinkler system.)
- 3) Change the construction type

FY1

(STANDARD COMMENT) THE DISAPPROVED ITEMS MAY NOT CONSTITUTE A COMPLETE LIST OF VIOLATIONS.

It is the responsibility of the design professional to conduct a complete re-review of the plans for additional violations of the adopted codes/standards and incorrect information prior to resubmitting.

Page 21 of 61

(STANDARD COMMENT) CORRECTIONS

All corrections and comments are to be submitted back to RBD. Corrections are not accepted over the phone, via fax, email or verbally.

FY1

(STANDARD COMMENT) PERMITS

Insure all applicable permits are obtained from the Regional Building Department and the Colorado Springs Fire Department for the work that is being done at this site.

FY1

(STANDARD COMMENT) REVIEWS: 2015 IFC 105.4.4

Colorado Springs Fire Department plan reviews are based upon information provided on the drawings and/or the attached reference material. Issues or features that are not presented within the construction documents are assumed to be complaint with applicable codes/standards. It is the responsibility of the building owner to ensure that minimum code requirements are met as established by the Authority Having Jurisdiction, whether or not the requirements are specifically indicated on the submitted construction documents.

The CSFD has reviewed the submittal in accordance with the adopted fire code requirements, CSFD local amendments, City Code Standards, and applicable NFPA Standards. All plan review comments are subject to final on-site field inspections, and testing by the CSFD. Review and approval by the CSFD shall not relieve the applicant of the responsibility of compliance with the International Fire Code.

FYI (STANDARD COMMENT) JCT REVIEWER CONTACT:

If you have any specific questions or concerns about these comments, please feel free to contact me at:

JAMES TRIMBLE  
Senior Fire Inspector, CSFD  
2880 International Circle, Suite 200-7  
Colorado Springs, CO 80910  
(T) 719-385-2232  
JAMES.TRIMBLE@coloradosprings.gov



**COLORADO SPRINGS FIRE PREVENTION  
PLAN REVIEW REPORT**

May 22, 2022

**Tax Id:** 7403204014

**DSN:**

**Project Description:** PURVIS RESIDENCE - 400 DAHLIA ST - NEW WUI HOME HARDENED STRUCTURE REQUIRED

SYSTEMS: monitored fire alarm in lieu of fire flow - reference variance tab

CN:Code: IRC - 15 IFC - 15 PPRBC 17/Class: R3 / Const: 5B /Stories: 2 /Size: 4938 /OL: 1

FH:Required Flow: 2000gpm /# Hydrants 2 /On site flow: 1688 PER ACTUAL 8/24/22 see PR comment for update 10.20.22

DV: NONE

Additional Comments:

**Business Name:** PURVIS RESIDENCE

**Address:** 00400 DAHLIA ST #400,

**Plan Id:** 20221410-HS-1

**Plan Description:** NEW RES DEV/HILSID

**Plan Status:** Approved

**Contractor:** LGA STUDIOS

**Review Status:** MEETING

**Plan Reviewer:** Valdez, Philip Warren

**Review Date:** 9/21/2022

**Status**  
Meeting

**Comment**  
Walkthru 9.21.22

Met with Larry Gilland of LPA Architects to discuss options for getting this home approved thru Construction Services.

Discuss why the gross sf and what he had shown on plans, was different. Read thru guidance doc which explains this per IFC B104.1 & B104.2.

Discuss options for reducing fire flow requirements - Guidance doc at counter with him and Ref'd B105.1 and B105.2

Discussed that the report he had in hand was NOT a simultaneous flow - he is going to request this and see what options the home owner wants to go with.

COLORADO SPRINGS FIRE PREVENTION  
PLAN REVIEW REPORT

May 22, 202

**Tax Id:** 7403204014

**DSN:**

**Project Description:** PURVIS RESIDENCE - 400 DAHLIA ST - NEW WUI HOME HARDENED STRUCTURE REQUIRED

SYSTEMS: monitored fire alarm in lieu of fire flow - reference variance tab

CN:Code: IRC - 15 IFC - 15 PPRBC 17/Class: R3 / Const: 5B /Stories: 2 /Size: 4938 /OL: 1

FH:Required Flow: 2000gpm /# Hydrants 2 /On site flow: 1688 PER ACTUAL 8/24/22 see PR comment for update 10.20.22

DV: NONE

Additional Comments:

**Business Name:** PURVIS RESIDENCE

**Address:** 00400 DAHLIA ST #400,

**Plan Id:** 20221410-HS-1

**Plan Description:** NEW RES DEV/HILSID

**Plan Status:** Approved

**Contractor:** LGA STUDIOS

**Review Status:** E-MAIL

**Plan Reviewer:** Valdez, Philip Warren

**Review Date:** 10/20/2022

**Comment**

**Status**  
E-Mail

PV receive an email with new flow report (while out of office on sick leave) and has since logged this report into Sdrive folder which shows an updated Actual Simultaneous flow report for hydrant C-767C as 1563 gpm. Discussed this project with Dee. Reviewed previous emails with this contractor to get up to speed. Dee/Larry recent email conversation on this project.....see below.

From: Larry Gilland <larryg@LGAStudios.com>

Sent: Wednesday, October 19, 2022 4:55 PM

To: Withee, Dee E. <Dee.Withee@coloradosprings.gov>; Trevor Hamilton <thamilton@csu.org>; Cameron Watson <cjwatson@csu.org>; Scott Hente <scotthente75@gmail.com>; Valdez, Phil W <Phil.Valdez@coloradosprings.gov>

Cc: Randall Purvis <rbpurvis@gmail.com>; Robin Purvis <robinpurvis@gmail.com>; Dawn Streb <dawns@LGAStudios.com>

Subject: RE: 400 Dahlia St. Fire Flow Report

Thank you Dee - We have requested from CSU the information - and seem to be at a standstill with CSU. ( maybe the wrong form or wrong person# but Dawn is pretty thorough and I can trace down the paperwork if needed)

I have also discussed some other options with the GC and owner. But we did not want to go down that path, unless we have to.

From: Withee, Dee E. <Dee.Withee@coloradosprings.gov>

Sent: Wednesday, October 19, 2022 4:27 PM

To: Larry Gilland <larryg@LGAStudios.com>; Trevor Hamilton <thamilton@csu.org>; Cameron Watson <cjwatson@csu.org>; Scott Hente <scotthente75@gmail.com>; Valdez, Phil W <Phil.Valdez@coloradosprings.gov>

Cc: Randall Purvis <rbpurvis@gmail.com>; Robin Purvis <robinpurvis@gmail.com>; Dawn Streb <dawns@LGAStudios.com>

Subject: RE: 400 Dahlia St. Fire Flow Report

Hi Larry,

Upon receipt of your email, I did some digging and found the size of this home requires minimum of 2000 gpm. So far, the records I can find show at most an available flow of 1400 gpm, as reported on the actual flow test conducted on 8/24/22.

So it appears we are still short on needed fire flow based on what has been proposed for the building. Trevor, if we can get current information for hydrants 1297-C and 767-C, they may contribute to a potential solution. I know this area, and pressure zone, is troublesome with the flows for these bigger homes.

Let me know what you think.

Regards

Dee Withee, PE

From: Larry Gilland <larryg@LGASudios.com>

Sent: Wednesday, October 19, 2022 4:06 PM

To: Trevor Hamilton <thamilton@csu.org>; Cameron Watson <cjwatson@csu.org>; Scott Hente <scotthente75@gmail.com>; Valdez, Phil W <Phil.Valdez@coloradosprings.gov>

Cc: Randall Purvis <rbpurvis@gmail.com>; Robin Purvis <robinpurvis@gmail.com>; Dawn Streb <dawns@LGASudios.com>

Subject: RE: 400 Dahlia St. Fire Flow Report

Trevor

Dawn, from my office ( who is on vacation this week) did request actual flows - the Fire Dept continues to reject the plan for approval because they can not seem to agree on the fire flow rate.

We have a number of pieces of data with all various fire flows - but nothing is working for the fire department - which is why Dawn requested an actual test because Phil Valdez from fire requested it.

We know it is an older neighborhood but there are a number of hydrants here and houses much larger than what the client wants to build and we keep getting a run around between Fire and CSU.

This morning the email to Phil Valdez was kicked back as he was on vacation so its another time delay.

The client is a former City council person and an attorney and the Contractor ( actually his partner is the GC ) is also a former City Council person and Chairman of the Planning commission currently.

This is the last item to be signed off for approval and it is taking weeks - if not months.

Is there anything we need to do on our part to help this client out?

**COLORADO SPRINGS FIRE PREVENTION  
PLAN REVIEW REPORT**

May 22, 202

**Tax Id:** 7403204014

**DSN:**

**Project Description:** PURVIS RESIDENCE - 400 DAHLIA ST - NEW WUI HOME HARDENED STRUCTURE REQUIRED

SYSTEMS: monitored fire alarm in lieu of fire flow - reference variance tab

CN:Code: IRC - 15 IFC - 15 PPRBC 17/Class: R3 / Const: 5B /Stories: 2 /Size: 4938 /OL: 1

FH:Required Flow: 2000gpm /# Hydrants 2 /On site flow: 1688 PER ACTUAL 8/24/22 see PR comment for update 10.20.22

DV: NONE

Additional Comments:

**Business Name:** PURVIS RESIDENCE

**Address:** 00400 DAHLIA ST #400,

**Plan Id:** 20221410-HS-1

**Plan Description:** NEW RES DEV/HILSID

**Plan Status:** Approved

**Contractor:** LGA STUDIOS

**Review Status:** E-MAIL

**Plan Reviewer:** Withee, Doreen E

**Review Date:** 10/20/2022

**Comment**

Attention

E-Mail

simultaneous report dated 10/4 and received by me 10/20/22 is inadequate due to a flow below 750 gpm in violation of 2015IFC B105.4.

From: Withee, Dee E.

Sent: Thursday, October 20, 2022 7:29 AM

To: Larry Gilland <larryg@LGASTudios.com>

Subject: RE: 400 Dahlia St. Fire Flow Report

Understood - if there is anything I can assist with, let me know and I will do what I can.

Regards

Dee Withee, PE

From: Larry Gilland <larryg@LGASTudios.com>

Sent: Wednesday, October 19, 2022 4:55 PM

To: Withee, Dee E. <Dee.Withee@coloradosprings.gov>; Trevor Hamilton <thamilton@csu.org>; Cameron Watson <cjwatson@csu.org>; Scott Hente

<scotthente75@gmail.com>; Valdez, Phil W <Phil.Valdez@coloradosprings.gov>

Cc: Randall Purvis <rwbpurvis@gmail.com>; Robin Purvis <robinpurvis@gmail.com>; Dawn Streb <dawns@LGASTudios.com>

Subject: RE: 400 Dahlia St. Fire Flow Report

CAUTION! - External Email. Malware is most commonly spread through unknown email attachments and links. DO NOT open attachments or click links from unknown senders or unexpected email!

Thank you Dee - We have requested from CSU the information - and seem to be at a standstill with CSU. ( maybe the wrong form or wrong person# but Dawn is pretty thorough and I can trace down the paperwork if needed)

I have also discussed some other options with the GC and owner #. But we did not want to go down that path, unless we have to.

From: Withee, Dee E. <Dee.Withee@coloradosprings.gov>  
Sent: Wednesday, October 19, 2022 4:27 PM  
To: Larry Gilliland <larry@LGASTudios.com>; Trevor Hamilton <thamilton@csu.org>; Cameron Watson <cjwatson@csu.org>; Scott Hente <scotthente75@gmail.com>; Valdez, Phil W <Phil.Valdez@coloradosprings.gov>  
Cc: Randall Purvis <rwbpurvis@gmail.com>; Robin Purvis <robinpurvis@gmail.com>; Dawn Streb <dawns@LGASTudios.com>  
Subject: RE: 400 Dahlia St. Fire Flow Report

Hi Larry,

Upon receipt of your email, I did some digging and found the size of this home requires minimum of 2000 gpm. So far, the records I can find show at most an available flow of 1400 gpm, as reported on the actual flow test conducted on 8/24/22.

So it appears we are still short on needed fire flow based on what has been proposed for the building.

Trevor, If we can get current information for hydrants 1297-C and 767-C, they may contribute to a potential solution. I know this area, and pressure zone, is troublesome with the flows for these bigger homes.

Let me know what you think.

Regards

Dee Withee, PE

CONTINUED...

E-Mail

From: Larry Gilliland <larry@LGASTudios.com>  
Sent: Wednesday, October 19, 2022 4:06 PM  
To: Trevor Hamilton <thamilton@csu.org>; Cameron Watson <cjwatson@csu.org>; Scott Hente <scotthente75@gmail.com>; Valdez, Phil W <Phil.Valdez@coloradosprings.gov>  
Cc: Randall Purvis <rwbpurvis@gmail.com>; Robin Purvis <robinpurvis@gmail.com>; Dawn Streb <dawns@LGASTudios.com>  
Subject: RE: 400 Dahlia St. Fire Flow Report

Trevor

Dawn, from my office ( who is on vacation this week) did request actual flows - the Fire Dept continues to reject the plan for approval because they can not seem to agree on the fire flow rate.

We have a number of pieces of data with all various fire flows - but nothing is working for the fire department - which is why Dawn requested an actual test because Phil Valdez from fire requested it.

We know it is an older neighborhood but there are a number of hydrants here and houses much larger than what the client wants to build and we keep getting a run around between Fire and CSU.

This morning the email to Phil Valdez was kicked back as he was on vacation so its another time delay.

The client is a former City council person and an attorney and the Contractor ( actually his partner is the GC ) is also a former City Council person and Chairman of the Planning commission currently.

This is the last item to be signed off for approval and it is taking weeks - if not months.

Is there anything we need to do on our part to help this client out?

From: Trevor Hamilton <thamilton@csu.org>  
Sent: Wednesday, October 19, 2022 2:25 PM  
To: Cameron Watson <cjwatson@csu.org>; Scott Hente <scorthe75@gmail.com>  
Cc: Randall Purvis <rbpurvis@gmail.com>; Robin Purvis <robinpurvis@gmail.com>; Larry Gilland <larryg@LGASudios.com>  
Subject: RE: 400 Dahlia St. Fire Flow Report

Good Afternoon All,

I do show a record of a Fire Flow request that was executed 8/24/22. Please see the attached file that Cameron include for that flow report.

As far as the Fire Flow request from September (1297-C) I do not show any record of this but that doesn't mean it didn't happen nor wasn't submitted. I will investigate this further and get back with you. If it was requested for this address it may not have been done because it is not an accurate representation of the flow needed for this structure, so the system may have reverted back to the flow requested on 8/24/22.

There is an actual formula that is calculated based off static pressures as well as the flowing pressure readings. There is a device called a "pitot" tube that provides the flowing pressure when the hydrant is full open. The number that you are reading in the report is the calculated flow in GPM @ 20psi per AWWA and CDPHE standards for minimum pressure in a water system. This calculation comes from a combination of the actual (pitot) flow on one hydrant and the residual pressure taken with a gauge on the same water main at a different hydrant. This is a method put together by the National Fire Protection Association, and what we use for all Fire Flow Tests performed throughout our system.

Please feel free to reach out to me with any questions or if further explanation is needed. My cell is the easiest way to reach me.

Thank you,

Trevor Hamilton | Water Distribution Operations Supervisor (Interim)  
Water System Operations

Office: 719.668.4680  
Mobile: 719.332.1795  
thamilton@csu.org | www.csu.org

**COLORADO SPRINGS FIRE PREVENTION  
PLAN REVIEW REPORT**

May 22, 202

**Tax Id:** 7403204014

**DSN:**

**Project Description:** PURVIS RESIDENCE - 400 DAHLIA ST - NEW WUI HOME HARDENED STRUCTURE REQUIRED

SYSTEMS: monitored fire alarm in lieu of fire flow - reference variance tab

CN:Code: IRC - 15 IFC - 15 PPRBC 17 /Class: R3 / Const: 5B /Stories: 2 /Size: 4938 /OL: 1

FH:Required Flow: 2000gpm # Hydrants 2 /On site flow: 1688 PER ACTUAL 8/24/22 see PR comment for update 10.20.22

DV: NONE

Additional Comments:

**Business Name:** PURVIS RESIDENCE

**Address:** 00400 DAHLIA ST #400,

**Plan Id:** 20221410-HS-1

**Plan Description:** NEW RES DEV/HILSID

**Plan Status:** Approved

**Contractor:** LGA STUDIOS

**Review Status:** MEETING

**Plan Reviewer:** Withee, Doreen E

**Review Date:** 11/14/2022

**Status**  
Meeting

**Comment**  
Meeting re lacking fire flow and how to get to approval

LGA Studios: Dawn Streb and Larry Gilland (Larry was remote)  
Signature Homes - Scott Hente  
Homeowner - Randy and Robin Purvis (Robin was remote)  
CSFD: Dee Withee, DFM Valdez

Due to lack of adequate fire flow, 1688 actual flow test where 2000 gpm is needed, fire sprinklers were recommended, but are not desirable to homeowners for:  
They go off  
Cause damage  
Concern with redesign of trusses

I provided the failure rate of fire sprinklers which is 1:16 million - they can fail but it is extremely rare.  
They cause less damage than a fire hose  
Generally residential systems do not require redesign due to materials used

However, due to email string shared by Dawn, a home near this one ran into the same issue. Upon researching that address, another home was referenced - both were allowed monitoring fire alarm in lieu of fire flow.

A monitored fire alarm allows for early notification of emergency forces. Larry Gilland was in agreement and thought this was a very reasonable and agreeable solution. We discussed what goes into them, has to be a listed system, with panel, monitoring, detection and notification installed by licensed contractors. Plans would be reviewed and approved by CSFD and a permit issued for the fire alarm system.

Home plans need only have a note added that a monitored fire alarm would be installed for us to approve house plans for permit.

All parties were agreeable.





**COLORADO SPRINGS FIRE PREVENTION  
PLAN REVIEW REPORT**

May 22, 202

**Tax Id:** 7403204014

**DSN:**

**Project Description:** PURVIS RESIDENCE - 400 DAHLIA ST - NEW WUI HOME HARDENED STRUCTURE REQUIRED

SYSTEMS: monitored fire alarm in lieu of fire flow - reference variance tab

CN:Code: IRC - 15 IFC - 15 PPRBC 17/Class: R3 /Const: 5B /Stories: 2 /Size: 4938 /OL: 1

FH:Required Flow: 2000gpm /# Hydrants 2 /On site flow: 1688 PER ACTUAL 8/24/22 see PR comment for update 10.20.22

DV: NONE

Additional Comments:

**Business Name:** PURVIS RESIDENCE

**Address:** 00400 DAHLIA ST #400,

**Plan Id:** 20221410-HS-1

**Plan Description:** NEW RES DEV/HILSID

**Plan Status:** Approved

**Contractor:** LGA STUDIOS

**Review Status:** APPROVED

**Plan Reviewer:** Withee, Doreen E

**Review Date:** 11/22/2022

**Status**  
FYI

**Comment**  
\*\*\*\*\*(STANDARD COMMENT) This project is: PURVIS RESIDENCE - 400 DAHLIA ST - NEW WUI HOME

This plan review is based on the requirements found within the adopted Editions of the International Building Code, International Fire Code and the related Standards.

FYI  
\*\*\*\*\*(STANDARD COMMENT) RED-LINED COMMENTS

The following RED-LINED items are to be corrected prior to final inspection:

1. Existing vegetation shown on site plan - need fuels management assessment on what may stay and must be removed as there are unidentified species of trees within safety zone.

Attention  
(STANDARD COMMENT) SCHEDULING INSPECTIONS

Homes within the Wildland Urban Interface require the following THREE inspections:

1. **PRIOR TO FRAMING:** Before you dig out and pour the foundation, you must schedule a fuels management inspection with the Wildfire Mitigation Section. you will need to have the home laid out in the intended location for an appropriate inspection to be conducted. Please call 719-385-7342 to schedule this inspection
  2. **AT FRAMING:** you will need to schedule an inspection to check any attic/roof/leave vent protection. Schedule this inspection with Construction services at the number indicated below.
  3. **FINAL:** schedule your final inspection with Construction Services at the number indicated below.
- Please call 719-385-5982 Extension 2 to schedule construction related inspection activities.

Due to the dynamic nature of inspectors schedules, PLEASE call your inspection requests in with ample time to allow scheduling. When calling, please have your complete CSFD plan review number(s) ready for each inspection request. ( i.e. 2013-1234 - HS-1)

The CSFD Approved sets of plans are to be available for all inspections.

2015 IFC 3310 ACCESS FOR FIREFIGHTING

FYI

Approved vehicle access for firefighting shall be provided to all construction/demolition sites. Vehicle access shall be either temporary or permanent roads, capable of supporting vehicle loading under all weather conditions. Vehicle access shall be maintained until permanent fire apparatus access roads are available.

(STANDARD COMMENT) INCREASED WILDFIRE RISK.

FYI

Residing in or near the wildland-urban interface areas involves increased fire risks that may not apply in urban or more urbanized types of developed communities.

\*\*\*\*(STANDARD COMMENT) ACCEPTED CONSTRUCTION MATERIALS/METHODS

FYI

Roofing materials is listed as being ---ASPHALT-- meeting the Class A requirements of Regional Building Code 303.4.61.1

Decking material is listed as being --COMPOSITE--- meeting the requirements for ignition resistant construction. UNDERSIDE OF DECK IS LEFT OPEN TO STRUCTURE AS PERMITTED.

Exterior cladding, is listed as being --FIBER CEMENT--- meeting the requirements for ignition resistant construction.

Soffit/Eaves is listed as being ---FIBER CEMENT-- meeting the requirements for ignition resistant construction.

Exterior overhangs (canti-lever areas, covered porch/deck ceilings) are listed as being ---COMPOSITE T&G PER REVIEW FORM-- meeting the requirements for ignition resistant construction.

Existing vegetation shown on site plan - need fuels management assessment on what may stay and must be removed. Landscape plan not included.

(See also the Amended 2015 International Fire Code Appendix K Section K104 for hardened structure requirements.)

(STANDARD COMMENT) HILLSIDE ORDINANCE

FYI

This lot/development is subject to the requirements of section of 20-4-10 5 CE (2) (Ordinances 93-48 and 93-49) of the City Code establishing minimum safety criteria for residential construction in the City's Hillside Areas. Ensure all landscaping complies with the wildfire interface specifications as required by the fire department and zoning/planning departments.

(STANDARD COMMENT) SOC RESPONSE TIMES

FYI

Fire service response times to this area do not fall within the CSFD interim Standard of Response Coverage. The CSFD is unable to provide the following level of service:  
- 90% of all emergencies reached within 8 minutes (first due company)

- 90% of structure fires requiring a full effective fire-fighting complement (2 engine companies, 1 ladder/truck company) within 12 minutes.

2015 IFC K102 FUELS MANAGEMENT

Attention

SAFETY ZONE:

Brush patches or clusters may be left in the safety zone, but shall be separated by clear areas of 10-feet or more of noncombustible materials or grass mowed to not more than 4-inches in height.

CLEARANCE TO MAIN STRUCTURE:

No hazardous brush, trees or shrubs shall be allowed within 15-feet of the main structure or significant accessory structure such as sheds, decks and pergolas. The trunks of deciduous trees may be allowed to be planted as close as 10-feet from structures where approved by the Fire Code Official.

Small brush patches not exceeding 100-square feet in size or trees no larger than 15 linear feet in any direction may be allowed to encroach into this zone.

PRUNING OF LIMBS:

Large trees shall not be allowed to have limbs overlap smaller trees or brush, and shall be pruned of dead limbs to a height up to 10-feet while maintaining a minimum 70% of the tree's crown. Certain tree clusters may be permitted if sufficient clear area is provided and approved by the Fire Code Official.

**CLEARANCE OF TREE BRANCHES TO STRUCTURES OR APPURTENANCES:**

Character tree branches shall not extend over or under the roof or eaves, and the canopy or drip-line shall not be within 15-feet of a deck or similar combustible projection, wood burning appliance or chimney unless approved by the Fire Code Official.

For additional information concerning this issue - contact our Wildfire Mitigation Administrator at 385-7368 or <https://coloradosprings.gov/fire-department/page/wildfire-mitigation-0?mid=9906>

**(STANDARD COMMENT) CLASS A ROOFING**

FYI

A Class A roof covering (excluding solid wood roofing products) shall be installed on all Residential Occupancies and a minimum Class B roof covering shall be installed on all remaining occupancies (Not to replace Class A where already required by Table 15-A) at the time an application is made for a roofing or re-roofing building permit within the limits of the City of Colorado Springs, Colorado.

**2015 IFC K104 IGNITION-RESISTANT CONSTRUCTION REQUIREMENTS**

Attention

1. Exterior cladding, eaves and soffits shall be constructed of ignition resistant materials, including but not limited to: fiber-cement board, stucco, masonry/brick, manufactured stone and similar materials. Natural wood/cedar siding, hardboard, vinyl and similar combustibles are not permitted. Natural wood or plastic products used for fascia, trim board materials and trim accents are allowed when painted or as approved.
2. For any portion of the attached structure with projections or overhangs, the area below shall have all horizontal under-floor areas enclosed with ignition resistive materials such as allowed in item 1 above.
3. Exterior doors shall be noncombustible or solid core not less than 1 3/4-inches thick. Windows within doors and glazed doors shall be tempered safety glass or multi-layered glazed panels.
4. Exterior windows shall be a minimum double pane. Tempered panes are preferable but not required.
5. All attic vents shall be screen with wire mesh or hardware cloth having openings no larger than 1/8-inch. Soffit vents are permitted, gable vents may be allowed as approved by the Fire Code Official.
6. Gutters and downspouts of non-combustible construction shall be installed such that the leading edge of the roof is finished with a metal drip edge so that no wood sheathing is exposed. Drip edge shall extend into the gutter. Vinyl gutters may be allowed but must have a noncombustible landing area below the roof line, a minimum of 5-feet from the side of the structure/foundation. Gutter caps are strongly recommended to prevent accumulation of combustible debris in the gutters.
7. Decks and other habitable spaces shall be of ignition resistant or non-combustible decking materials, such as metal or composite materials. Wood is permitted for use for large structural components and railings (ie vertical members).
8. The base of exterior walls, posts or columns shall be protected on the bottom side with provision such as fire resistant foam or wire mesh having openings no larger than 1/8-inch.
9. Chimneys serving fireplaces, and other solid or liquid fueled heating appliances shall have an approved spark arrestor or cap.

**(STANDARD COMMENT) CONSTRUCTION PERMIT REVIEW REQUIREMENTS:**

Attention

Plans for any structure lying within the WUI Overlay area must be approved by the Colorado Springs Fire Department Construction Services prior to issuance of a building permit.

Final approval by CSFD on all permits issued by RBD is required prior to issuance of the Certificate of Occupancy.

**\*\*\*\*(STANDARD COMMENT) FIRE FLOW/HYDRANT REQUIREMENTS:**

FYI

On this site fire flows are --1688-- gpm, and the numbers of hydrant(s) are --one-- based on a ACTUAL Report.

**MONITORED FIRE ALARM SYSTEM REQUIRED IN LIEU OF FIRE FLOW**

**(STANDARD COMMENT) MONITORED FIRE ALARM REQUIRED**

Attention

A monitored fire alarm system is required in this home. However, a residential fire sprinkler system is an acceptable alternative or can be installed in addition to the fire alarm requirement.

**(STANDARD COMMENT) PERMITS**

FYI

Insure all applicable permits are obtained from the Regional Building Department and the Colorado Springs Fire Department for the work that is being done at this site.

FYI

(STANDARD COMMENT) REVIEWS: 2015 IFC 105.4.4

Colorado Springs Fire Department plan reviews are based upon information provided on the drawings and/or the attached reference material. Issues or features that are not presented within the construction documents are assumed to be complaint with applicable codes/standards. It is the responsibility of the building owner to ensure that minimum code requirements are met as established by the Authority Having Jurisdiction, whether or not the requirements are specifically indicated on the submitted construction documents.

The CSFD has reviewed the submittal in accordance with the adopted fire code requirements, CSFD local amendments, City Code Standards, and applicable NFPA Standards. All plan review comments are subject to final on-site field inspections, and testing by the CSFD. Review and approval by the CSFD shall not relieve the applicant of the responsibility of compliance with the International Fire Code.

FYI

(STANDARD COMMENT) DEW REVIEWER CONTACT:

If you have any specific questions or concerns about these comments, please feel free to contact me at:

Doreen "Dee" Withee, PE  
Fire Protection Engineer II, CSFD  
2880 International Circle, Suite 200-7  
Colorado Springs, CO 80910  
(T) 719-385-7361  
dee.withee@coloradosprings.gov

**COLORADO SPRINGS FIRE PREVENTION  
PLAN REVIEW REPORT**

May 22, 2022

**Tax Id:** 7403204014

**DSN:**

**Project Description:** PURVIS RESIDENCE - 400 DAHLIA ST - NEW WUI HOME HARDENED STRUCTURE REQUIRED

SYSTEMS: monitored fire alarm in lieu of fire flow - reference variance tab

**CN:Code:** IRC - 15 IFC - 15 PPRBC 17 /Class: R3 /Const: 5B /Stories: 2 /Size: 4938 /OL: 1

**FH:Required Flow:** 2000gpm /# Hydrants 2 /On site flow: 1688 PER ACTUAL 8/24/22 see PR comment for update 10.20.22

**DV:** NONE

**Additional Comments:**

**Business Name:** PURVIS RESIDENCE

**Address:** 00400 DAHLIA ST #400,

**Plan Id:** 20221410-HS-1

**Plan Description:** NEW RES DEV/HILSID

**Plan Status:** Approved

**Contractor:** LGA STUDIOS

**Review Status:** ATTENTION

**Plan Reviewer:** Taylor II, Wyman L

**Review Date:** 2/7/2023

**Status**  
E-Mail

**Comment**

From: Whitworth, Ashley <Ashley.Whitworth@coloradosprings.gov>  
Sent: Tuesday, February 7, 2023 4:19 PM  
To: scothente75@gmail.com  
Cc: Horton, Bailey E <Bailey.Horton@coloradosprings.gov>; Gregory, Andi <Andi.Gregory@coloradosprings.gov>; Taylor, Wyman L. <Wyman.Taylor@coloradosprings.gov>  
Subject: 400 Dahlia Street  
Importance: High

Scott,

It was a pleasure meeting with you today at 400 Dahlia Street. Per our onsite visit all vegetation on the property will be removed besides the juniper that is by the powerline because it is farther than 15 feet away from the structure. Please pass along to the homeowners that they do have to abide by the vegetation management requirements when they are landscaping their property (no conifers/junipers/evergreens within 15 feet of the structure). This information can be found in our Ignition Resistant Design Manual: [https://www.coswildfiready.org/uploads/b/2721a780-1003-11ec-bf67-0310173bc1c8/2021%20WUJ%20Wildfire%20Mitigation%20Design%20Manual\\_NzE4MD.pdf](https://www.coswildfiready.org/uploads/b/2721a780-1003-11ec-bf67-0310173bc1c8/2021%20WUJ%20Wildfire%20Mitigation%20Design%20Manual_NzE4MD.pdf).

Please let me know if you have any further questions or if there is anything additional I can assist with.

Thank you,

Ashley Whitworth  
Wildfire Mitigation Program Administrator  
Colorado Springs Fire Department  
375 Printers Parkway  
Colorado Springs, CO 80910  
Office: 719.385.7342

Fax: 719.385.7334

Ashley.Whitworth@coloradosprings.gov

"Sharing the Responsibility!"



2 Pages with Map

### Fire Flow Calculations

Date Request Received:	8/12/2022	Date of Calculation:	8/16/2022
Project Name:	Purvis Residence		
Project Location:	400 Dahlia Street		
Project No:	NA	RMS No:	NA
		UDCF No:	NA
Project Contact:	Elena Hepworth	Company:	LGA Studios
Phone:	719-635-0880	Email:	<a href="mailto:ElenaH@LGASudios.com">ElenaH@LGASudios.com</a>
Pressure Zone:	Columbia	Overflow Elevation:	6540
Requested Fire Flow (gpm):	NA	Map Sheet:	C-31

Hydrant	Elevation	Theoretical Flow @ 20 psi (gpm)	Static Pressure @ Max Day Demand (psi)	Max Static Pressure @ Bury Depth (psi)*
761-C	6207	800	144	148
768-C	6237	800	131	135

**\*Bury depth is assumed to be 9 feet below the hydrant flange elevation**

**Per Colorado Springs Fire Department, the calculations provided are acceptable up to 1 year from above date.**

**Comments:**

Flows were less than the minimum allowable flow of 1500 gpm. Colorado Springs Fire Department will determine further actions upon review.

**\*\* Colorado Springs Rules and Regulations require that second and subsequent fire flow requests for the same address within a 12-month period are supplied with a minimum \$50.00 fee for existing infrastructure and \$200.00 fee for multiple runs for proposed infrastructure.**

Colorado Springs Utilities  
Water Planning  
[waterplanning@csu.org](mailto:waterplanning@csu.org)

Distribution: Jerry Edwards - Water Planning and Design, Doreen Withee - Fire Prevention









# Colorado Springs Utilities

It's how we're all connected

Water Services Division  
Operations Department

## Fire Flow Test Report

<b>DATE:</b>	8/24/2022
<b>WORK ORDER #:</b>	3913729
<b>REQUESTER NAME:</b>	Elena Hepworth LGA Studios <small>Requester #1</small>
<b>FAX #/Email:</b>	elenah@LGASudios.com <small>Requester #2</small>
<b>PHONE #:</b>	719-635-0880 ext 104
<b>LOCATION:</b>	400 Dahlia St
<b>FLOWING HYDRANT #:</b>	768-C
<b>NOZZLE SIZE:</b>	2.5"
<b>WATER MAIN SIZE:</b>	
<b>FLOW HYDRANT STATIC PSI:</b>	125
<b>PITOT (PSI):</b>	45
<b>FLOW (GPM):</b>	1126
<b>RESIDUAL HYDRANT #:</b>	761-C
<b>RESIDUAL HYD STATIC PSI:</b>	138
<b>WATER MAIN SIZE:</b>	
<b>RESIDUAL PRESSURE (PSI):</b>	58
<b>FIRE DEPT REVIEW PLAN #:</b>	
<b>FIRE INSPECTOR:</b>	
<b>CSFD REQUIRED FLOW (GPM):</b>	
<b>CALCULATED FLOW @ 20 PSI:</b>	1388
<b>RESIDUAL (GPM):</b>	Contact Fire Inspector to obtain Official Final Fire Flow Calculations.

**COMMENTS:**

*Oct 4, 22 1563 gpm*

*Another of 160 gpm*

Please call with questions or comments.

Thank You

Sean Higbee, Water Distribution Supervisor

Distribution: Fire Prevention (CSFD 385-7334)

404 W. FONTANERO ST. BUILDING 457

P.O. BOX 1103, MAIL CODE 1210

COLORADO SPRINGS, CO 80947-1210

PHONE 719-668-4595, FAX 719-668-2890, shigbee@csu.org, http://www.csu.org



**Colorado Springs Utilities**  
*It's how we're all connected*

Water Services Division  
 Operations Department

## SIMULTANEOUS FIRE FLOW TEST REPORT

<b>FLOW TEST DATE:</b> 10/4/2022	<b>WORK ORDER #:</b> 3925202
<b>REQUESTER NAME:</b> Scott Hente (Robert Scott Construction)	
<b>FAX NUMBER/EMAIL:</b> <a href="mailto:scotthente75@gmail.com">scotthente75@gmail.com</a>	<b>PHONE NUMBER:</b> 719-499-6752
<b>LOCATION:</b> 400 Dahlia Street, 80904	

### FLOW HYDRANTS

<b>FLOW HYDRANT #1:</b>	761-C	<b>STATIC PSI:</b>	134	<b>FLOW AT RESIDUAL PSI:</b>	978
<b>MAIN SIZE:</b>	6"	<b>PITOT PSI:</b>	34	<b>CALCULATED FLOW @ 20 PSI:</b>	905
<b>FLOW HYDRANT #2:</b>	768-C	<b>STATIC PSI:</b>	125	<b>FLOW AT RESIDUAL PSI:</b>	712
<b>MAIN SIZE:</b>	6"	<b>PITOT PSI:</b>	18	<b>CALCULATED FLOW @ 20 PSI:</b>	658
<b>FLOW HYDRANT #3:</b>		<b>STATIC PSI:</b>		<b>FLOW AT RESIDUAL PSI:</b>	0
<b>MAIN SIZE:</b>		<b>PITOT PSI:</b>		<b>CALCULATED FLOW @ 20 PSI:</b>	0
<b>FLOW HYDRANT #4:</b>		<b>STATIC PSI:</b>		<b>FLOW AT RESIDUAL PSI:</b>	0
<b>MAIN SIZE:</b>		<b>PITOT PSI:</b>		<b>CALCULATED FLOW @ 20 PSI:</b>	0

\*Hydrants listed above were flowed at the same time.

### RESIDUAL HYDRANT

<b>RESIDUAL HYDRANT #:</b>	767-C	<b>STATIC PSI:</b>	110	<b>MAIN SIZE:</b>	6"
		<b>RESIDUAL PSI:</b>	6		

<b>CALCULATED FIRE FLOW @ 20 PSI RESIDUAL:</b>	1563
--	------

### COMMENTS:

---



---



---



---



---



---



---

Please call with questions or comments.  
 Thank You

Sean Higbe, Water Distribution Operations Supervisor

404 W. Fontanero St. Building 456  
 P.O. Box 1103, Mail Code 1210  
 Colorado Springs, CO. 80947-1210  
 Phone: 719-668-4595 | [shigbee@csu.org](mailto:shigbee@csu.org) | <http://www.csu.org>

# APPENDIX B

## FIRE-FLOW REQUIREMENTS FOR BUILDINGS

*The provisions contained in this appendix are not mandatory unless specifically referenced in the adopting ordinance.*

### SECTION B101 GENERAL

#### B101.1 Scope.

The procedure for determining fire-flow requirements for buildings or portions of buildings hereafter constructed shall be in accordance with this appendix. This appendix does not apply to structures other than buildings.

### SECTION B102 DEFINITIONS

#### B102.1 Definitions.

For the purpose of this appendix, certain terms are defined as follows:

**FIRE-FLOW.** The flow rate of a water supply, measured at 20 pounds per square inch (psi) (138 kPa) residual pressure, that is available for fire fighting.

**FIRE-FLOW CALCULATION AREA.** The floor area, in square feet (m<sup>2</sup>), used to determine the required fire flow.

### SECTION B103 MODIFICATIONS

#### B103.1 Decreases.

The fire chief is authorized to reduce the fire-flow requirements for isolated buildings or a group of buildings in rural areas or small communities where the development of full fire-flow requirements is impractical.

#### B103.2 Increases.

The fire chief is authorized to increase the fire-flow requirements where conditions indicate an unusual susceptibility to group fires or conflagrations. An increase shall not be more than twice that required for the building under consideration.

#### B103.3 Areas without water supply systems.

For information regarding water supplies for fire-fighting purposes in rural and suburban areas in which adequate and reliable water supply systems do not exist, the *fire code official* is authorized to utilize NFPA 1142 or the *International Wildland-Urban Interface Code*.

### SECTION B104 FIRE-FLOW CALCULATION AREA

#### B104.1 General.

The fire-flow calculation area shall be the total floor area of all floor levels within the *exterior walls*, and under the horizontal projections of the roof of a building, except as modified in Section B104.3.

#### B104.2 Area separation.

Portions of buildings which are separated by *fire walls* without openings, constructed in accordance with the *International Building Code*, are allowed to be considered as separate fire-flow calculation areas.

#### B104.3 Type IA and Type IB construction.

The fire-flow calculation area of buildings constructed of Type IA and Type IB construction shall be the area of the three largest successive floors.

**Exception:** Fire-flow calculation area for open parking garages shall be determined by the area of the largest floor.

### SECTION B105 FIRE-FLOW REQUIREMENTS FOR BUILDINGS

#### B105.1 One- and two-family dwellings, Group R-3 and R-4 buildings and townhouses.

The minimum fire-flow and flow duration requirements for one- and two-family *dwellings*, Group R-3 and R-4 buildings and townhouses shall be as specified in Tables B105.1(1) and B105.1(2).

**TABLE B105.1(1)**  
**REQUIRED FIRE-FLOW FOR ONE- AND TWO-FAMILY DWELLINGS, GROUP R-3 AND R-4**  
**BUILDINGS AND TOWNHOUSES**

FIRE-FLOW CALCULATION AREA (square feet)	AUTOMATIC SPRINKLER SYSTEM (Design Standard)	MINIMUM FIRE- FLOW (gallons per minute)	FLOW DURATION (hours)
0-3,600	No automatic sprinkler system	<i>1,500</i>	1
3,601 and greater	No automatic sprinkler system	Value in Table B105.1(2)	Duration in Table B105.1(2) at the required fire-flow rate
0-3,600	<i>Section 903.3.1.3 of the International Fire Code</i>	<i>1,500</i>	$\frac{1}{2}$
3,601 and greater	<i>Section 903.3.1.3 of the International Fire Code</i>	$\frac{1}{2}$ value in Table B105.1(2)	1

For SI: 1 square foot = 0.0929 m<sup>2</sup>, 1 gallon per minute = 3.785 L/m.

*a. Reduced fire-flow shall not be less than 1,500 gallons per minute.*

**TABLE B105.1(2)  
REFERENCE TABLE FOR TABLES B105.1(1) AND B105.2**

FIRE-FLOW CALCULATION AREA (square feet)					FIRE-FLOW (gallons per minute) <sup>b</sup>	FLOW DURATION (hours)
Type IA and IB <sup>a</sup>	Type IIA and IIIA <sup>a</sup>	Type IV and V-A <sup>a</sup>	Type IIB and IIIB <sup>a</sup>	Type V-B <sup>a</sup>		
0-22,700	0-12,700	0-8,200	0-5,900	0-3,600	1,500	2
22,701-30,200	12,701-17,000	8,201-10,900	5,901-7,900	3,601-4,800	1,750	
30,201-38,700	17,001-21,800	10,901-12,900	7,901-9,800	4,801-6,200	2,000	
38,701-48,300	21,801-24,200	12,901-17,400	9,801-12,600	6,201-7,700	2,250	
48,301-59,000	24,201-33,200	17,401-21,300	12,601-15,400	7,701-9,400	2,500	
59,001-70,900	33,201-39,700	21,301-25,500	15,401-18,400	9,401-11,300	2,750	
70,901-83,700	39,701-47,100	25,501-30,100	18,401-21,800	11,301-13,400	3,000	3
83,701-97,700	47,101-54,900	30,101-35,200	21,801-25,900	13,401-15,600	3,250	
97,701-112,700	54,901-63,400	35,201-40,600	25,901-29,300	15,601-18,000	3,500	
112,701-128,700	63,401-72,400	40,601-46,400	29,301-33,500	18,001-20,600	3,750	
128,701-145,900	72,401-82,100	46,401-52,500	33,501-37,900	20,601-23,300	4,000	4
145,901-164,200	82,101-92,400	52,501-59,100	37,901-42,700	23,301-26,300	4,250	
164,201-183,400	92,401-103,100	59,101-66,000	42,701-47,700	26,301-29,300	4,500	
183,401-203,700	103,101-114,600	66,001-73,300	47,701-53,000	29,301-32,600	4,750	
203,701-225,200	114,601-126,700	73,301-81,100	53,001-58,600	32,601-36,000	5,000	
225,201-247,700	126,701-139,400	81,101-89,200	58,601-65,400	36,001-39,600	5,250	
247,701-271,200	139,401-152,600	89,201-97,700	65,401-70,600	39,601-43,400	5,500	
271,201-295,900	152,601-166,500	97,701-106,500	70,601-77,000	43,401-47,400	5,750	
295,901-Greater	166,501-Greater	106,501-115,800	77,001-83,700	47,401-51,500	6,000	
—	—	115,801-125,500	83,701-90,600	51,501-55,700	6,250	
—	—	125,501-135,500	90,601-97,900	55,701-60,200	6,500	
—	—	135,501-145,800	97,901-106,800	60,201-64,800	6,750	
—	—	145,801-156,700	106,801-113,200	64,801-69,600	7,000	

*(continued)*

**TABLE B105.1(2) -- continued  
REFERENCE TABLE FOR TABLES B105.1(1) AND B105.2**

FIRE-FLOW CALCULATION AREA (square feet)					FIRE-FLOW (gallons per minute) <sup>b</sup>	FLOW DURATION (hours)
Type IA and IB <sup>a</sup>	Type IIA and IIIA <sup>a</sup>	Type IV and V-A <sup>a</sup>	Type IIB and IIIB <sup>a</sup>	Type V-B <sup>a</sup>		
—	—	156,701- 167,900	113,201- 121,300	69,601- 74,600	7,250	4
—	—	167,901- 179,400	121,301- 129,600	74,601- 79,800	7,500	
—	—	179,401- 191,400	129,601- 138,300	79,801- 85,100	7,750	
—	—	191,401- Greater	138,301- Greater	85,101- Greater	8,000	

For SI: 1 square foot = 0.0929 m<sup>2</sup>, 1 gallon per minute = 3.785 L/m, 1 pound per square inch = 6.895 kPa.

- a. Types of construction are based on the *International Building Code*.
- b. Measured at 20 psi residual pressure.

**TABLE B105.2  
REQUIRED FIRE-FLOW FOR BUILDINGS OTHER THAN ONE- AND  
TWO-FAMILY DWELLINGS, GROUP R-3 AND R-4 BUILDINGS AND TOWNHOUSES**

AUTOMATIC SPRINKLER SYSTEM (Design Standard)	MINIMUM FIRE-FLOW (gallons per minute)	FLOW DURATION (hours)
No automatic sprinkler system	Value in Table B105.1(2)	Duration in Table B105.1(2)
Section 903.3.1.1 of the <i>International Fire Code</i>	<i>Down to 50% of the value in Table B105.1(2)<sup>a</sup></i>	Duration in Table B105.1(2) at the reduced flow rate
Section 903.3.1.2 of the <i>International Fire Code</i>	<i>Down to 50% of the value in Table B105.1(2)<sup>b</sup></i>	Duration in Table B105.1(2) at the reduced flow rate

For SI: 1 gallon per minute = 3.785 L/m.

- a. The reduced fire-flow shall be not less than 1,000 gallons per minute.

**B105.2 Buildings other than one- and two-family dwellings, Group R-3 and R-4 buildings and townhouses.**

The minimum fire-flow and flow duration for buildings other than one- and two-family dwellings, Group R-3 and R-4 buildings and townhouses shall be as specified in Tables B105.2 and B105.1(2).

**B105.3 Water supply for buildings equipped with an automatic sprinkler system.**

For buildings equipped with an approved automatic sprinkler system, the water supply shall be capable of providing the greater of:

1. The automatic sprinkler system demand, including hose stream allowance.
2. The required fire-flow.

***B105.4. Simultaneous flows.***

*Any hydrant must produce a minimum flow of 1,500 gallons per minute at 20 psi of residual pressure when flowing individually, or a minimum of 750 gallons per minute at 20 psi of residual pressure when flowing simultaneously to be considered by Table C102.1 or by Table C102.1's footnotes as one of the minimum hydrants required to protect any structure, hazard or potential hazard.*

**SECTION B106  
REFERENCED STANDARDS**

ICC	IBC—15	International Building Code	B104.2, Tables
ICC	IFC—15	International Fire Code	B105.1.(1) and B105.2
ICC	IWUIC—15	International Wildland-Urban Interface Code	B103.3
ICC	IRC—15	International Residential Code	Table B105.1.(1)
NFPA	1142—12	Standard on Water Supplies for Suburban and Rural Fire Fighting	B103.3

## Code Path for Compliance on Residential Occupancies

Applicable Code: 2015 Colorado Springs Fire Prevention Code (non-applicable sections omitted)

**101.3 Intent.** The purpose of this code is to establish the minimum requirements consistent with nationally recognized good practice for providing a reasonable level of life safety and property protection from the hazards of fire, explosion or dangerous conditions in new and existing buildings, structures and premises, and to provide a reasonable level of safety to fire fighters and emergency responders during emergency operations.

**102.1 Construction and design provisions.** The construction and design provisions of this code shall apply to:

1. Structures, facilities and conditions arising after the adoption of this code.
2. Existing structures, facilities and conditions not legally in existence at the time of adoption of this code.

**102.5 Application of residential code.** Where structures are designed and constructed in accordance with the *International Residential Code*, the provisions of this code shall apply as follows:

1. Construction and design provisions of this code pertaining to the exterior of the structure shall apply including, but not limited to, premises identification, fire apparatus access and water supplies. Where interior or exterior systems or devices are installed, construction permits required by Section 105.7 of this code shall apply.

**507.1 Required water supply.** An *approved* water supply capable of supplying the required fire flow for fire protection shall be provided to premises upon which facilities, buildings or portions of buildings are hereafter constructed or moved into or within the jurisdiction.

**507.3 Fire flow.** Fire flow requirements for buildings or portions of buildings and facilities shall be determined as *outlined in Appendix B of this code*.

**B101.1 Scope.** The procedure for determining fire-flow requirements for buildings or portions of buildings hereafter constructed shall be in accordance with this appendix. This appendix does not apply to structures other than buildings.

**B104.1 General.** The fire-flow calculation area shall be the total floor area of all floor levels within the *exterior walls*, and under the horizontal projections of the roof of a building, except as modified in Section B104.3.

**B105.1 One- and two-family dwellings, Group R-3 and R-4 buildings and townhouses.** The minimum fire-flow and flow duration requirements for one- and two-family *dwellings*, Group R-3 and R-4 buildings and townhouses shall be as specified in Tables B105.1(1) and B105.1(2).



**TABLE B105.1(1) REQUIRED FIRE-FLOW FOR ONE- AND TWO-FAMILY DWELLINGS, GROUP R-3 AND R-4 BUILDINGS AND TOWNHOUSES**

<b>FIRE-FLOW CALCULATION AREA (square feet)</b>	<b>AUTOMATIC SPRINKLER SYSTEM (Design Standard)</b>	<b>MINIMUM FIRE-FLOW (gallons per minute)</b>	<b>FLOW DURATION (hours)</b>
0-3,600	No automatic sprinkler system	1,500	1
3,601 and greater	No automatic sprinkler system	Value in Table B105.1(2)	Duration in Table B105.1(2) at the required fire-flow rate
0-3,600	<i>Section 903.3.1.3 of the International Fire Code</i>	1,500	½
3,601 and greater	<i>Section 903.3.1.3 of the International Fire Code</i>	½ value in Table B105.1(2)	1

For SI: 1 square foot = 0.0929 m<sup>2</sup>, 1 gallon per minute = 3.785 L/m.

*a. Reduced fire-flow shall not be less than 1,500 gallons per minute.*

# PURVIS RESIDENCE


APPROVED  
11/22/2023 9:04:30 AM  
Colorado Springs Fire Department



FIRE ALARM IS IN LIEU OF MEETING REQUIRED FIRE FLOW, CSPD

FIRE DEPARTMENT REQUIREMENTS  
THIS RESIDENCE TO HAVE AN INSTALLED MONITORED FIRE ALARM SYSTEM PER CODE REQUIREMENTS

## COMMON HATCHES




## SQUARE FOOTAGE

AREA SCHEDULE	Name	Area
RI LOWER LEVEL	1244 SF	
UNFINISHED LOWER	563 SF	
GARAGE AREA	475 SF	
SHOP AREA	241 SF	
FINISHED MAIN LEVEL	1812 SF	
COVERED DECK	251 SF	
COVERED PORCH	110 SF	
Grand total:	4887 SF	

## REVISIONS

## COMMON SYMBOLS



## COMMON ABBREVIATIONS

AFF	= ABOVE FINISH FLOOR
B.C.	= BOTTOM CHORD
BRW	= BEARING WALL
BTM	= BOTTOM
CL	= CENTERLINE
CL	= COLUMN
CAN	= CANTILEVER
CLG BRK	= CEILING BREAK
CLR	= CLEARANCE
CONC	= CONCRETE
CR	= CROPPED
DV	= DIRECT VENT
EA	= EACH
EE	= EACH END
ELC	= ELECTRICAL
FF	= FINISH FLOOR
FLR	= FLOOR
FND	= FOUNDATION
GLB	= GULLY
GYP	= GYPSUM
HDR	= HEADER
HB	= HOSE BIBB
HBN	= HANGING
HGT	= HEIGHT
ICC	= INTERNATIONAL CODE COUNCIL
INSUL	= INSULATION
JST	= JOIST
LVL	= LAMINATED VENEER LUMBER
MIN	= MINIMUM
MAX	= MAXIMUM
O.C.	= ON CENTER
O.C.	= ON CENTER
O.H.	= OVERHANG
P.T.	= PRESSURE TREATED
PSF	= POUNDS PER SQUARE FOOT
REQD	= REQUIRED
R.S.	= ROUGH SAW
R.S.	= ROUGH SAW
SFSOFT	= SQUARE FEET or SQUARE FOOT
T	= TO BE DETERMINED
TBD	= TO BE DETERMINED
TEMP	= TEMPERED
TOW	= TOP OF WALL
TYP	= TYPICAL
UNCL.	= UNLESS NOTED OTHERWISE
UNCL.	= UNLESS NOTED OTHERWISE
VTR	= VENT THROUGH ROOF
VP	= WEATHER PROTECTED

## LOADING

WIND LOAD:	130 MPH (ULTIMATE) EXPOSURE 'C'
ROOF LOADS:	30# PSF DEAD LOAD= LIVE LOAD= 15# PSF
FLOOR LOADS:	40# PSF DEAD LOAD= LIVE LOAD= 10# PSF
DECK LOADS:	40# PSF DEAD LOAD= LIVE LOAD= 66# PSF LEDGER= 66# PSF

## ASSEMBLY NOTES

ASSEMBLY NUMBER	PRODUCT SPECIFICATION REFERENCE
A	Roof: Class 'A' Fiberglass Reinforced Asphalt Shingles - less than 24"08 between Oct. - May on undecked and 7/16" sheathing over factory built trusses or rafters w/ specified insulation. Provide ice shield starting at the eave and continuing to a point 24" inside the exterior wall line. Refer to Specification Sections 061000, 061700, 073113, 072100, 072824
B	Fascia: Soffit: 2x10 Cement Board Fascia Board over 2x sub-lath. 6" gutter and down spouts w/ minimum 5" extensions @ grade. Cement Board Soffit on 2x ledgers with backer at buttions and 2x framing 24" O.C. Provide soffit vents as required by code which shall be covered with corrosion resistant metal mesh (1/8" inch or less in dimension). Refer to Specification Sections 061000 and 076500.
C	Exterior Wall: 2x6 wood studs 16" O.C., double top plates w/ 48" minimum tabs - Exterior solidly sheathed. Batt insulation, vapor barrier per 2015 IRC. Finish interior face w/ 1/2" gypsum board. Exterior face, 7/16" OSB sheathing. Continuous safety glass per manufacturer's stone or vapor retarder, as indicated. Provide insulation per IECC requirements. Refer to Specification Sections 042000, 061000, 061700, 072100, 072500, 074626, and 092513.
D	Exterior Wall (balloon frame): 2x6 wood studs per IRC, code to bottom chord of factory built trusses or rafters. Balance of material matching specified exterior wall note above. Provide insulation per attached IECC. Refer to Specification Sections 042000, 061000, 061700, 072100, 072500, 074626, and 092513.
E	Framed Floor System: 2x32 7/8x T&G sub-floor on 2" joist framing system with joist mfg's OSB rim joist. Refer to Floor Framing Plans. Refer to Specification Sections 061000, 061700 and 072100.
F	Exterior Deck System: Flat 2x6 ICC listed and approved composite lumber over joists. Refer to Floor Framing Plans. Refer to Specification Sections 057300, 061000 and 067300.
G	Railing System: 38" high rail system w/ maximum 4" openings. Handrail grip surface to conform to IRC Code. Handrails shall be provided on a min of one side of continuous treads of a run of four or more risers running continuously the entire flight at a vertical distance of 34" min to 36" max from stair nosing. Refer to Specifications Sections 059300 and 061000.
H	Stairs: 7/8" maximum rise, 10" minimum run, 36" minimum width. Provide handrails as required by the IRC Code. Provide 18" minimum landing at either side of exterior door when door is not used as the main entrance and stairs shall have a minimum tread depth of 10" at the valve at 12" in from the narrowest wooden part. Refer to Specification Sections 061000.
I	Basement Foundation Wall: Concrete foundation wall with fluid applied dampening per IRC section R408.1 depending from top of footing to the finish grade. Provide Styrofoam seal coat at unexcavated portions of exterior face. At basement walls finish interior face with 2x4 framing, insulation per IECC code, vapor barrier (warm side) beneath 1/2" gypsum board. Refer to Specification Sections 033000, 061000, 071113, 072100, 082116, 092513 and to engineered stamped foundation design for concrete reinforcement.
J	Slab on Grade: 4" thick concrete with rebar fabric reinforcement over prepared sub-grade and vapor barrier, as recommended by S&P. Engineer, 2015 IRC. Provide 1/2" expansion material at perimeter of slab and at all penetrations. Control joints as indicated or not less than 12 feet on center each way. Refer to Specification Sections 033000, 310000, and 334600.
K	Perimeter Drain System: Perforated perimeter drain system set in three draining gravel wrapped in geo-textile fabric. Daylight to headwall as indicated or drain to sump pumped to storm drain. Refer to Specification Section 334600.

## FOR ALL HILLSIDE AREAS:

IGNITION RESISTANT MATERIALS ARE REQUIRED FOR ROOFS, EAVES, SOFFITS, FASCIA AND TRIM, GUTTERS AND DOWNSPOUTS, DECK MATERIAL, ALL CEILING, THE UNDERSIDE OF ALL EXTERIOR PROJECTIONS AND THE BASE OF EXTERIOR WALLS, POSTS, COLUMNS TO BE PROTECTED AT BOTTOM W/ FIBER RESISTANT SEALANT OR WIRE MESH (1/8" OR LESS IN DIMENSION).

## GENERAL NOTES:

- GENERAL CONTRACTOR, SUB-CONTRACTORS AND TRADES SHALL VERIFY ALL DIMENSIONS AND DRAWINGS SHOWN ON THESE DOCUMENTS PRIOR TO STARTING CONSTRUCTION. IT SHALL BE THE RESPONSIBILITY OF THOSE PARTIES TO REPORT ANY DISCREPANCIES REGARDING THESE DOCUMENTS INCLUDING INTERPRETATION, DIMENSIONS, NOTES, SCALE AND OTHER SIMILAR QUESTIONS SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGNER IMMEDIATELY IN WRITING. THE DESIGNER SHALL NOT BE RESPONSIBLE FOR ANY ERRORS, OMISSIONS OR CONFLICTS OF ANY KIND. THE DESIGNER SHALL NOT BE RESPONSIBLE FOR ANY CHANGES NOT NOTED IN WRITING TO THESE DRAWINGS AND SPECIFICATIONS.
- ALL MANUFACTURED PRODUCTS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS.
- DESIGNER SHALL NOT BE RESPONSIBLE FOR PLUMBING, ELECTRICAL OR MECHANICAL SYSTEM DESIGN, SIZING OR LOCATION.
- UNLESS NOTED OTHERWISE ALL FOUNDATION WALLS SHALL BE CONCRETE.
- UNLESS NOTED OTHERWISE ALL EXTERIOR WOOD STUD FRAME WALLS ARE 5 1/2".
- UNLESS NOTED OTHERWISE ALL INTERIOR WOOD STUD FRAME WALLS ARE 3 1/2".
- UNLESS NOTED OTHERWISE ALL ANGLES ARE 45° OR 90°.
- UNLESS NOTED OTHERWISE ALL WINDOWS AND DOOR HEADER HEIGHTS ARE AT 80" AND 96".
- UNLESS NOTED OTHERWISE ALL WINDOWS AND DOORS SHALL BE 2 1/8" MINIMAL FEET & INCHES. EXAMPLE: 2688 = 2'-8" WIDE & 6" TALL.

## COMMON SPECIFIC NOTES:

- FLOOR LINE ABOVE
- DECK LINE ABOVE
- WALL LINE BELOW
- CEILING BREAK
- 2x6 INTERIOR STUD WALL
- NOT USED
- NOT USED
- NOTE: SEE SITE PLAN FOR SPECIFIC DRIVE & WALKWAY INFORMATION
- NOT USED
- NOT USED
- TEMP GLASS DOOR & ENCLOSURE @ DOOR
- LOWER GLASS UNITS SHALL BE 8 SQ. FT. OF GLAZING OR LESS
- WINDOW SILL SHALL BE MIN 10" ABOVE TUB DRAIN STANDING SURFACE OR 1/2" INGS7 ABOVE VRECLANDING SURFACE
- NOTE: GLAZING ADJACENT AND WITHIN A 24" ARC OF DOOR IN THE CLOSED POSITION SHALL BE TEMP GLASS
- NOT USED
- PROVIDE MINIMUM 1/2" GYP BD UNDER STAIRS
- PROVIDE 68" TYP 2" GYP BD TO BE ATTACHED AT 16" O.C. PER CODE SEPARATION REQUIREMENTS AT ENTIRE GARAGE CEILING & WALLS ADJACENT TO LIVING AREA, WRAP BEAMS & ALL COLUMNS, AND UNDERSIDE OF ALL CANTILEVERS
- PROVIDE 68" TYP 2" GYP BD UNDER STAIRS AND A MAX CLEAR NET OPENING OF 57.5" & A CLEAR NET OPERABLE HEIGHT DIM OF 24" MIN & A CLEAR OPERABLE WIDTH OF 20" MIN & A FINISHED SILL HEIGHT OF NOT MORE THAN 4" AFF.
- NOT USED
- ALL FURRED CEILING SHALL BE LIMITED TO MAX 8" FURRED HEIGHT, 16" MAX 8" MIN CEILING HEIGHT, AS PER LOCAL CODE
- 1/2" GYP BD, TEXTURE, PAINT AND INSULATE THESE WALLS AS SHOWN
- NOT USED
- DIRECT VENT ZERO CLR GAS FIREPLACE W/ APPROVED ICC
- NOT USED
- HEARTH
- CASEWORK  
SEE CABINET MFG DETAILS FOR SPECIFIC CABINET LAYOUT & DIMENSIONS  
SEE CLOSET DETAILS FOR SPECIFIC CABINET LAYOUTS, SHELVING, CUBBIES, MISC & DIMENSIONS
- NOT USED
- CUSTOM MUD SET SHOWER. SEE FLOOR PLAN FOR SPECIFIC DIMENSIONS.  
30"X60" TUB/SHOWER
- NOT USED
- NOT USED
- LAUNDRY TUB
- NOT USED
- WASHER/DRYER
- DRYER DUCT SHALL NOT EXCEED 25' LENGTH SHALL BE INSTALLED AT AN ANGLE OF 3° MAX. THE EXTERIOR WALL WITHIN 3' OF ANY OPENINGS PROVIDE 100 SQ. IN. MIN. MAKE-UP AIR DOOR NEEDS TO BE LOUVERED OR GRILLED. MAKE-UP AIR NEEDS TO BE LOUVERED OR GRILLED. MAKE-UP AIR OR LARGER - OR PROVIDE GRILL ABOVE DOOR
- NOT USED
- PROVIDE INSULATION AS NOTED ON PLANS AND/OR AS PER IECC, INTERNATIONAL ENERGY CONSERVATION CODE CERTIFICATE

## REVISIONS

NO.	DESCRIPTION	DATE
1		11/15/2023

Released for Permit  
11/21/2023 4:12:14 PM  
REGULATORY  
CONSTRUCTION

THE  
PURVIS RESIDENCE  
400 DAHLIA STREET  
COLORADO SPRING, CO 80904  
PROJECT NUMBER # 22-2215

DRAWN BY: EAH  
CHECKED: DMNS  
PLOT: 11/15/2023


Sheet # **CS1** OF 1 SHEETS








**REVISIONS**



**LGA STUDIOS**  
 201 E. Las Animas Street  
 Suite 113  
 Colorado Springs, CO. 80903  
 Phone: (719) 636-0880  
 office@lga-studios.com  
 www.lgastudios.com

**CONTRACTOR**  
**ROBERT SCOTT**  
**CUSTOM HOMES**  
 COLORADO SPRING, CO 80902  
 PH: 719-499-6754  
 RSHOMES2@GMAIL.COM

**THE**  
**PURVIS RESIDENCE**  
 400 DAHLIA STREET  
 COLORADO SPRING, CO 80904  
 PROJECT NUMBER # 22-2215

Released for Permit  
 08/24/2022 10:53:32 AM  
  
 BUILDING DEPARTMENT  
 CONSTRUCTION

**DRAWN BY: EAH**  
**CHECKED: DMINS**  
**PLOT: 8/18/2022**

Sheet #  
**SS2**

OF 2 SHEETS

**09 6500 Resilient Flooring**  
 1.0 GENERAL  
 1.1 Sheetrock  
 2.0 PRODUCTS  
 2.1 Sheet Vinyl Flooring (80) inch thick, as selected by contractor  
 3.0 EXECUTION  
 3.1 Sheet vinyl flooring joints shall be heat welded, flush with each other, and matching the color and texture of the sheet vinyl flooring. Install in accordance with manufacturer's specifications.

**09 6900 Carpeting**  
 1.0 GENERAL  
 2.0 PRODUCTS  
 2.1 Carpet, As selected by the Owner.  
 3.0 EXECUTION

**09 9100 GENERAL Painting**  
 1.1 Exterior and interior surfaces not factory finished and not specifically excluded shall be painted. Interior trim selected by Owner shall be sanded with clear finish, balance painted.  
 2.0 PRODUCTS  
 2.1 All paint, stain, and clear finish shall be Acrylic Latex "professional best grade" products of acceptable manufacturers. 150L VOC Rating.  
 2.2 Provide primers and undercoat paint produced by the same manufacturer as the finish paint.  
 2.3 Wall and ceiling surfaces shall be stain resistant finish at Kitchen and Baths. All other wall and ceiling finishes shall be flat.  
 2.4 All exterior paint finishes shall be a semi-gloss finish.  
 2.5 Primer to be 2116 Gypsum board partitions and ceilings for drywall. Stain resistant primer to be applied in place of primer for areas requiring level 5 drywall finish.  
 3.0 EXECUTION  
 3.1 Apply one coat of primer and two finish coats of paint to all painted surfaces. Primer and first finish coat shall be applied to all surfaces selected interior trim.  
 3.2 Apply one coat stain and two coats clear polyurethane finish to wood surfaces.  
 3.3 Make an necessary surface preparation, testing, and sample approval for all finishes.  
 3.4 Sand finishes on wood and metal surfaces between coats as necessary to assure smoothness and adhesion of subsequent coats.  
 3.5 Furnish and lay drop coats or mask off areas where painting is being performed. Prime and deposit work from damage during painting and finish operation.

**DIVISION 10 SPECIALTIES**  
**10 7000 Toilet Accessories**  
 1.0 GENERAL  
 2.0 PRODUCTS  
 2.1 Toilet paper holders (label paper holders, paper towel dispensers, towel bars, mirrors, medicine cabinets) as selected by Owner.  
 3.0 EXECUTION  
 3.1 Provide solid blocking as required for mounting of selected toilet accessories.

**10 9000 Manufactured Fireplaces**  
 1.0 GENERAL  
 2.0 PRODUCTS  
 2.1 Provide fireplace and stove units as shown on plans. Gas log, venting, and/or direct vent as indicated (ICC listed and approved). As required, provide pre-finished chimney crown as manufactured by Chimney King, specific style as shown.  
 2.2 Provide pre-finished chimney crown as manufactured by Chimney King, specific style as shown.  
 2.3 Selected style must be listed and labeled for use with the specific manufacturer's chimney system utilized with the fireplace.  
 3.0 EXECUTION  
 3.1 Install fireplace unit, flue, and chimney crown as recommended by the manufacturer and for specific conditions and systems indicated.

**DIVISION 11 EQUIPMENT**  
**11 3100 Appliances**  
 1.0 GENERAL  
 2.0 PRODUCTS  
 2.1 Kitchen Appliances: As selected by the Owner – all Energy Star certified.  
 3.0 EXECUTION  
 3.1 Installation shall be true and level according to manufacturer's written instructions.  
 3.2 Provide all necessary power and plumbing connections.

**DIVISION 12 FURNISHINGS**  
**12 3200 Wood Casework**  
 1.0 GENERAL  
 2.0 PRODUCTS  
 2.1 Cabinetry shall be as selected by the Owner.  
 2.2 Kitchen countertops shall be as selected by the Owner  
 3.0 EXECUTION  
 3.1 Finish casework accurately to place, level, and secure to floor and walls as required. Install items complete. Scribe and closely fit casework to adjacent work. Fasten base cabinets securely to base and to floor.  
 3.2 Adjust casework and hardware so that doors and drawers operate smoothly without warp or bind.

**DIVISION 13 SPECIAL CONSTRUCTIONS -None Required-**  
**DIVISION 14 CONVEYING SYSTEMS -None Required-**  
**DIVISION 22 PLUMBING**  
**22 0000 Plumbing Fixtures and Equipment**  
 1.0 GENERAL  
 2.0 PRODUCTS  
 2.1 Refer to Plumbing Plan, fixtures as selected by the Owner.  
 3.0 EXECUTION  
 3.1 Shall comply with local code.

**DIVISION 23 HEATING, VENTILATION, AND AIR-CONDITIONING**  
**23 0000 Mechanical Equipment**  
 1.0 GENERAL  
 2.0 PRODUCTS  
 2.1 Refer to Mechanical Plans for Heating and Air-Conditioning Equipment per Schedule and Notes by mechanical contractor.  
 3.0 EXECUTION  
 3.1 Shall comply with local codes and shall be installed using duct sealing methods per Chapter 12, Building Code of Code Officials. Reused 2006 Joe Lsbueck.

**DIVISION 26 ELECTRICAL**  
**26 0000 Basic Electrical Requirements**  
 1.0 GENERAL  
 2.0 PRODUCTS  
 2.1 Lighting fixtures as selected by the Owner.  
 3.0 EXECUTION  
 3.1 Coordinate with Owner for Computer, TV and other data cabling to be included.

**DIVISION 31 EARTHWORK**  
**31 0000 Earthwork**  
 1.1 The Soils Engineer will be hired directly by the Owner/GC. Costs of earthwork testing and oversight by the Soils Engineer will be paid by the Owner/GC.  
 2.0 PRODUCTS  
 2.1 On-Site or Imported fill and backfill Materials as acceptable to the Soils engineer.  
 3.0 EXECUTION  
 3.1 In addition to required compaction of fill and backfill materials, compact bottom of all footing excavations to the satisfaction of the Soils Engineer using a vibratory compactor immediately prior to forming.

3.2 Cut and fill areas as indicated or required to finish grades indicated. Leave graded surface clean, free from rubbish and large clods, and free from ruts, holes, or depressions.  
 3.3 Sub-grade Below Footings, Foot Slab, Sidewalk, & Paving: Tolerance +/- 0.02' (1/4").  
 3.4 Sub-grade Under All Other Areas Disturbed by Site Grading: Tolerance +/- 0.02' (1/4").  
 3.5 Final Finish Grades: All in hardscape areas. Tolerance +/-0.11'(1/4").  
 3.6 Indicated on site plan.  
 3.7 Import or export material as necessary to achieve finish grades indicated on drawings. Import and export material shall be at the Owner's expense. Unusable or excess material including cobbles and boulders shall be disposed of off-site.

**31 2113 Radon Venting**  
 1.0 GENERAL  
 1.1 Provide radon mitigation system in accordance with design and layout of radon test results. Radon mitigation system shall be installed in accordance with radon mitigation system design and layout of radon test results.  
 2.0 PRODUCTS  
 2.1 Radon mitigation system according to approved submittals  
 3.0 EXECUTION

**DIVISION 32 EXTERIOR IMPROVEMENTS**  
**32 0000 Planting and Irrigation**  
 1.0 GENERAL  
 2.0 PRODUCTS  
 3.0 EXECUTION

**32 1413 Precast Concrete Unit Paving**  
 1.0 GENERAL  
 1.1 Provide precast concrete paver units, sand, setting and sand joint filler. Related Requirements: Section 31 0000 Earthwork, for preparation of soil substrate.  
 1.2 Related Requirements: Section 31 0000 Earthwork, for preparation of soil substrate.  
 1.3 Submittals:  
 a. Samples, Submit two samples of each paver type.  
 b. Manufacturer's installation instructions. Indicate substrate requirements and installation methods.  
 2.0 PRODUCTS  
 2.1 Interlocking Concrete Pavers: The design is based on the following product: Pavestone Concrete Pavers. Also acceptable, subject to approval by the Architect:  
 a. Haronor Avashchabul Pavers, Inc.  
 b. Oldcastle  
 2.2 Concrete Pavers: Hydraulically pressed concrete, complying with ASTM C1091, and finished with a non-slip surface.  
 2.3 Sand for setting Bed: Clean washed natural sand or crushed stone complying with the gradation requirements of ASTM C33 for fine aggregate.  
 2.4 Joint Filler: Fine washed sand, with 100 percent passing No. 16 sieve and not more than 10 percent passing No. 200 sieve.  
 3.0 EXECUTION  
 3.1 Verify that substrate is level or to correct gradient, smooth, capable of supporting pavers and imposed loads, ready to receive paver installation.  
 3.2 Treat soil with herbicide to retard plant growth.  
 3.3 Spread setting bed sand, dampen and compact, place paver units, and install joint filler.  
 3.4 Cut paver units at edges, joints, and changes in direction with masonry saw.  
 3.5 Trim and level cover units with mechanical vibrator until units are fully bedded, tamped, and to correct elevation and gradients. Do not tamper unrestrained edges.


**DIVISION 33 UTILITIES**  
**33 0000 Utilities**  
 1.0 GENERAL  
 1.1 Perform all Utility Extension work in accordance with Local Utilities Provider standard specifications and details.  
 1.2 Refer to Utility Plans for details. Contractor shall pay all over permit fees and construction related fees.  
 2.0 PRODUCTS  
 3.0 EXECUTION

**33 4600 Sub-drainage Systems**  
 1.0 GENERAL  
 1.1 Coordinate installation of system with Soils Engineer. Allow Soils Engineer to observe field conditions prior to layout, excavation, and installation.  
 2.0 PRODUCTS  
 2.1 PVC or HDPE single wall pipe, Perforated pipe at foundation drain system. Solid pipe outside of drainage areas for connection to outfall.  
 3.0 EXECUTION  
 3.1 Refer to Utility Plans for details. Contractor shall pay all over permit fees indicated on Drawings.  
 3.2 Refer to referenced Subsurface Soil Investigation for sub-drain detail.  
 3.3 Outfall to sump or daylight, as required.

**END OF OUTLINE SPECIFICATION-LGA STUDIOS**

Copyright 2022, by LGA Studios. No part of this plan may be reproduced or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without permission in writing from LGA Studios. The user of this plan shall be deemed to have accepted responsibility for the use of this plan. No part shall be used for any other project without the express written approval of LGA Studios and the user. This plan is provided as a guide only and does not constitute a contract. The user of this plan shall be deemed to have accepted responsibility for the use of this plan.

**REVISIONS**



LGA STUDIOS  
201 E. Las Animas Street  
Suite 113  
Colorado Springs, CO 80903  
Phone: (719) 636-8880  
office@lga-studios.com  
www.lgastudios.com

**ROBERT SCOTT  
CUSTOM HOMES**  
CONTRACTOR  
COLORADO SPRING, CO 80902  
PH: 719-499-6754  
RSHOMES2@GMAIL.COM

**THE  
PURVIS RESIDENCE**  
400 DAHLIA STREET  
COLORADO SPRING, CO 80904  
PROJECT NUMBER # 22-2215

Released for Permit  
08/24/2022 10:53:32 AM  
LGA STUDIOS  
CONSTRUCTION

DRAWN BY: EAH  
CHECKED: DMINS  
PLOT: 8/18/2022

Sheet # **A1**  
OF 9 SHEETS

**GENERAL FOUNDATION NOTES:**

- FOUNDATION DESIGN TO BE COMPLETED ON-SITE. INSPECTION OF SOILS BY COLORADO REGISTERED SOILS ENGINEER, DESIGN & SOILS REPORT TO BE ON HAND AT TIME OF INSPECTION AND/OR SUBMITTED TO THE BUILDING DEPARTMENT AT THE TIME OF PLAN CHECK. FOUNDATION DESIGN TO BE COMPLETED BY LGA STUDIOS FOUNDATION DRAWINGS BY LGA STUDIOS, INC. THE PLANS SHALL BE VERIFIED BY A PROFESSIONAL ENGINEER AND DISCREPANCIES REPORTED TO THE DESIGNER. LGA STUDIOS SHALL DO SO TO RELIEVE THE DESIGNER OF ERRORS.
- ALL GRADES SHALL SLOPE AWAY FROM ANY STRUCTURE A MINIMUM OF 10% OR 1" IN 10' AND SHALL BE VERIFIED BY A PROFESSIONAL ENGINEER. SOILS REPORT, SOILS REPORT SHALL GOVERN SLABS AND FOUNDATION DRAINAGE. STEP FOUNDATION AS PER GRADE CONDITIONS AS SHOWN ON THE ELEVATIONS AND MAY NEED SOME ADJUSTMENT AT SITE.
- SEE PLUMBING AND MECHANICAL CONTRACTORS FOR ANY REQUIRED PENETRATIONS.
- INSTALL ALL COLUMN ANCHORS PER MFG. SEE MAIN LEVEL FLOOR FINISHING PLAN FOR COLUMN ANCHOR TYPE AND LOCATION.
- PROVIDE 3" MINIMUM BEARING AT BEAM POCKETS (TYP.).
- FIELD VERIFY ACTUAL WALKOUT LOCATION WITH SITE PLAN AND AT SITE PER EXISTING SITE CONDITIONS.
- PROVIDE MINIMUM PERIMETER FOUNDATION AS SHOWN. FOUNDATION SHALL BE PERMANENTLY ATTACHED PER STATE BUILDING DEPARTMENT INTERNATIONAL ENERGY CONSERVATION CODE CERTIFICATE.

**ASSEMBLY NOTES:**


A	ROOF:
B	FASCIA/SOFFT:
C	EXTERIOR WALL:
D	EXTERIOR WALL BALLOON FRAME:
E	FRAMED FLOOR SYSTEM:
F	EXTERIOR DECK SYSTEM:
G	RAILING SYSTEM:
H	STAIRS:
I	BASEMENT FOUNDATION WALL:
J	SLAB ON GRADE:
K	PERIMETER DRAIN SYSTEM:

ALL ASSEMBLIES AND GENERAL NOTES REFER TO SHEET CS1 AND SPECIFICATIONS SHEET SS1

**SPECIFIC FOUNDATION NOTES:**

- 40 DROP TOP OF WALL 6" @ DOOR & POUR SLAB OVER. CONTRACTOR TO VERIFY R.O. WIDTH.
- 41 DROP TOP OF WALL 8" @ DOOR & POUR SLAB OVER. CONTRACTOR TO VERIFY R.O. WIDTH.
- 42 2X4 MUJ SILL W/ 1/2" DIA X 10' ANCHOR BOLTS @ 48" FROM ENDS W/ MIN. 7" EMBEDMENT W/ 2 PER PIECE MIN.
- 43 DASHED LINES INDICATE RL PLUMBING FIXTURES
- 44 NOT USED
- 45 STEP TOP OF FND.
- 46 NOT USED
- 47 RIPPED 6" T. OR REDWOOD 2X10 SILL PLATE AT OP FND W/ 1/2" DIA X 10' ANCHOR BOLTS @ 48" O.C. & 12" FROM ENDS W/ MIN. 7" EMBEDMENT W/ 2 PER PIECE MIN.


NOTE:  
FOR OTHER APPLICABLE KEYNOTES, SYMBOLS & HATCHES SEE GENERAL NOTE SHEET "CS1" FOR KEYNOTES AND CORRESPONDING ASSEMBLY NOTES.



**FOUNDATION LAYOUT PLAN**

SCALE: 1/4" = 1'-0"

**REVISIONS**



LGA STUDIOS  
201 E. Las Animas Street  
Suite 113  
Colorado Springs, CO 80903  
Phone: (719) 635-1880  
office@lgestudios.com  
www.lgestudios.com

**CONTRACTOR**  
**ROBERT SCOTT**  
**CUSTOM HOMES**  
COLORADO SPRING, CO 80902  
RSHOMES2@GMAIL.COM  
PH: 719-696-6754

**THE PURVIS RESIDENCE**  
400 DAHLIA STREET  
COLORADO SPRING, CO 80904  
PROJECT NUMBER # 22-2215

Released for Permit  
08/24/2022 10:53:22 AM  
BRUNNEN  
CONSTRUCTION

DRAWN BY: P.C.  
CHECKED: LGA  
PLOT: 8/18/2022

Sheet #  
**A2**

OF 9 SHEETS

**GENERAL LOWER LEVEL NOTES**

- UNLESS NOTED OTHERWISE ALL CONCRETE FOUNDATION WALL HEIGHTS THIS LEVEL TO BE A 4'-0" MINIMUM INTERIOR WALL HEIGHTS TO BE 8'-0" MINIMUM. VERIFY.
- PROVIDE 1" LOW RESISTANCE RETURN AIR PATH FOR ALL CLOSED ROOMS. PER CODE CAN USE T-GRILLS OR UNDER-CUT DOORS.
- ALL NON-BEARING WALL, STAIRS AND LANDINGS MUST FLOAT.
- MAINTAIN MINIMUM 30" CLEAR SPACE IN FRONT OF THE CONTROL SIDE OF FURNACE & WATER HEATER. WATER HEATER MUST BE PLACED SO THE VENT IS ADJACENT & CLOSEST TO THE VENT STACK.
- MAX-HIGH RETAINING WALLS ARE SHOWN FOR REFERENCE ONLY. FIELD VERIFY WITH SITE PLAN AND ACTUAL SITE CONDITIONS PRIOR TO BACKFILLING. IN ALL CASES CONTRACTOR SHALL VERIFY ACTUAL RETAINING WALL CONSTRUCTION.

**SPECIFIC ELECTRICAL NOTES / SYMBOLS**

(E) EXHAUST FAN (VENT TO EXTERIOR) FANS VENTED THROUGH UNCONDITIONED SPACE MAX 25'-0" & MIN R-6 INSUL

(S) SMOKE ALARM HARDWIRED & INTERLOCK SMOKE ALARM DETECTOR w/BATTERY BACK-UP

(C) CARBON MONOXIDE DETECTOR

NOTES:  
ALL PLACEMENT OF LIGHTING, OUTLETS, TV, PHONES, SECURITY, COMPUTER, STEREO/VIDEO EQUIPMENT, AND ALL ELECTRICAL FIXTURES SHALL BE VERIFIED PRIOR TO CONSTRUCTION w/CONTRACTOR. ELECTRICAL SHALL BE WIRED PER THE NATIONAL ELECTRICAL CODE AND LOCAL CODES. SEE SPECIFICATIONS DIVISION 16010 BASIC ELECTRICAL REQUIREMENTS.

**ASSEMBLY NOTES:**

A	ROOF:
B	FASCIA/SOFFT:
C	EXTERIOR WALL:
D	EXTERIOR WALL BALCONY FRAME:
E	FRAMED FLOOR SYSTEM:
F	EXTERIOR DECK SYSTEM:
G	RAILING SYSTEM:
H	STAIRS:
I	BASEMENT FOUNDATION WALL:
J	SLAB ON GRADE:
K	PERIMETER DRAIN SYSTEM:

ALL ASSEMBLIES AND GENERAL SPECIFICATIONS REFER TO SHEETS CS1 AND CS2 DIVISION 16010 BASIC ELECTRICAL REQUIREMENTS.

**SPECIFIC LOWER LEVEL NOTES:**

48 PROVIDE BLOCK OUTS AS NEEDED IN STEPPED FOUNDATION WALL FOR NOTED WINDOWS.


49 METAL WINDOW WELL AS GRADE REQUIRES: MINIMUM 12" CLEARANCE TO EXTERIOR W/ LADDER PER CODE (8 50' MIN CLR)

50 NOT USED

51 PROVIDE MECHANICAL VENTILATION PER IRC 2015 SECTION R303.1.2 AND ARTIFICIAL LIGHT PER SECTION R303.1.1

52 PROVIDE FIRE PROTECTION OF FLOORS PER 2015 R302.1.3 @ ENTIRE CEILING

NOTE:  
FOR OTHER APPLICABLE KEYNOTES, SYMBOLS, & HATCHES SEE GENERAL NOTE SECTION 10000 GENERAL NOTES, CORRESPONDING ASSEMBLY NOTES.



**LOWER LEVEL FLOOR PLAN** SCALE: 1/4" = 1'-0"

**REVISIONS**

**LGA STUDIOS**  
 201 E. Las Animas Street  
 Suite 113  
 Colorado Springs, CO 80903  
 Phone: (719) 635-4880  
 office@lga studios.com  
 www.lgastudios.com

**ROBERT SCOTT**  
 CONTRACTOR  
 COLORADO SPRING, CO 80902  
 RSHOMES2@GMAIL.COM  
 PH: 719-499-6754

**THE PURVIS RESIDENCE**  
 400 DAHLIA STREET  
 COLORADO SPRING, CO 80904  
 PROJECT NUMBER # 22-2215

Released for Permit  
 09/24/2022 11:32:32 AM  
**SHARPS**  
 CONSTRUCTION

DRAWN BY: P.C.  
 CHECKED: LGA  
 PLOT: 8/18/2022

Sheet # **A3**  
 OF 9 SHEETS

**GENERAL MAIN LEVEL NOTES:**

- UNLESS NOTED OTHERWISE ALL WALL HEIGHTS THIS LEVEL TO BE 10'-1 1/8".
- PROVIDE 'LOW RESISTANCE' RETURN AIR PATH FOR ALL CLOSED ROOMS. PER CODE CAN USE T-GRILLS OR UNDER-CUT DOORS.

**SPECIFIC ELECTRICAL NOTES / SYMBOLS**

(E) EXHAUST FAN (VENT TO EXTERIOR) FANS UNCONDITIONED SPACE MAX 25'x4' x MN R45 INSUL.

(S) SMOKE HARDWIRED & INTERLOCK SMOKE ALARM DETECTOR w/BATTERY BACK-UP

(C) CARBON MONOXIDE DETECTOR

NOTES:  
 ALL PLACEMENT OF LIGHTING, OUTLETS, TV, PHONES, SECURITY, COMPUTER, STEREO/VIDEO WIRING, INTERCOM OR ANY OTHER ELECTRICAL FIXTURES SHALL BE VERIFIED PRIOR TO COMMENCEMENT OF CONSTRUCTION. ALL WIRING SHALL BE WIRED PER THE NATIONAL ELECTRICAL CODE AND LOCAL CODES. SEE SPECIFICATIONS DIVISION 16010 BASIC ELECTRICAL REQUIREMENTS.

**ASSEMBLY NOTES:**

A	ROOF:
B	FASCIA/SOFFIT:
C	EXTERIOR WALL:
D	EXTERIOR WALL BALLOON FRAME:
E	FRAMED FLOOR SYSTEM:
F	EXTERIOR DECK SYSTEM:
G	RAILING SYSTEM:
H	STAIRS:
I	BASEMENT FOUNDATION WALL:
J	SLAB ON GRADE:
K	PERIMETER DRAIN SYSTEM:


ALL ASSEMBLIES AND GENERAL NOTES REFER TO SHEET CS1 AND SPECIFICATIONS SHEET S51

**SPECIFIC MAIN LEVEL NOTES:**

55 NOT USED

APPROVED  
 11/22/2022 9:06:09 AM  
 FDDPM  
 Colorado Springs Fire Department

NOTE:  
 FOR OTHER APPLICABLE KEYNOTES, SYMBOLS & HATCHES SEE GENERAL NOTE SHEET CS1 AND CORRESPONDING ASSEMBLY NOTES.




**MAIN LEVEL FLOOR PLAN**  
 SCALE: 1/4" = 1'-0"

Copyright © 2022, LGA Studios. No part of this plan may be reproduced or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without permission in writing from LGA Studios. This plan is intended for the use of the owner and is not to be used for any other purpose. The user of this plan is responsible for obtaining all necessary permits and for obtaining appropriate liability insurance coverage.




- Class A Roofing Required.
- Exterior cladding, eaves and soffits shall be ignition-resistant (to include fascia and trim).
- Exterior doors non-combustible or solid core not less than 1-3/4"
- Attic & Roof vents screened with wire mesh or hardware cloth with openings 1/8" or less.
- No gable vents.
- Gutters and downspouts of non-combustible materials with drip edge extending to gutter and no exposed wood. If vinyl used, non-combustible landing area below minimum 5' from structure is required.
- Decks and other habitable spaces to be of ignition resistant or noncombustible materials.
- Base of exterior walls, posts, columns protected on bottom with fire resistant sealant or wire mesh with no larger than 1/8" openings.
- Fuels management within 30' of all construction.



Copyright 2022, LGA Studios. No part of this drawing may be reproduced or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of LGA Studios and the architect. The architect and the contractor shall be responsible for the construction of the building. The architect and the contractor shall be responsible for the construction of the building. The architect and the contractor shall be responsible for the construction of the building.

## SECTION 1

SCALE: 1/4" = 1'-0"



Copyright 2022, LGA Studios. No part of this drawing may be reproduced or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of LGA Studios and the architect. The architect and the contractor shall be responsible for the construction of the building. The architect and the contractor shall be responsible for the construction of the building. The architect and the contractor shall be responsible for the construction of the building.

## SECTION 2

SCALE: 1/4" = 1'-0"

- ### GENERAL SECTION NOTES:
- UNLESS OTHERWISE NOTED ALL SECTIONS ARE SECTIONED IN ACCORDANCE WITH THE REFERENCE OF COMPLETE LABELING AND NOTES.
  - SEE STRUCTURAL SHEETS FOR ALL CALLOUTS OF FRAMING MEMBERS, BEAMS, HEADERS, AND CONNECTIONS ETC., TYPICAL.
  - ALIGN FLOOR JOISTS TO ALLOW FOR PLUMBING AND MECHANICAL INSTALLATION.
  - SECTION BEYOND ITEMS ARE SHOWN FOR REFERENCE ONLY AND DOES NOT INDICATE ANY SPECIFIC MATERIAL, MANUFACTURER OR TYPE.

### ASSEMBLY NOTES:

A	ROOF:
B	FASCIA/SOFFT:
C	EXTERIOR WALL:
D	EXTERIOR WALL BALLOON FRAME:
E	FRAMED FLOOR SYSTEM:
F	EXTERIOR DECK SYSTEM:
G	RAILING SYSTEM:
H	STAIRS:
I	BASEMENT FOUNDATION WALL:
J	SLAB ON GRADE:
K	PERIMETER DRAIN SYSTEM:


ALL ASSEMBLIES AND GENERAL NOTES REFER TO SHEET CS1 AND SPECIFICATIONS SHEET S1

### SPECIFIC SECTION NOTES:

- 66 NOT USED
- 67 BEARING WALL. SEE STRUCTURAL SHEETS FOR ADDITIONAL INFORMATION
- 68 HANGER TRUSS OR RAFTER. SEE STRUCTURAL SHEETS FOR ADDITIONAL INFORMATION

NOTE:  
FOR OTHER APPLICABLE KEYNOTES, SYMBOLS & HATCHES SEE GENERAL NOTE SHEET "CS1" FOR KEYNOTES AND CORRESPONDING ASSEMBLY NOTES.

### SECTION NOTE SYMBOLS:



## SECTIONS

SCALE: 1/4" = 1'-0"

REVISIONS

LGA STUDIOS  
201 E. Las Animas Street  
Suite 113  
Colorado Springs, CO. 80903  
Phone: (719) 635-4880  
office@lgastudios.com  
www.lgastudios.com

CONTRACTOR  
**ROBERT SCOTT  
CUSTOM HOMES**  
COLORADO SPRING, CO 80902  
RSHOMES2@GMAIL.COM  
PH: 719-499-6754

THE  
**PURVIS RESIDENCE**  
400 DAHLIA STREET  
COLORADO SPRING, CO 80904  
PROJECT NUMBER # 22-2215

Released for Permit  
09/24/2022 11:32:32 AM  
LGA STUDIOS  
CONSTRUCTION

DRAWN BY: EAH  
CHECKED: DMINS

PLOT: 8/18/2022

Sheet #  
**A4**  
OF 9 SHEETS



**REVISIONS**

**LGA STUDIOS**  
 201 E. Las Animas Street  
 Suite 113  
 Colorado Springs, CO. 80903  
 Phone: (719) 635-4880  
 office@lga-studios.com  
 www.lgastudios.com

**CONTRACTOR**  
**ROBERT SCOTT**  
**CUSTOM HOMES**  
 COLORADO SPRING, CO 80902  
 PH: 719-499-6754  
 RSHOMES2@GMAIL.COM

**THE**  
**PURVIS RESIDENCE**  
 400 DAHLIA STREET  
 COLORADO SPRING, CO 80904  
 PROJECT NUMBER # 22-2215

Released for Permit  
 09/24/2025 11:32:32 AM  
**BRIDGES**  
**CONSTRUCTION**

**DRAWN BY: EAH**  
**CHECKED: DMINS**  
**PLOT: 8/18/2022**

Sheet #  
**A5**  
 OF 9 SHEETS

**GENERAL SECTION NOTES:**

- UNLESS OTHERWISE NOTED ALL SECTIONS ARE SHOWN IN PLAN. REFER TO GENERAL NOTES FOR COMPLETE LABELING AND NOTES.
- SEE STRUCTURAL SHEETS FOR ALL CALLOUTS OF FRAMING MEMBERS, BEAMS, HEADERS, AND CONNECTIONS ETC. TYPICAL.
- ALIGN FLOOR JOISTS TO ALLOW FOR PLUMBING AND MECHANICAL INSTALLATION.
- SECTION BEYOND ITEMS ARE SHOWN FOR REFERENCE ONLY AND DOES NOT INDICATE ANY SPECIFIC MATERIAL, MANUFACTURER OR TYPE.

**ASSEMBLY NOTES:**

A	ROOF:
B	FASCIA/SOFFIT:
C	EXTERIOR WALL:
D	EXTERIOR WALL BALLOON FRAME:
E	FRAMED FLOOR SYSTEM:
F	EXTERIOR DECK SYSTEM:
G	RAILING SYSTEM:
H	STAIRS:
I	BASEMENT FOUNDATION WALL:
J	SLAB ON GRADE:
K	PERIMETER DRAIN SYSTEM:


ALL ASSEMBLIES AND GENERAL NOTES REFER TO SHEET CS1 AND SPECIFICATIONS SHEET S1

**SPECIFIC SECTION NOTES:**

66	NOT USED
67	BEARING WALL. SEE STRUCTURAL SHEETS FOR ADDITIONAL INFORMATION
68	HANGER TRUSS OR RAFTER. SEE STRUCTURAL SHEETS FOR ADDITIONAL INFORMATION


**SECTION NOTE SYMBOLS:**

[Symbol]	= EARTH MATERIAL
[Symbol]	= CONCRETE



**SECTION 3**

SCALE: 1/4" = 1'-0"



**SECTION 4**

SCALE: 1/4" = 1'-0"

Class A Roofing Required.  
 Exterior cladding, eaves and soffits shall be ignition-resistant (to include fascia and trim).  
 Exterior doors non-combustible or solid core not less than 1-3/4"  
 Attic & Roof vents screened with wire mesh or hardware cloth with openings 1/8" or less.  
 No gable vents.  
 Gutters and downspouts of non-combustible materials with drip edge extending to gutter and no exposed wood. If vinyl used, non-combustible landing area below minimum 5' from structure is required.  
 Decks and other habitable spaces to be of ignition resistant or noncombustible materials.  
 Base of exterior walls, posts, columns protected on bottom with fire resistant sealant or wire mesh with no larger than 1/8" openings.  
 Fuels management within 30' of all construction.


**SECTION 4**

SCALE: 1/4" = 1'-0"

**SECTIONS**

SCALE: 1/4" = 1'-0"

**REVISIONS**



LGA STUDIOS  
201 E. Las Animas Street  
Suite 113  
Colorado Springs, CO. 80903  
Phone: (719) 636-4880  
office@lgastudios.com  
www.lgastudios.com

**CONTRACTOR**  
**ROBERT SCOTT**  
**CUSTOM HOMES**  
COLORADO SPRING, CO 80902  
RSHOMES2@GMAIL.COM  
PH: 719-499-6754

**THE**  
**PURVIS RESIDENCE**  
400 DAHLIA STREET  
COLORADO SPRING, CO 80904  
PROJECT NUMBER # 22-2215

Released for Permit  
09/24/2022 11:32:32 AM  
Bridges  
CONSTRUCTION

**DRAWN BY:** EAH  
**CHECKED:** LGA  
**PLOT:** 8/18/2022

Sheet #  
**A6**  
OF 9 SHEETS

**GENERAL ELEVATION NOTES:**

1. PROVIDE 6" MIN. GUTTER AT ALL OVERHANGS AND DOWNSPOUTS. LOCATE DOWNSPOUTS SUCH THAT THEY SHALL DRAIN 70% OF ROOF SURFACE PER 2"x1" DOWN SPOUT. ALL DOWN SPOUTS SHALL HAVE TYPICALS THAT ALLOW FOR PROPER DRAINAGE. DOWNSPOUTS SHALL BE VERTICAL WALL TO PROVIDE DRAINAGE AWAY FROM STRUCTURE IN ALL DIRECTIONS.
2. ROOF VENTILATION SHALL COMPLY WITH 2015 IRC. PROVIDE 1" MIN. CLEARANCE BETWEEN GUTTER EDGE OR 1/2" MIN. CLEARANCE BETWEEN GUTTER EDGE AND SLAB EDGE OR 1/2" MIN. CLEARANCE BETWEEN GUTTER EDGE AND SLAB EDGE SPACED FOR ROOF AREAS.
3. NOTES SHALL APPLY TO ALL ELEVATION CONDITIONS OF LINE OR SIMILAR CONDITIONS.
4. ANY BOULDER RETAINAGE WALL SHOWN SHALL BE LESS THAN 48" IN HEIGHT W/8" MIN APART IF MORE THAN (1) WALL OR SHALL BE DESIGNED BY SOILS ENGINEER.
5. ICE AND SNOW SHIELD REQUIRED ABOVE 7,000 FEET ABOVE SEA LEVEL.

**ASSEMBLY NOTES:**

A	ROOF:
B	FASCIA/SOFFT:
C	EXTERIOR WALL:
D	EXTERIOR WALL BALLOON FRAME:
E	FRAMED FLOOR SYSTEM:
F	EXTERIOR DECK SYSTEM:
G	RAILING SYSTEM:
H	STAIRS:
I	BASEMENT FOUNDATION WALL:
J	SLAB ON GRADE:
K	PERIMETER DRAIN SYSTEM:

ALL ASSEMBLY AND GENERAL NOTES REFER TO SHEET CS1 AND SPECIFICATIONS SHEET SS1


**SPECIFIC ELEVATION NOTES:**

- 80 STUCCO BUILT UP CAP AT OP FALSE STONE VENEER
- 81 1X4 CORNER BOARDS
- 82 HORIZONTAL SIDING MATERIAL TBD PRIOR TO ORDERING & INSTALLING. F.V. W/ CONTRACTOR
- 83 DIVIDED LIGHTS AS SHOWN. FIELD VERIFY W/ CONTRACTOR PRIOR TO ORDERING AND INSTALLATION
- 84 FALSE STONE VENEER FIELD VERIFY ACTUAL STONE INSTALLATION
- 85 2x8 TOP TRIM, 2X4 SIDE TRIM, & 1X1 AT OP 2X6 BTM TRIM
- 86 DOOR STYLE IS REPRESENTATIONAL ONLY. F.V. MATERIAL & AVAILABILITY W/ MFG PRIOR TO ORDERING
- 87 FALSE DECO CORBEL. SCREW INTO GABLE END TRUSS WEBS OR BLOCKING BETWEEN WEBS.
- 88 VERTICAL SIDING MATERIAL TBD PRIOR TO ORDERING & INSTALLING. F.V. W/ CONTRACTOR
- 89 2x4 AT OP 1X6 TRIM
- 89 2X12 BELLY BAND


**ELEVATION NOTE SYMBOLS:**

- = FINISH GRADE LINE
- - - = NATURAL GRADE LINE
- [ 01 ] = EXISTING GRADE ELEVATION
- 01 = FINISH GRADE ELEVATION
- TOW-07 = TOP OF FOUNDATION WALL ELEVATION
- MO=08 = MAIN LEVEL FINISH FLOOR ELEVATION

NOTE:  
FOR OTHER APPLICABLE KEYNOTES, SPECIFICATIONS AND GENERAL NOTE SHEETS FOR KEYNOTES AND CORRESPONDING ASSEMBLY NOTES.




**FRONT ELEVATION** SCALE: 1/4" = 1' - 0"



**LEFT ELEVATION** SCALE: 1/4" = 1' - 0"

**REVISIONS**



LGA STUDIOS  
201 E. Las Animas Street  
Suite 113  
Colorado Springs, CO. 80903  
Phone: (719) 636-0880  
office@lgastudios.com  
www.lgastudios.com

**CONTRACTOR**  
**ROBERT SCOTT**  
**CUSTOM HOMES**  
COLORADO SPRING, CO 80902  
RSHOMES2@GMAIL.COM  
PH: 719-499-6754

**THE PURVIS RESIDENCE**  
400 DAHLIA STREET,  
COLORADO SPRING, CO 80904  
PROJECT NUMBER # 22-2215

Released for Permit  
09/24/2025 11:32:32 AM  
Colorado Springs  
CONSTRUCTION

**DRAWN BY:** EAH  
**CHECKED:** LGA  
**PLOT:** 8/18/2022

Sheet #  
**A7**

OF 9 SHEETS

**GENERAL ELEVATION NOTES:**

1. PROVIDE 6" MIN. GUTTER AT ALL OVERHANGS AND AT ALL STAIRS. GUTTER RUNS TO BE LOCATED OUTSIDE OF GUTTER RUNS FIELD. LOCATE ALL DOWN SPOUTS SUCH THAT THEY SHALL DRAIN 70% OF ROOF SURFACE PER 2"x1" DOWN SPOUT. ALL DOWN SPOUTS SHALL HAVE TYPICAL 2" ALLOW FOR OVERHANG. DOWN SPOUTS SHALL BE SPACED FROM VERTICAL WALL TO PROVIDE DRAINAGE AWAY FROM STRUCTURE IN ALL DIRECTIONS.
2. ROOF VENTILATION SHALL COMPLY WITH 2015 IRC REQUIREMENTS. PROVIDE 1" x 6" BAND TYPICAL EAVE OR 1/2" x 3/8" SO. FT. UPPER ROOF TOTAL EQUAL SPACED FOR ROOF AREAS.
3. NOTES SHALL APPLY TO ALL ELEVATION CONDITIONS OF LINE OR SIMILAR CONDITIONS.
4. ANY BOULDER RETAINMENT WALL SHOWN SHALL BE LESS THAN 48" IN HEIGHT w/ 6" MIN APART IF MORE THAN (1) WALL OR SHALL BE DESIGNED BY SOILS ENGINEER.
5. ICE AND SNOW SHIELD REQUIRED ABOVE 7,000 FEET ABOVE SEA LEVEL.

**ASSEMBLY NOTES:**

A	ROOF:
B	FASCIA/SOFFIT:
C	EXTERIOR WALL:
D	EXTERIOR WALL BALLOON FRAME:
E	FRAMED FLOOR SYSTEM:
F	EXTERIOR DECK SYSTEM:
G	RAILING SYSTEM:
H	STAIRS:
I	BASEMENT FOUNDATION WALL:
J	SLAB ON GRADE:
K	PERIMETER DRAIN SYSTEM:

ALL ASSEMBLIES AND GENERAL SPECIFICATIONS REFER TO SHEET CS1 AND SPECIFICATIONS SHEET SS1



**SPECIFIC ELEVATION NOTES:**

- 80 STUCCO BUILT UP CAP ATOP FALSE STONE VENEER
- 81 1X4 CORNER BOARDS
- 82 HORIZONTAL SIDING MATERIAL TBD PRIOR TO ORDERING & INSTALLING. F.V. W/ CONTRACTOR
- 83 DIVIDED LIGHTS AS SHOWN. FIELD VERIFY W/ CONTRACTOR PRIOR TO ORDERING AND INSTALLATION
- 84 FALSE STONE VENEER FIELD VERIFY ACTUAL STONE LOOK W/ OWNER PRIOR TO ORDERING AND INSTALLATION
- 85 2x6 TOP TRIM, 2x4 SIDE TRIM, & 1X1 ATOP 2x6 BTM TRIM
- 86 6" x 6" S.T.E. IS REPRESENTATIVE. ONLY F.V. CHECK MATERIAL & AVAILABILITY W/ MFG PRIOR TO ORDERING
- 87 FALSE DECO CORBEL. SCREW INTO GABLE END TRUSS WEBS OR BLOCKING BETWEEN WEBS.
- 88 VERTICAL SIDING MATERIAL TBD PRIOR TO ORDERING & INSTALLING. F.V. W/ CONTRACTOR
- 89 2x4 ATOP 1X6 TRIM
- 90 2X12 BELLY BAND

**ELEVATION NOTE SYMBOLS:**

- = FINISH GRADE LINE
- - - = NATURAL GRADE LINE
- 01 = EXISTING GRADE ELEVATION
- 01 = FINISH GRADE ELEVATION
- TOW-07 = TOP OF FOUNDATION WALL ELEVATION
- MO-08 = MAIN LEVEL FINISH FLOOR ELEVATION

NOTE: FOR OTHER APPLICABLE KEYNOTES, SEE GENERAL NOTE SHEET CS1 FOR KEYNOTES AND CORRESPONDING ASSEMBLY NOTES.



**REAR ELEVATION**  
SCALE: 1/4" = 1'-0"

**Class A Roofing Required.**  
Exterior cladding, eaves and soffits shall be ignition-resistant (to include fascia and trim).  
Exterior doors non-combustible or solid core not less than 1-3/4"  
Attic & Roof vents screened with wire mesh or hardware cloth with openings 1/8" or less.  
No gable vanis.  
Gutters and downspouts of non-combustible materials with drip edge extending to gutter and no exposed wood. If vinyl used, non-combustible landing area below minimum 5' from structure is required.  
Decks and other habitable spaces to be of ignition resistant or noncombustible materials.  
Base of exterior walls, posts, columns protected on bottom with fire resistant sealant or wire mesh with no larger than 1/8" openings.  
Fuels management within 30' of all construction.

**RIGHT ELEVATION**  
SCALE: 1/4" = 1'-0"

**REAR AND RIGHT ELEVATIONS**  
SCALE: 1/4" = 1'-0"



**COLORADO SPRINGS FIRE DEPARTMENT**  
**RESIDENTIAL CONSTRUCTION PLAN REVIEW SUBMITTAL FORM**



**CSFD**  
 11/22/2022 9:55:28 AM

CONTRACTOR NAME: HOME OWNER DATE: 8/12/22

COMPANY REPRESENTATIVE: ELENA HEPWORTH w/LGA STUDIOS

COMPANY ADDRESS: 201 E LAS ANIMAS #112 C/S/C 80903

PHONE: 719.635.0880 FAX: N/A EMAIL: ELENAH@LGASTUDIOS.COM

PROPERTY ADDRESS: 400 DAHLIA ST

SUBDIVISION NAME: LENNON PARK

FILING #: LOT: 21,22 BLOCK: BLK B TAX SCHEDULE NUMBER: 7403204014

GROSS SQ. FOOTAGE OF HOME<sup>1</sup>: 4938 NUMBER OF FLOOR LEVELS: 2

CONSTRUCTION TYPE: VB (Wood Frame=VB)

**TYPE OF MATERIALS:**

ROOF: ASPHALT SIDING: STONE/COMPOSITE FLOOR JOISTS: BCI

SOFFITS/EAVES: COMPOSITE DECKING MATERIALS: COMPOSITE

CEILING FINISHES OVER COVERED PORCE/PATIO: COMPOSITE T&G

FIRE SPRINKLER SYSTEM: REQUIRED<sup>2</sup>: VOLUNTARY<sup>2</sup>: N/A:

FIRE ALARM SYSTEM: REQUIRED: VOLUNTARY: N/A:

REQUIRED FIRE FLOW<sup>2,3</sup>: 2000

MINIMUM NUMBER OF HYDRANTS REQUIRED: 2

MAXIMUM DISTANCE BETWEEN HYDRANTS<sup>3</sup>: 450

MAXIMUM HOSE LAY DISTANCE<sup>3</sup>: 225

CALCULATED "ON SITE" FIRE FLOW: hydrant 761-C=1388 768-C= 1126

CITY WATER MAP NUMBER:

For water flow calculations/modeling in the City of Colorado Springs – Please contact:  
[www.csu.org](http://www.csu.org) then using the Search bar, search for Fire Flow Report.

**ATTENTION:** The Colorado Springs Utilities attempts to get all fire flow calculations completed as soon as possible, but you must understand it may take approximately 2-3 working days for the calculations to be processed.

<sup>1</sup> The gross square footage must include all floors, basement, garage, and covered decks

<sup>2</sup> A 50% water flow credit will be allowed for all fire sprinkled structures.

<sup>3</sup> See Water Supplies for Commercial & Residential Fire Protection Packet.





**MONITORED  
FIRE ALARM  
SYSTEM IN LIEU  
OF FIRE FLOW**

2 Pages with Map

**Fire Flow Calculations**

Date Request Received:	8/12/2022	Date of Calculation:	8/16/2022
Project Name:	Purvis Residence		
Project Location:	400 Dahlia Street		
Project No:	NA	RMS No:	NA
		UDCF No:	NA
Project Contact:	Elena Hepworth	Company:	LGA Studios
Phone:	719-635-0880	Email:	<a href="mailto:ElenaH@LGAStudios.com">ElenaH@LGAStudios.com</a>
Pressure Zone:	Columbia	Overflow Elevation:	6540
Requested Fire Flow (gpm):	NA	Map Sheet:	C-31

Hydrant	Elevation	Theoretical Flow @ 20 psi (gpm)	Static Pressure @ Max Day Demand (psi)	Max Static Pressure @ Bury Depth (psi)*
761-C	6207	800	144	148
768-C	6237	800	131	135

**\*Bury depth is assumed to be 9 feet below the hydrant flange elevation**

**Per Colorado Springs Fire Department, the calculations provided are acceptable up to 1 year from above date.**


*Comments:*

Flows were less than the minimum allowable flow of 1500 gpm. Colorado Springs Fire Department will determine further actions upon review.

**\*\* Colorado Springs Rules and Regulations require that second and subsequent fire flow requests for the same address within a 12-month period are supplied with a minimum \$50.00 fee for existing infrastructure and \$200.00 fee for multiple runs for proposed infrastructure.**

Colorado Springs Utilities  
Water Planning  
[waterplanning@csu.org](mailto:waterplanning@csu.org)

Distribution: Jerry Edwards - Water Planning and Design, Doreen Withee - Fire Prevention



This information is provided solely for the purposes of this report and for no other purposes. While every effort is made to present accurate and reliable information, Colorado Springs Utilities does not represent or warrant this information to be appropriate for any use, reuse, or reliance other than the limited intended purpose of this report. Under no circumstances will Colorado Springs Utilities be liable for any general, special, direct, indirect, punitive or consequential damages that may result in any way from use of the information provided on this report, nor does it waive any part of the protections of the Colorado Governmental Immunity Act.



**Colorado Springs Utilities**  
It's how we're all connected

*Water Services Division  
Operations Department*

## *Fire Flow Test Report*

<b>DATE:</b>	8/24/2022	
<b>WORK ORDER #:</b>	3913729	
<b>REQUESTER NAME:</b>	Elena Hepworth LGA Studios <small>Requester #1</small>	<small>Requester #2</small>
<b>FAX #/Email:</b>	elenah@LGASudios.com	
<b>PHONE #:</b>	719-635-0880 ext 104	
<b>LOCATION:</b>	400 Dahlia St	
<b>FLOWING HYDRANT #:</b>	768-C	
<b>NOZZLE SIZE:</b>	2.5"	
<b>WATER MAIN SIZE:</b>		
<b>FLOW HYDRANT STATIC PSI:</b>	125	
<b>PITOT (PSI):</b>	45	
<b>FLOW (GPM):</b>	1126	
<b>RESIDUAL HYDRANT #:</b>	761-C	
<b>RESIDUAL HYD STATIC PSI:</b>	138	
<b>WATER MAIN SIZE:</b>		
<b>RESIDUAL PRESSURE (PSI):</b>	58	
<b>FIRE DEPT REVIEW PLAN #:</b>		
<b>FIRE INSPECTOR:</b>		
<b>CSFD REQUIRED FLOW (GPM):</b>		
<b>CALCULATED FLOW @ 20 PSI RESIDUAL (GPM):</b>	1388	Contact Fire Inspector to obtain Official Final Fire Flow Calculations.

**COMMENTS:**

*Please call with questions or comments.*

*Thank You*

*Sean Higbee, Water Distribution Supervisor*

Distribution: Fire Prevention (CSFD 385-7334)

**404 W. FONTANERO ST. BUILDING 457**

**P.O. BOX 1103, MAIL CODE 1210**

**COLORADO SPRINGS, CO 80947-1210**

**PHONE 719-668-4595, FAX 719-668-2890, shigbee@csu.org, <http://www.csu.org>**

*Page 1 of 1*