

ARCHITECTURAL ABBREVIATIONS

A

A/C

AIR CONDITIONING

ABV

ABOVE

ACST

ACOUSTIC, ACOUSTICAL

ADA

AMERICANS WITH DISABILITIES ACT

ADJ

ADJUSTABLE

ADJT

ADJACENT

AFI

ABOVE FINISH FLOOR

ALT

ALTERNATE

ALUM

ALUMINUM

ANOD

ANODIZED

ARCH

ARCHITECT, ARCHITECTURAL

ASPH

ASPHALT

ASSY

ASSEMBLY

AUTO

AUTOMATIC

B

BATT

BATT INSULATION

BKR

BACKER ROD

BD

BOARD

BF

BOTH FACES

BLDG

BUILDING

BLKG

BLOCKING

BLW

BELOW

BM

BEAM

BN

BULLNOSE

BOS

BOTTOM OF STEEL

BOT

BOTTOM

BRG

BEARING

BS

BOTH SIDES

BSMT

BASEMENT

BTWN

BETWEEN

BUR

BUILT UP ROOFING

BW

BOTH WAYS

BYND

BEYOND

C

CG

CORNER GUARD

CIP

CAST IN PLACE

CJ

CONTRACT JOINT

CL

CENTER LINE

CLG

CEILING

CLST

CLOSET

CLR

CLEAR

CLRM

CLASSROOM

CLU

CONCRETE MASONRY UNIT

CO

COMPANY

COL

COLUMN

CONC

CONCRETE

CONT

CONTINUE

CONTR

CONTRACTOR

COORD

COORDINATE

CORR

CORRIDOR

CPT

CARPET

CRS

COURSE(S)

CSWK

CASEWORK

CTR

CERAMIC TILE

CTV

CENTER

CTV

CABLE TELEVISION

CU

CUBIC

CUH

CABINET UNIT HEATER

CW

COLD WATER PIPING

D

DBL

DOUBLE

DEPT

DEPARTMENT

DTL

DETAIL

DF

DRINKING FOUNTAIN

DIA

DIAMETER

DIM

DIMENSION

DISP

DISPENSER

DL

DEAD LOAD

DMPF

DAMPROOFING

DN

DOWN

DR

DOOR

DS

DOWNSPOUT

DW

DISHWASHER

DWG

DRAWING

E

E

EAST

EA

EACH

ED

EDUCATION

EL

EXPANSION JOINT

ELEV

ELEVATION

ELEC

ELECTRICAL

ELEV

ELEVATOR

ENCL

ENCLOSURE

ENGR

ENGINEER

EPDM

ETHYLENE PROPYLENE DIENE MONOMER

EQ

EQUAL

EQUIP

EQUIPMENT

EW

ELECTRIC WATER COOLER

EWH

ELECTRIC WATER HEATER

EXC

EXCAVATE

EXIST

EXISTING

EF

EXHAUST FAN

EXP

EXPANSION

EXT

EXTERIOR

F

F/F

FACE TO FACE

FA

FIRE ALARM

FAAP

FIRE ALARM ANNUNCIATOR PANEL

FACP

FIRE ALARM CONTROL PANEL

FCO

FLOOR CLEAN OUT

FD

FLOOR DRAIN

FDC

FIRE DETRIMENT CONNECTION

FDTN

FOUNDATION

FE

FIRE EXTINGUISHER

FEC

FIRE EXTINGUISHER CABINET

FF

FINISH FACE

FFH

FINISH FLOOR ELEVATION

FH

FIRE HYDRANT

FHC

FIRE HOSE CABINET

FIN

FINISH

FXT

FITURE

FLR

FLOOR

FOF

FACE OF FINISH

FOS

FACE OF STUD

FR

FRAME

FRP

FIBERGLASS REINFORCED PLASTIC

FT

FOOT

FUR

FURRING

G

G

GAGE

GALV

GALVANIZED

GB

GRAB BAR

GL

GLASS

GLU LAM

GLUED LAMINATED WOOD

GLAZ

GLAZING

GYP

GYPSON

H

H

HOSE BIB

HDR

HEADER

HDW

HARDWARE

HDWD

HARDWOOD

HM

HOLLOW METAL

HRDL

HANDRAIL

HORIZ

HORIZONTAL

HP

HORSEPOWER

HGT

HEIGHT

HVAC

HEATING VENTILATING & AIR CONDITIONING

HW

HOT WATER

HYD

HYDRANT

I

I

INSIDE DIAMETER

INCL

INCLUDED

INSUL

INSULATION

INT

INTERIOR

J

J

JOIST

K

K

KELVIN

KW

KILOWATT

L

L

ANGLE

LAV

LAVATORY

LB

LUMBER

LF

LINEAR FEET (FOOT)

LIB

LIBRARY

LINO

LINOLEUM

LKR

LOCKER

LLH

LONG LEG HORIZONTAL

LLV

LONG LEG VERTICAL

LT

LIGHT

LV

LOUVER

M

MAX

MAXIMUM

MECH

MECHANICAL

MEMB

MEMBRANE

MFD

MANUFACTURED

MFR

MANUFACTURER

MIN

MINIMUM

MIRR

MIRROR

MISC

MISCELLANEOUS

MLDG

MOLDING

MO

MASONRY OPENING

MTD

MOUNTED

MTL

METAL

N

NA

NOT APPLICABLE

NONCOM

NONCOMBUSTIBLE

NIC

NOT IN CONTRACT

NO

NUMBER

NOM

NOMINAL

NRC

NOISE REDUCTION COEFFICIENT

NTS

NOT TO SCALE

O

OA

OVERALL

OC

ON CENTER

OD

OUTSIDE DIAMETER

OF/CI

OWNER FURNISHED/CONTRACTOR INSTALLED

OF/OI

OWNER FURNISHED/OWNER INSTALLED

OH

OVERHEAD

OPP

OPPOSITE

OPNG

OPENING

ORD

OVERFLOW ROOF DRAIN

P

PBD

PARTICLEBOARD

PCF

POUND PER CUBIC FOOT

PCP

PORLAND CEMENT PLASTER

PLAM

PLASTIC LAMINATE

PLBG

PLUMBING

PLYWD

PLYWOOD

PRFAB

PREFABRICATED

PREFIN

PREFINISHED

PRKG

PARKING

PSF

POUNDS PER SQUARE FOOT

PSI

POUNDS PER SQUARE INCH

PT

PAINT

PTD

PAPER TOWEL DISPENSER

PTN

PARTITION

PVC

POLYVINYL CHLORIDE

Q

QT

QUARRY TILE

QTB

QUARRY TILE BASE

QTY

QUANTITY

R

R

RADIUS, RISER

R-

THERMAL RESISTANCE

RA

RETURN AIR

RB

RUBBER BASE

RD

ROOF DRAIN

RDL

ROOF DRAIN LEADER

REF

REFER TO

REIN

REINFORCE

REQD

REQUIRED

REV

REVISION

RM

ROOM

RO

ROUGH OPENING

RPM

REVOLUTIONS PER MINUTE

RTU

ROOF TOP UNIT

S

SECTION

SECTION

SF

SQUARE FOOT, FEET

SA

SUPPLY AIR

SAT

SUSPENDED ACOUSTICAL TILE

SB

SPLASH BLOCK

SCHED

SCHEDULE

SCP

SCUPPER

SD

SOAP DISPENSER

SGT

SLAB ON GRADE

SGFS

STRUCTURAL GLAZED FACED TILE

SHT

SHEET

SHHG

SHEATHING

SIM

SIMILAR

SJ

SLIP JOINT

SLDG

SLIDING

SLNT

SEALANT

SND

SANITARY NAPKIN DISPENSER

SNDU

SANITARY NAPKIN DISPOSAL UNIT

SPEC

SPECIFICATION

SQ

SQUARE

SST

STAINLESS STEEL

STC

STANDARD TRANSMISSION CLASS

STD

STANDARD

STL

STEEL

STOR

STORAGE

STRUCT

STRUCTURAL

SUSP

SUSPENDED

SYMM

SYMMETRICAL

SYS

SYSTEM

T

T&G

TONGUE & GROOVE

TD

TOWEL DISPENSER

TEL

TELEPHONE

THK

THICKNESS

TO

TOP OF

TOC

TOP OF CONCRETE

TOM

TOP OF MASONRY

TOS

TOP OF STEEL

TOW

TOP OF WALL

TPD

TOILET PAPER DISPENSER

TYP

TYPICAL

U

UNFIN

UNFINISHED

UNL

UNLESS OTHERWISE NOTED

UR

URINAL

V

VAR

VARIABLE, VARIATION

VCT

VINYL COMPOSITION TILE

VERT

VERTICAL

VEST

VESTIBULE

VIF

VERIFY IN FIELD

VTR

VENT THROUGH ROOF

VWC

VINYL WALL COVERING

W

W

WEST

W/

WITH

WO

WITHOUT

WB

WOOD BASE

WBL

WOOD BLOCKING

WC

WATER CLOSET

WCO

WALL CLEAN OUT

WD

WOOD

WF

WIDE FLANGE

PLUMBING COUNT

GOVERNING CODES:		2011 PIKES PEAK REGIONAL BUILDING CODE 2009 INTERNATIONAL BUILDING CODE 2009 INTERNATIONAL FIRE CODE 2006 INTERNATIONAL MECHANICAL CODE 2006 INTERNATIONAL PLUMBING CODE 2012 INTERNATIONAL PLUMBING CODE 2014 NATIONAL ELECTRICAL CODE			
BUILDING AREA:		BASEMENT: 12321 SF FIRST FLOOR: 28314 SF SECOND FLOOR: 14355 SF			
PLUMBING COUNCIL ARE BASED ON BUILDING OCCUPANCY CLASSIFICATION:					
A-3 OCCUPANCY					
BASEMENT:	34 OCCUPANTS				
FIRST FLOOR:	1653 OCCUPANTS				
SECOND FLOOR:	1476 OCCUPANTS				
TOTAL:	3097 OCCUPANTS				
MALE:		1549			
FEMALE:		1548			

	WC/URINAL		LAVS	DRINKING FOUNTAIN
	MALE	FEMALE		
	1 PER 125 OCC	1 PER 65 OCC	1 PER 200 OCC	1 PER 500 OCC
FIXTURES REQUIRED	13	24	16	1
FIXTURES PROVIDED	14	15	16	1

FIXTURE COUNT EXCEPTION:	<p>THE PROPOSED PROJECT WILL RENOVATE THE EXISTING RESTROOMS OF THE COLORADO SPRINGS CITY AUDITORIUM TO INCREASE THE CAPACITY OF RESTROOM FIXTURES.</p> <p>CURRENTLY THE MAJORITY OF THE BUILDING IS SERVED BY MENS AND WOMENS RESTROOMS ON THE MAINFLOOR. THERE ARE OTHER RESTROOM IN THE BASEMENT AND IN THE SERVICE AREAS. THE MAJORITY OF PEOPLE ATTENDING THE AUDITORIUM USE THE MAIN FLOOR RESTROOMS.</p> <p>THIS PROJECT WILL INCREASE THE WATER CLOSETS IN THE MAIN FLOOR WOMENS ROOM FROM 6 TO 10 AND LAVATORIE FROM 4 TO 8.</p> <p>IN THE MENS ROOM THE NUMBER OF WATER CLOSETS WILL INCREASE FROM 3 TO 4. THE NUMBER OF URINALS WILL INCREASE FROM 3 TO 6 AND LAVATORIES FROM 3 TO 4.</p> <p>THE WORK IN THIS PROJECT WILL NOT ALTER ANY OF THE USES OF THE BUILDING WITH THE EXCEPTION OF TAKING OVER A STORAGE ROOM TO EXPAND THE RESTROOMS.</p> <p>THE TOTAL NUMBER OF FIXTURES IS BELOW WHAT IS REQUIRED FOR NEW CONSTRUCTION, HOWEVER THE PROPOSED PROJECT IS CONFINED BY THE EXISTING HISTORIC BUILDING. BY NOT CHANGING ANY OF THE BUILDINGS USES WE ARE CONFIDENT THAT WE ARE IMPROVING THE BUILDING AND OCCUPANT COMFORT AND DO NOT NEED TO ME THE PRESCRIBED NUMBER OF FIXTURES PER THE IPC2012.</p>
-------------------------------------	---

CONSTRUCTION TYPE:	II-B
NUMBER OF STORIES:	2

NATIONAL REGISTER OF HISTORIC PLACES INFORMATION:	THE COLORADO SPRINGS CITY AUDITORIUM WAS LISTED ON THE NATIONAL REGISTER IN NOVEMBER 7, 1995. SITE NUMBER: 5EP 628
--	---

VICINITY MAP



SHEET INDEX

INDEX GENERAL SHEETS

G-001	GENERAL INFORMATION AND SHEET INDEX
G-100	BASEMENT CODE PLAN
G-101	FIRST FLOOR CODE PLAN
G-102	SECOND FLOOR CODE PLAN

INDEX STRUCTURAL SHEETS

S001	GENERAL NOTES AND PARTIAL PLAN
S100	SECTIONS

INDEX ARCHITECTURAL SHEETS

AD410	ENLARGED RESTROOM DEMO PLAN & RCP
A-110	BASEMENT FLOOR PLAN (FOR REFERENCE ONLY)
A-111	FIRST FLOOR PLAN
A-112	SECOND FLOOR PLAN (FOR REFERENCE ONLY)
A-410	ENLARGED RESTROOM PLAN & DOOR SCHEDULE
A-411	RESTROOM FINISH PLAN
A-421	RESTROOM ENLARGED RCP
A-500	PARTITION DETAILS

INDEX ELECTRICAL SHEETS

E001	GENERAL NOTES AND ELECTRICAL LEGEND
E100	ELECTRICAL PLANS

INDEX MECHANICAL SHEETS

M-100	MECHANICAL LEGEND AND SPECIFICATIONS
M-101	MECHANICAL SCHEDULES AND DIAGRAMS
M-110	ENLARGED BASEMENT MECHANICAL PLAN
M-111	ENLARGED FIRST LEVEL MECHANICAL PLANS

INDEX PLUMBING SHEETS

P-100	PLUMBING LEGEND AND SPECIFICATIONS
P-101	PLUMBING SCHEDULES AND DIAGRAMS
P-110	ENLARGED BASEMENT PLUMBING PLANS
P-111	ENLARGED FIRST LEVEL PLUMBING PLAN

PROJECT TEAM

ARCHITECT:

Slaterpaul | Hord Coplan Macht
1331 19th St.
Denver, CO. 80202

Ph: 303-607-0977
Fax: 303-607-0767
URL: www.HCM2.com

STRUCTURAL ENGINEER:

JVA CONSULTING ENGINEERS
1319 Spruce Street
Boulder, CO 80302

Ph: 303-444-1951
URL: www.JVAJVA.com

ELECTRICAL ENGINEER:

Corey Electrical Engineering, Inc.
7822 S. Wheeling Court, Suite B
Englewood, CO 80112


Ph: 303-696-1257
Fax: 303-696-1459
URL: www.COREYENG.com

MECHANICAL/PLUMBING ENGINEER:

MEP Engineering, Inc.
6402 S. Troy Circle, Suite 100
Centennial, Colorado 80111

Ph: 303-936-1633
Fax: 303-934-3299
URL: www.MEP-ENG.com

ARCHITECTURAL LEGEND



C:\Revit Local Files\11503_Colorado Springs Auditorium_Central_glee.rvt
10/20/2015 10:50:11 AM

A1 BASEMENT CODE PLAN

1/8" = 1'-0"



SLATERPAULL
hord | coplan | macht

1331 Nineteenth Street
Denver, CO. 80202

P 303.607.0977
www.slaterpaul.com

CONSULTANT:

PROJECT:

CS AUDITORIUM
RESTROOM
RENOVATION

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

COLORADO SPRINGS
CITY AUDITORIUM

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/15 ISSUED FOR BIDDING AND
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 11503.000

DRAWN BY: G Lee

CHECKED BY: J Reske

APPROVED BY: G Petri

SHEET TITLE:

BASEMENT CODE
PLAN

G-100

SHEET OF

C:\Revit Local Files\11503_Colorado Springs Auditorium_Central_glee.rvt
10/20/2015 10:50:15 AM

A1 FIRST FLOOR CODE PLAN

1/8" = 1'-0"



SLATERPAULL
hord | coplan | macht

1331 Nineteenth Street
Denver, CO. 80202

P 303.607.0977
www.slaterpaul.com

CONSULTANT:

PROJECT:

CS AUDITORIUM
RESTROOM
RENOVATION

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

COLORADO SPRINGS
CITY AUDITORIUM

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/15 ISSUED FOR BIDDING AND
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 11503.000

DRAWN BY: G Lee

CHECKED BY: J Reske


APPROVED BY: G Petri

SHEET TITLE:

FIRST FLOOR CODE
PLAN


G-101

SHEET OF



C:\Revit Local Files\11503_Colorado Springs Auditorium_Central_glee.rvt
10/20/2015 10:50:19 AM

A1 SECOND FLOOR CODE PLAN
1/8" = 1'-0"



SLATERPAULL
hord | coplan | macht

1331 Nineteenth Street
Denver, CO. 80202

P 303.607.0977
www.slaterpaul.com

CONSULTANT:

PROJECT:

**CS AUDITORIUM
RESTROOM
RENOVATION**

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

**COLORADO SPRINGS
CITY AUDITORIUM**

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/15 ISSUED FOR BIDDING AND
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 11503.000

DRAWN BY: G Lee

CHECKED BY: J Reske

APPROVED BY: G Petri

SHEET TITLE:

**SECOND FLOOR
CODE PLAN**

G-102

SHEET OF



STRUCTURAL GENERAL NOTES						
DESIGN LOADS: 2011 Pikes Peak Regional Building Code, 2009 International Building Code, 2009 International Existing Building Code, ASCE 7-05						
Risk Category III Substantial Hazard						
Floor Live Loads:						
Occupancy or use	Uniformly distributed (psf)	Concentrated (lbs)	Live Load Reduction			
Public Spaces	100	2,000	Yes*			
First Floor Corridors	100	N/A	Yes			
Restrooms	60	N/A	Yes			
*members supporting 2+ floors						
REINFORCED CONCRETE:						
Design is based on ACI 318 "Building Code Requirements for Reinforced Concrete." Concrete work shall conform to ACI 301 "Standard Specifications for Structural Concrete."						
Structural concrete shall have the following properties:						
Intended Use	f'c, psi	Max W/C Ratio	Maximum Aggregate	Slump, inches	Entrained Air, percent	Cement Type
Structural	3,500	0.50	3/4" Stone	(+/- 1")	(+/- 1.5%)	I
slab on deck						
Detailing, fabrication, and placement of reinforcing steel shall be in accordance with ACI 318 "Details and Detailing of Concrete Reinforcement." Reinforcing bars shall conform to ASTM A615, Grade 60, except ties or bars shown to be field-bent, which shall be Grade 40. Bars to be welded shall conform to ASTM A706. Unless noted otherwise on the Structural Drawings, lap bars 50 diameters (minimum). At corners and intersections, make horizontal bars continuous or provide matching corner bars for each layer of reinforcement. Trim openings in walls and slabs with 2-#5 for each layer of reinforcement, fully developed by extension or hook. Except as noted on the drawings, concrete protection for reinforcement in cast-in-place concrete shall be as follows:						
Cast against and permanently exposed to earth: 3"						
Exposed to earth or weather: 2"						
#6 through #18 bars 1-1/2"						
#5 bar, #31 or #31 wire, and smaller 3/4"						
Not exposed to weather or in contact with ground: 1-1/2"						
Slabs, walls, joists: #11 bars and smaller 1-1/2"						
Beams and columns: 1-1/2"						
Primary reinforcement 1-1/2"						
Stirrups, ties, spirals 1-1/2"						
STRUCTURAL STEEL:						
Structural steel shall be detailed, fabricated, and erected in accordance with the "Specification for Structural Steel Buildings" (AISC 360) and the "Code of Standard Practice for Steel Buildings and Bridges" (AISC 303) by the American Institute of Steel Construction (AISC). Rolled shapes, including plates, channels, WTs, and angles shall conform to ASTM A36-04, 36 ksi yield. Hollow structural section (HSS) rectangular shapes shall conform to ASTM A500-03a, Grade B, 46 ksi yield. Anchor rods shall conform to ASTM F1554-99, Grade 36, 55, and/or 105) as noted on the Structural Drawings with weldability supplement S1. Welding shall be done by a certified welder in accordance with the AISC documents listed above, the American Welding Society (AWS) D1.1: 2006 Structural welding code, and the recommendations for use of weld E70 electrodes. Where not specifically noted, minimum weld shall be 3/16" fillet by length of contact edge. All post-installed anchors shall have current International Code Council Evaluation Service (ICC-ES) reports, shall be installed in accordance with the manufacturer's requirements, and shall be approved for use in cracked concrete. Chemical anchors shall be approved epoxy or similar adhesive type as appropriate for installation in solid and non-solid base materials.						
STEEL DECKING:						
Steel roof, non-composite floor (or "form"), and composite floor deck shall be manufactured and erected in accordance with the standard deck specifications and the "Manual of Construction with Steel Deck" (SDI No. MOC) as prepared by the Steel Deck Institute (SDI). Non-composite and composite floor deck shall be connected to supporting members and interconnected as required to satisfy SDI minimum requirements except as noted on the Structural Drawings. Welding patterns, screw patterns, and details shall be indicated on the deck supplier's shop drawings.						
SHOP DRAWINGS:						
The Structural drawings are copyrighted and shall not be copied for use as erection plans or shop details. Use of JVA's electronic files as the basis for shop drawings requires prior approval by JVA, a signed release of liability by the general Contractor and/or his subcontractors, and deletion of JVA's name and logo from all sheets so used. The General Contractor shall submit in writing any requests to modify the Structural Drawings or Project Specifications. All shop and erection drawings shall be checked and stamped (after having been checked) by the General Contractor prior to submission for Structural Engineer's review; shop drawing submittals not checked by the general Contractor prior to submission to the Structural Engineer will be returned without review. Furnish two (2) prints of shop and erection drawings to the Structural Engineer for review prior to fabrication for reinforcing steel, structural steel, steel deck, concrete mix designs. Submit in a timely manner to permit 10 working days for review by the Structural Engineer. Shop drawings submitted for review do not constitute "request for change in writing" unless specific suggested changes are clearly marked. In any event, changes made by means of the shop drawing submittal process become the responsibility of the one initiating the change.						

FIELD VERIFICATION OF EXISTING CONDITIONS:
The General Contractor shall thoroughly inspect and survey the existing structure to verify conditions that affect the work shown on the drawings or discrepancies to the Architect and Structural Engineer before proceeding.

STRUCTURAL ERECTION AND BRACING REQUIREMENTS:
The Structural Drawings illustrate and describe the completed structure with elements in their final positions, properly supported, connected, and/or braced. The Structural Drawings illustrate typical and representative details to assist the General Contractor. Details shown apply at all similar conditions unless otherwise indicated. Although due diligence has been applied to make the drawings as complete as possible, not every detail is illustrated and not every exceptional condition is addressed. All proprietary connections and elements shall be installed in accordance with the manufacturers' recommendations. All work shall be accomplished in a workmanlike manner and in accordance with the applicable codes and local ordinances. The General Contractor is responsible for coordination of all work, including layout and dimension verification, materials coordination, shop drawing review, and the work of subcontractors. Any discrepancies or omissions discovered in the course of the work shall be immediately reported to the Architect and Structural Engineer for resolution. Continuation of work without notification of discrepancies relieves the Architect and Structural Engineer from all consequences. Unless otherwise specifically indicated, the Structural Drawings do not describe methods of construction. The General Contractor, in the proper sequence, shall perform or supervise all work necessary to achieve the final completed structure, and to protect the structure, workmen, and others during construction. Such work shall include, but not be limited to temporary bracing, shoring for construction equipment, shoring for excavation, formwork, scaffolding, safety devices and programs of all kinds, support and bracing for cranes and other erection equipment. Do not backfill against basement or retaining walls until supporting slabs and floor framing are in place and securely anchored, unless adequate temporary bracing is provided. Temporary bracing shall remain in place until all floors, walls, roofs and any other supporting elements are in place. The Architect and Structural Engineer bear no responsibility for the above items, and observation visits to the site do not in any way include inspections of these items.

LETTERS OF CONSTRUCTION COMPLIANCE:
The General Contractor shall determine from the local building authority, at the time the building permit is obtained, whether any letters of construction compliance will be requested from the Structural Engineer. The Contractor shall notify the Structural Engineer of all such requirements in writing prior to the start of construction. Two day advance notice shall be given when requesting site visits necessary as the basis for the compliance letter. The General Contractor shall provide copies of all third-party testing and inspection reports to the Architect and Structural Engineer a minimum of one week prior to the date that the compliance letter is needed.

SPECIAL INSPECTIONS:
The following Special Inspections and Testing shall be performed by a qualified Special Inspector, retained by the Owner, in accordance with the following sections of IBC Chapter 17:
Section 1704 Special Inspections and the following sub-sections:
1704.3 Steel construction including 1704.3.1 welding, 1704.3.2 details, 1704.4 Concrete construction
The Special Inspector shall be a qualified person who shall demonstrate competence, to the satisfaction of the building official, for inspection of the particular type of construction or operation requiring special inspection. The approved inspector must be independent from the contractor responsible for the work being inspected. Duties and responsibilities of the special inspector shall be to inspect and/or test the work outlined above and within the Statement of Special Inspections in accordance with chapter 17 of the IBC for conformance with the approved construction documents. All discrepancies shall be brought to the immediate attention of the contractor for correction. Per section 1704.1.2 the special inspector shall furnish regular reports to the building official and the Structural Engineer. Progress reports for continuous inspection shall be furnished weekly. Individual reports of periodic inspections shall be furnished within one week of inspection dates. The reports shall note uncorrected deficiencies, correction of previously reported deficiencies, and changes to the approved construction documents authorized by the Structural Engineer of Record. The special inspector shall submit a final signed report within 10 days of the final special inspection stating whether the work requiring special inspection was, to the best of the inspector's knowledge, in conformance with the approved construction documents and the applicable workmanship provisions of the IBC. Work not in compliance shall be noted in the report. The Contractor shall submit a written statement of responsibility to the Building Official and the Owner prior to the commencement of work on a main wind- or seismic-force-resisting system per section 1709. The statement shall acknowledge the awareness of the special listed requirements of designated seismic system or a wind- or seismic-resisting component in the Statement of Special Inspections per section 1705. Except as noted, the special inspections outlined above are in addition to, and beyond the scope of, periodic structural observations as defined in section 1710. Structural observations are included in the structural engineering design and construction administration services provided by the Structural Engineer.



- (E) INDICATES EXISTING
- (N) INDICATES NEW
- CONTRACTOR SHALL FIELD VERIFY ALL (E) DIMENSIONS AND CONDITIONS PRIOR TO START OF CONSTRUCTION. NOTIFY A/E OF ANY DISCREPANCIES BEFORE PROCEEDING WITH NEW WORK.
- SEE SECTION 4/A-410 FOR STEEL LOOSE LINTELS OVER LOUVER OPENINGS IN EXTERIOR WALL.


STRUCTURAL DRAWING LIST	
S001	GENERAL NOTES AND PARTIAL PLAN
S100	SECTIONS

SLATERPAULL
hord | coplan | macht

1331 Nineteenth Street
Denver, CO. 80202

P 303.607.0977
www.slaterpaul.com

CONSULTANT:



JVA, Incorporated 1319 Spruce Street
Boulder, CO 80302 Phone: 303.444.1951
Fax: 303.444.1957 E-mail: info@jvaja.com
JVA Project # 17727

PROJECT:

CS AUDITORIUM
RESTROOM
RENOVATION

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

COLORADO SPRINGS
CITY AUDITORIUM

ISSUE:

10/16/15 ISSUE FOR BIDDING AND
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 11503.000

DRAWN BY: EWH

CHECKED BY: IRG

APPROVED BY: AJT


SHEET TITLE:

GENERAL NOTES AND
PARTIAL PLAN


S001

SHEET OF

C:\Revit Local Files\11503_Colorado Springs Auditorium_Central_glee.rvt
10/20/2015 10:50:09 AM



A2 ENLARGED RESTROOM DEMO RCP
1/4" = 1'-0"



A4 ENLARGED RESTROOM DEMO PLAN
1/4" = 1'-0"

CONSTRUCTION ENLARGED PLAN GENERAL NOTES

1. GENERAL CONTRACTOR TO COORDINATE SCHEDULING ALL WORK WITH OWNER.
2. GENERAL CONTRACTOR TO VERIFY IN FIELD ALL DIMENSIONS AND EXISTING DIMENSIONS PRIOR TO COMMENCEMENT OF WORK. NOTIFY ARCHITECT IF DISCREPANCIES OCCUR.
3. PROTECT ALL EXISTING TO REMAIN FROM DAMAGE DURING DEMOLITION AND CONSTRUCTION.
4. GENERAL CONTRACTOR TO LIMIT STORAGE AND ASSEMBLY OF MATERIALS TO THE STAGING AREA.
5. DO NOT SCALE DRAWINGS; NOTIFY ARCHITECT IF CRITICAL DIMENSIONS DO NOT APPEAR ON THE DRAWINGS.
6. NOT ALL KEY NOTES ARE USED ON ALL SHEETS.

SHEET NOTES - DEMOLITION PLANS

1. REMOVE EXISTING INTERIOR PARTITION WALL
2. REMOVE EXISTING DOOR AND FRAME
3. REMOVE EXISTING WATER CLOSET AND CAP PLUMBING
4. REMOVE EXISTING WALL MOUNTED URINAL AND CAP PLUMBING
5. REMOVE EXISTING RESTROOM PARTITION
6. REMOVE EXISTING LAVATORY SINK AND FAUCETS
7. REMOVE EXISTING COUNTEROP
8. REMOVE EXISTING WALL MOUNTED MIRROR
9. REMOVE EXISTING WALL MOUNTED SOAP DISPENSERS, HAND DRYERS AND PAPER TOWEL DISPENSERS
10. REMOVE EXISTING OPERABLE PANEL
11. REMOVE EXISTING SHELVING IN STORAGE ROOM
12. REMOVE EXISTING 2"x2" TILE FLOORING
13. REMOVE EXISTING 6"x6" TILE FLOORING
14. EXISTING RADIATOR TO REMAIN
15. RCP - REMOVE EXISTING 2X4 LAY-IN GRID CEILING INCLUDING ALL MOUNTING HARDWARE. TAKE CARE TO MINIMIZE DAMAGE TO EXISTING PLASTER WALLS AND CEILINGS.
16. RCP - COORDINATE THE REMOVAL OF EXISTING ELECTRICAL FIXTURES WITH ELECTRICAL PLANS

SLATERPAULL
hord | coplan | macht

1331 Nineteenth Street
Denver, CO. 80202

P 303.607.0977
www.slaterpaul.com

CONSULTANT:

PROJECT:

CS AUDITORIUM RESTROOM RENOVATION

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

COLORADO SPRINGS CITY AUDITORIUM

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/15 ISSUED FOR BIDDING AND
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 11503.000

DRAWN BY: G Lee

CHECKED BY: J Reske

APPROVED BY: G Petri


SHEET TITLE:

ENLARGED RESTROOM DEMO PLAN & RCP

AD410

SHEET OF

C:\Revit Local Files\11503_Colorado Springs Auditorium_Central_glee.rvt
10/20/2015 10:49:43 AM



A1 BASEMENT FLOOR PLAN
1/8" = 1'-0"



SLATERPAULL
hord | coplan | macht

1331 Nineteenth Street
Denver, CO. 80202

P 303.607.0977
www.slaterpaul.com

CONSULTANT:

PROJECT:

**CS AUDITORIUM
RESTROOM
RENOVATION**

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

**COLORADO SPRINGS
CITY AUDITORIUM**

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/15 ISSUED FOR BIDDING AND
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 11503.000

DRAWN BY: G Lee

CHECKED BY: J Reske

APPROVED BY: G Petri

SHEET TITLE:

**BASEMENT FLOOR
PLAN (FOR
REFERENCE ONLY)**

A-110

SHEET OF

C:\Revit Local Files\11503_Colorado Springs Auditorium_Central_glee.rvt
10/20/2015 10:49:47 AM

A1 FIRST FLOOR PLAN

1/8" = 1'-0"



SLATERPAULL

hord | coplan | macht

1331 Nineteenth Street
Denver, CO. 80202

P 303.607.0977

www.slaterpaul.com

CONSULTANT:

PROJECT:

**CS AUDITORIUM
RESTROOM
RENOVATION**

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

**COLORADO SPRINGS
CITY AUDITORIUM**

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/15 ISSUED FOR BIDDING AND
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 11503.000

DRAWN BY: G Lee

CHECKED BY: J Reske

APPROVED BY: G Petri

SHEET TITLE:

FIRST FLOOR PLAN


A-111

SHEET OF

C:\Revit Local Files\11503_Colorado Springs Auditorium_Central_glee.rvt
10/20/2015 10:49:51 AM

A1 SECOND FLOOR PLAN

1/8" = 1'-0"



SLATERPAULL
hord | coplan | macht

1331 Nineteenth Street
Denver, CO. 80202

P 303.607.0977
www.slaterpaul.com

CONSULTANT:

PROJECT:

CS AUDITORIUM
RESTROOM
RENOVATION

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

COLORADO SPRINGS
CITY AUDITORIUM

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/15 ISSUED FOR BIDDING AND
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 11503.000

DRAWN BY: G Lee

CHECKED BY: J Reske

APPROVED BY: G Petri

SHEET TITLE:


SECOND FLOOR PLAN
(FOR REFERENCE
ONLY)

A-112

SHEET OF


TYPICAL ADULT MOUNTING HEIGHTS

WATER CLOSET



RE: ENLARGED PLAN FOR HORIZONTAL PLACEMENT.

URINAL




RE: ENLARGED PLAN FOR HORIZONTAL PLACEMENT.

TOILET PAPER DISPENSER

102800.A03

SANITARY NAPKIN DISPOSAL


102800.H03



SURFACE MOUNT TOILET TISSUE DISPENSER 7" MIN. TO 9" MAX IN FRONT OF WC MEASURED TO THE CENTER LINE OF THE DISPENSER.

42" HORIZONTAL GRAB BAR

18" VERTICAL GRAB BAR




SIDE WALL: 42" MIN. LENGTH, MOUNT 12" MAX. FROM REAR WALL.

18" MIN. VERTICAL BAR: MOUNT 40" FROM REAR WALL AND 40" (FROM BOTTOM OF BAR) A.F.F.

ELECTRIC HAND DRYER


102800.P01



MOUNT 48" TO OPERATING MECHANISM FOR FRONT APPROACH.

SOAP DISPENSER


102800.F01



MOUNT 44" MAX TO OPERATING MECHANISM FOR FRONT APPROACH.


SANITARY NAPKIN DISPENSER

102800.H02



MOUNT 48" TO OPERATING MECHANISM FOR FRONT APPROACH.

36" HORIZ. GRAB BAR



REAR WALL: 36" MIN. LENGTH, EXTEND FROM CENTER LINE OF WC 12" MIN. ON SIDE CLOSEST TO WALL & 24" MIN. ON TRANSFER SIDE.

RESTROOM FINISH LEGEND

TILE


T1	PORCELAIN FLOOR TILE MANU: CONCEPT SURFACES PROD: MAXXI COLOR: FIVE SIZE: 12" X 24"	T3	ACCENT GLAZED WALL TILE MANU: EMSE PROD: VOGUE COLOR: GRAY, MATTE SIZE: 4" X 16"
T2	O.A. GLAZED WALL TILE MANU: EMSE PROD: VOGUE COLOR: WHITE, MATTE SIZE: 4" X 16"	T4	GLASS MOSAIC TILE MANU: CAPCO PROD: BLISS LINEAR BLEND COLOR: WATERFALL SIZE: 12" X 12" SHEETS

PAINT

PT1	WALL COLOR MANU: SHERWIN WILLIAMS COLOR: 7016 MINDFUL GRAY SHEEN: EGGSHELL	PT2	O.A. CEILING COLOR MANU: TO MATCH (E) COLOR: TO MATCH (E) SHEEN: FLAT
-----	---	-----	--


PLASTIC PLAMINATE

PL1	APRON @ SINK MANU: FORMICA PATTERN: 8829-58 GRAPHITE TWILL FINISH: MATTE	SS1	QUARTZ COUTNERTOP MANU: CAMBRIA PRODUCT: DURIHAM THICK: 3CM
-----	---	-----	--




D3 MENS WEST ELEVATION

1/4" = 1'-0"




D4 MENS NORTH ELEVATION

1/4" = 1'-0"




C3 MENS EAST ELEVATIONS

1/4" = 1'-0"



C4 MENS SOUTH ELEVATION

1/4" = 1'-0"



C6 SECTION @ VANITY

3/4" = 1'-0"

RESTROOM GENERAL NOTES

- ALL 'HOLD' AND 'MIN' DIMENSIONS TAKE PRECEDENT OVER OTHER DIMENSIONS. IF THERE IS A DESCREFENCY, NOTIFY THE ARCHITECT.
- INTERIOR WALL PARTITION DIMENSIONS SHOWN ARE TO FACE OF FINISHED MATERIAL U.N.O.
- ALL FLOOR MATERIALS TO BE BUTT JOINED AT TRANSITIONS ON CENTER OF DOOR WHERE APPLICABLE.
- PROVIDE SCHLUTER SYSTEMS EDGE PROTECTION AND TRANSITION PROFILES AT ALL OUTSIDE CORNERS, AND WHERE MATERIAL CHANGES AND/OR STOPS.
- PAINT ALL EXPOSED PIPES, AIR GRILLES, ETC. TO MATCH ADJACENT WALL COLOR
- ALL WALL MOUNTED CASEWORK, MILLWORK, HARDWARE, EQUIPMENT, ETC. SHALL BE ANCHORED TO METAL STRAPPING OR 3/4" FRT PLYWOOD BACKING BETWEEN STUDS, U.N.O. COORDINATE ACCORDINGLY.
- ALL TILE TYPES AND PAINT COLORS TO WRAP AROUND OUTSIDE CORNERS AND TERMINATE AT INSIDE CORNERS, TYP.

SLATERPAULL
hord | coplan | mach

1331 Nineteenth Street
Denver, CO. 80202

P 303.607.0977

www.slaterpaul.com

CONSULTANT:

PROJECT:

CS AUDITORIUM
RESTROOM
RENOVATION

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

COLORADO SPRINGS
CITY AUDITORIUM

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/15 ISSUED FOR BIDDING AND
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 11503.000

DRAWN BY: K Myron-Karels

CHECKED BY: J Reske

APPROVED BY: G Petri

SHEET TITLE:

RESTROOM FINISH
PLAN

A-411

SHEET OF


C:\Revit Local Files\11503_Colorado Springs Auditorium_Central_glee.rvt
10/20/2015 10:50:08 AM

REFLECTED CEILING PLAN
GENERAL NOTES

1. GENERAL CONTRACTOR TO COORDINATE SCHEDULING ALL WORK WITH OWNER.
2. GENERAL CONTRACTOR TO VERIFY IN FIELD ALL DIMENSIONS AND EXISTING DIMENSIONS PRIOR TO COMMENCEMENT OF WORK. NOTIFY ARCHITECT IF DISCREPANCIES OCCUR.
3. PROTECT ALL EXISTING TO REMAIN FROM DAMAGE DURING DEMOLITION AND CONSTRUCTION.
5. DO NOT SCALE DRAWINGS; NOTIFY ARCHITECT IF CRITICAL DIMENSIONS DO NOT APPEAR ON THE DRAWINGS.
6. NOT ALL KEY NOTES ARE USED ON ALL SHEETS.

ENLARGED RCP KEYNOTES

1. PATCH PAINT PLASTER CEILING WHERE PREVIOUS PARTITION WAS REMOVED.
2. PATCH AREAS IN (E) PLASTER CEILING WHERE PREVIOUS MECHANICAL, ELECTRICAL AND CEILING FIXTURES WERE ATTACHED TO THE PLASTER.



A4 RESTROOM ENLARGEMENT RCP
1/4" = 1'-0"



SLATERPAULL
hord | coplan | macht

1331 Nineteenth Street
Denver, CO. 80202

P 303.607.0977
www.slaterpaul.com

CONSULTANT:

PROJECT:

CS AUDITORIUM
RESTROOM
RENOVATION

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

COLORADO SPRINGS
CITY AUDITORIUM

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/15 ISSUED FOR BIDDING AND
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 11503.000

DRAWN BY: G Lee

CHECKED BY: J Reske

APPROVED BY: G Petri

SHEET TITLE:


RESTROOM
ENLARGED RCP

A-421

SHEET OF



C:\Revit Local Files\11503_Colorado Springs Auditorium_Central_glee.rvt
10/20/2015 10:50:09 AM

PARTITION TYPES LEGEND






PARTITION TYPES NOTES

- PARTITION TYPES ARE INDICATED ON THE FLOOR PLANS.
- ALL PARTITIONS SHALL EXTEND STRUCTURE TO STRUCTURE UNLESS NOTED OTHERWISE.
- PROVIDE FIRE-RETARDANT TREATED WOOD BLOCKING FOR PARTITION MOUNTED EQUIPMENT AND CASEWORK.
- PARTITION TYPES DESCRIBE THE PRIMARY MEMBER AND SHEATHING. REFER TO FINISH SCHEDULE FOR ALL PARTITION FINISH DESIGNATIONS.
- PROVIDE TYPE 'WR' WATER RESISTANT GYP. BD. IN ALL WET AREAS SUCH AS TOILET, LOCKER, AND SHOWER ROOMS. PROVIDE 5/8" CONCRETE BACKER BOARD AT ALL CERAMIC TILE FINISHES TO ALIGN WITH 5/8" TYPE 'WR' GYP. BD. ABOVE.
- PROVIDE SLIP JOINT CONNECTIONS AT THE TOPS OF ALL PARTITIONS WHICH INTERSECT THE STRUCTURE ABOVE.



PLAN DETAIL @ PARTITION INTERSECTION



CONSULTANT:

PROJECT:

CS AUDITORIUM
RESTROOM
RENOVATION

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

COLORADO SPRINGS
CITY AUDITORIUM

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/15 ISSUED FOR BIDDING AND
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 11503.000

DRAWN BY: G Lee

CHECKED BY: J Reske

APPROVED BY: G Petri

SHEET TITLE:

PARTITION DETAILS

ELECTRICAL GENERAL NOTES - APPLICABLE TO ALL ELECTRICAL SHEETS

1. PRIOR TO SUBMITTING BIDS THE ELECTRICAL CONTRACTOR SHALL VISIT THE SITE TO VERIFY EXISTING ELECTRICAL EQUIPMENT CONDITIONS AND DIFFICULTIES THAT WILL AFFECT EXECUTION OF THE WORK. FIELD VERIFY QUANTITIES OF EXISTING LIGHT FIXTURES, ELECTRICAL DEVICES, COMMUNICATION DEVICES, FIBER-OPTIC DEVICES, AND ELECTRICAL EQUIPMENT. NOTIFY THE ARCHITECT AND ENGINEER OF ANY EXISTING CONDITIONS WHICH MODIFY THE SCOPE OF WORK AS SHOWN ON THE CONSTRUCTION DOCUMENTS. SUBMISSION OF A BID PROPOSAL WILL BE CONSTRUED AS EVIDENCE THAT SUCH AN EXAMINATION HAS BEEN MADE AND LATER CLAIMS FOR MOBILIZATION, LABOR, EQUIPMENT, AND/OR MATERIALS REQUIRED BECAUSE OF DIFFICULTIES ENCOUNTERED WILL NOT BE RECOGNIZED.
2. THE ELECTRICAL CONTRACTOR SHALL EXAMINE THE DRAWINGS OF ALL TRADES WHOSE WORK RELATES TO OR IS DEPENDENT ON ELECTRICAL WORK TO BECOME FULLY INFORMED OF THE EXTENT AND CHARACTER OF THEIR SPECIFIED WORK AND BE ABLE TO COORDINATE IT WHILE AVOIDING POSSIBLE INTERFERENCE WITH THE ELECTRICAL WORK.
3. IT IS THE INTENTION OF THESE SPECIFICATIONS AND DRAWINGS TO CALL FOR FINISHED WORK, TESTED AND READY FOR OPERATION. WHEREVER THE WORD "PROVIDE" IS USED, IT SHALL MEAN "FURNISH AND INSTALL COMPLETE AND READY FOR USE." "REPLACE" SHALL MEAN TO PUT NEW IN PLACE OF EXISTING. THE ARCHITECTURAL GENERAL AND SPECIAL CONDITIONS FOR THE WORK OF THIS PROJECT AND BASE BUILDING SPECIFICATIONS SHALL BE PART OF THE ELECTRICAL SPECIFICATIONS. THE ELECTRICAL CONTRACTOR SHALL EXAMINE THE GENERAL AND SPECIAL CONDITIONS BEFORE SUBMITTING A BID.
4. ALONGSIDE SUBMISSION OF THE BID, THE ELECTRICAL CONTRACTOR SHALL GIVE WRITTEN NOTICE TO THE ARCHITECT/ENGINEER OF ANY NECESSARY ITEMS OR WORK THAT HAVE BEEN OMITTED FROM THE DRAWINGS OR SPECIFICATIONS. IN THE ABSENCE OF SUCH WRITTEN NOTICE, IT IS THE INTENTION OF THESE SPECIFICATIONS THAT THE CONTRACTOR HAS INCLUDED THE COST OF ALL REQUIRED ITEMS IN HIS BID, AND THAT THE ELECTRICAL CONTRACTOR WILL BE RESPONSIBLE FOR THE APPROVED SATISFACTORY FUNCTIONING OF THE ENTIRE SYSTEM WITHOUT EXTRA COMPENSATION.
5. THE CONTRACTOR IS RESPONSIBLE FOR THE COMPLETE AND SATISFACTORY ELECTRICAL INSTALLATION IN ACCORDANCE WITH THE TRUE INTENT OF THE DRAWINGS AND SPECIFICATIONS. HE SHALL PROVIDE, WITHOUT EXTRA CHARGE, ALL INCIDENTAL ITEMS REQUIRED AS A PART OF THIS ELECTRICAL INSTALLATION. THE INSTALLATION SHALL BE SO MADE THAT ITS SEVERAL COMPONENT PARTS WILL FUNCTION TOGETHER AS A WORKABLE SYSTEM AND SHALL BE LEFT WITH ALL PARTS ADJUSTED AND IN WORKING ORDER.
6. ELECTRICAL CONTRACTOR SHALL OBTAIN AND PAY FOR ALL LOCAL FEES, PERMITS, AND SERVICES OF INSPECTION AUTHORITIES REQUIRED BY ELECTRICAL WORK FOR THIS ELECTRICAL CONSTRUCTION. FILE ALL NECESSARY PLANS, PREPARE ALL DOCUMENTS, AND OBTAIN ALL NECESSARY APPROVALS REQUIRED BY ALL GOVERNMENTAL DEPARTMENTS HAVING JURISDICTION. ALL WORK PERFORMED UNDER THIS CONTRACT SHALL REMAIN EXPOSED TO VIEW UNTIL APPROVED BY THE INSPECTION AUTHORITY.
7. ELECTRICAL CONTRACTOR SHALL FULLY COORDINATE WITH OWNER REPRESENTATIVES. ALL ELECTRICAL WORK PERFORMED UNDER THIS CONTRACT SHALL CONFORM WITH LATEST EDITIONS OF THE NATIONAL ELECTRICAL CODE, INTERNATIONAL BUILDING CODE, LOCAL BUILDING AND FIRE DEPARTMENT REQUIREMENTS. PERFORM WORK IN ACCORDANCE WITH REQUIREMENTS OF OWNER REPRESENTATIVE.
8. ELECTRICAL CONTRACTOR SHALL NOTIFY THE ARCHITECT AND ENGINEER OF ANY CHANGES REQUIRED BY THE BUILDING MANAGEMENT AND TENANT REPRESENTATIVES.
9. BEFORE STARTING WORK, ELECTRICAL CONTRACTOR SHALL PREPARE AND SUBMIT TO THE ARCHITECT/ENGINEER FIVE (5) SETS OF SHOP DRAWINGS, BROCHURES, INSTALLATION INSTRUCTIONS, AND DESCRIPTIVE EQUIPMENT DATA RELATED TO SPECIFIED EQUIPMENT, WIRING DEVICES, AND ACCESSORIES FOR APPROVAL. ELECTRONIC SUBMITTALS (PDF OR SIMILAR) ARE ACCEPTABLE WITH PRIOR APPROVAL FROM THE ARCHITECT. THE CONTRACTOR SHALL IDENTIFY ANY "LONG LEAD TIME" ITEMS WHICH MAY IMPACT THE OVERALL PROJECT SCHEDULE. ALL BIDS SHALL INCLUDE COSTS ASSOCIATED WITH THE PURCHASE AND DELIVERY OF EQUIPMENT TO MEET THE PROJECT SCHEDULE. NO EQUIPMENT SHALL BE ORDERED, PURCHASED, OR INSTALLED PRIOR TO THE APPROVAL OF SHOP DRAWINGS, BROCHURES, INSTALLATION INSTRUCTIONS, AND SCHEDULES. APPROVAL BY THE ARCHITECT/ENGINEER IS INTENDED TO ESTABLISH CONFORMANCE WITH THE PROJECT DESIGN CONCEPT AND THE REQUIREMENTS OF THE DRAWINGS AND SPECIFICATIONS.
10. THE NAMING OF THE MANUFACTURER OR BRAND WITH CATALOG NUMBER OR OTHER PRODUCT IDENTIFICATION WITHOUT THE WORDS "OR EQUAL" IN THE SPECIFICATIONS OR NOTES SHALL INDICATE THAT IT IS THE ONLY PRODUCT APPROVED FOR PURCHASE. IF THE WORDS "OR EQUAL" ARE USED THEY SHALL BE INTERPRETED AS ESTABLISHING A QUALITY OR PERFORMANCE STANDARD FOR THE MATERIAL OR PRODUCT TO BE PURCHASED. THIS SHALL INDICATE THAT THE ELECTRICAL CONTRACTOR IS NOT RESTRICTED TO THE USE OF THE NAMED AND IDENTIFIED PRODUCT IF A SUBSTITUTE APPROVED BY THE ARCHITECT/ENGINEER IS AVAILABLE. HOWEVER, WHERE A SUBSTITUTION IS REQUESTED, IT WILL BE PERMITTED ONLY WITH THE WRITTEN APPROVAL OF THE ARCHITECT/ENGINEER. NO SUBSTITUTE MATERIAL OR EQUIPMENT SHALL BE ORDERED, FABRICATED, OR PROCESSED IN ANY MANNER PRIOR TO THE APPROVAL OF THE ARCHITECT/ENGINEER. THE ELECTRICAL CONTRACTOR SHALL ASSUME ALL RESPONSIBILITY FOR ADDITIONAL EXPENSES AS REQUIRED MAKING CHANGES FROM THE ORIGINAL MATERIAL OR PRODUCT SPECIFIED.
11. THE ELECTRICAL DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL ARRANGEMENT OF ELECTRICAL WORK. LOCATIONS ARE APPROXIMATE AND SHALL BE SUBJECT TO MINOR MODIFICATIONS AS DIRECTED BY THE GENERAL CONTRACTOR AND/OR OWNER REPRESENTATIVES. ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE EXACT FITTING OF ALL MATERIALS, EQUIPMENT, ETC., IN THE BUILDING AND TENANT SPACE. ALL DIMENSIONS SHALL BE VERIFIED ON THE JOB.
12. DRAWINGS SHALL NOT BE SCALED FOR ROUGH-IN MEASUREMENTS OR USED AS SHOP DRAWINGS, WHERE DIMENSIONS ARE SHOWN ON PLANS OR DETAILS. THESE DIMENSIONS ARE TO BE FIELD-VERIFIED BY THE ELECTRICAL CONTRACTOR AGAINST EXISTING FIELD CONDITIONS, INSTALLATION REQUIREMENTS OF OTHER TRADES, AND THE MANUFACTURER'S SUBMITTALS FOR EQUIPMENT TO BE INSTALLED. SHOULD ANY CONFLICTS ARISE WHICH CANNOT BE EASILY RESOLVED IN THE FIELD WITHOUT CHANGING THE DESIGN INTENT, THE ELECTRICAL CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY.
13. WHILE ALL WORK IS IN PROGRESS, EXCEPT FOR SHORT DESIGNATED INTERVALS DURING WHICH CONNECTIONS ARE TO BE MADE, CONTINUITY OF SERVICE TO ALL EXISTING SYSTEMS SERVING OCCUPIED SPACES SHALL BE MAINTAINED. THE CONTRACTOR SHALL COORDINATE AND COOPERATE WITH OWNER AT ALL TIMES FOR ALL NEW-TO-EXISTING CONNECTIONS, SYSTEM SHUTDOWNS, AND RESTART-UP.
14. ANY WORK WHICH WILL AFFECT THE BUILDING OCCUPANTS, INCLUDING, BUT NOT LIMITED TO WORK WHICH GENERATES EXCESSIVE NOISE, DUST, SMOKE, OR INCONVENIENCE TO BUILDING OCCUPANTS, SHALL BE PERFORMED AFTER BUSINESS HOURS. UNLESS PRIOR APPROVAL HAS BEEN OBTAINED FROM THE BUILDING MANAGER OR OWNER.
15. ELECTRICAL ITEMS AFFECTED BY REMODEL WORK ARE SHOWN ON DRAWINGS ALONG WITH EXISTING ELECTRICAL INSTALLATION SHOWN WITH LIGHT LINE WEIGHT. EXISTING ELECTRICAL INSTALLATION SHOWN IS NOT NECESSARILY ALL-INCLUSIVE. RETAIN CIRCUIT CONTINUITY FOR EXISTING ELECTRICAL EQUIPMENT, FIXTURES, AND DEVICES THAT ARE TO REMAIN. SUCH EQUIPMENT SHALL BE RECONNECTED TO EXISTING CIRCUITS OR CONNECTED TO NEW CIRCUIT(S) AS INDICATED ON DRAWINGS. ENSURE ALL ELECTRICAL DEVICES IN WORK AREA ARE FULLY FUNCTIONAL. FOR DEVICES OR JUNCTION BOXES LOCATED IN WALLS, THAT MUST REMAIN IN PLACE FOR CIRCUIT CONTINUITY, PROVIDE BLANK COVER PLATES TO MATCH WALL PLATES STYLE IN THE AREA OF WORK. FOR ALL OTHER UNUSED JUNCTION BOXES, REMOVE WIRING AND PROVIDE BLANK COVER PLATE, OR COORDINATE WITH GENERAL CONTRACTOR FOR PATCHING OF WALL TO MATCH ADJACENT SURFACE AS DIRECTED BY ARCHITECT. WHERE EXISTING DEVICES CONFLICT WITH NEW WALL CONSTRUCTION, RELOCATE EXISTING DEVICE AND REWORK CIRCUITRY AS REQUIRED TO MAINTAIN CIRCUIT CONTINUITY. DEVICES MAY ONLY BE REMOVED WITH PRIOR APPROVAL FROM THE DESIGN TEAM AND BUILDING MANAGEMENT. COORDINATE FINAL DIRECTIONS WITH ARCHITECT PRIOR TO DEMOLITION.
16. REPORT ANY EXISTING DAMAGED EQUIPMENT OR SYSTEMS TO THE OWNER PRIOR TO BEGINNING THE PROJECT.
17. BEFORE ANY EQUIPMENT IS INSTALLED, DETERMINE THAT SAID EQUIPMENT WILL PROPERLY FIT WITHIN THE SPACE ALLOCATED. INSTALL ALL EQUIPMENT AND MATERIALS IN SUCH A MANNER AS TO PROVIDE REQUIRED ACCESS FOR SERVICING AND MAINTENANCE. ALLOW AMPLE SPACE FOR REMOVAL OF ALL PARTS THAT REQUIRE REPLACEMENT OR SERVICING.
18. MINIMUM WORKING CLEARANCES PER THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE SHALL BE PROVIDED AROUND AND IN FRONT OF ALL ELECTRICAL EQUIPMENT.
19. ALL CIRCUIT BREAKER LUGS SHALL BE RATED FOR A MINIMUM OF 75 DEGREES CELSIUS.
20. ALL MATERIALS AND EQUIPMENT SHALL BE NEW, UNDAMAGED, BEAR THE UL LABEL WHERE

- APPLICABLE, AND BE AS SPECIFIED FOR USE IN EACH SPECIFIC LOCATION. ANY INCIDENTAL ACCESSORIES NECESSARY TO COMPLETE THE WORK IN ALL RESPECTS AND MAKE IT READY FOR OPERATION, EVEN IF NOT SPECIFICALLY SPECIFIED, SHALL BE FURNISHED, DELIVERED, AND INSTALLED BY THE ELECTRICAL CONTRACTOR WITHOUT ADDITIONAL EXPENSE TO THE CLIENT.
21. MINOR DETAILS NOT USUALLY SHOWN OR SPECIFIED, BUT NECESSARY FOR THE PROPER INSTALLATION AND OPERATION OF A SYSTEM OR EQUIPMENT, SHALL BE INCLUDED IN THE ELECTRICAL CONTRACTOR'S ESTIMATE, AS IF SPECIFIED HEREIN OR SHOWN.
22. ALL NEW, RELOCATED AND EXISTING MATERIALS, IN CEILING PLENUMS NOT ENCLOSED IN CONDUIT SHALL HAVE CLASS, FLAME SPREAD AND SMOKE DEVELOPMENT RATINGS AS REQUIRED FOR USE IN OPEN PLENUMS. REMOVE AND REPLACE ALL EXISTING MATERIALS IN WORK AREA NOT IN COMPLIANCE.
23. COORDINATE THE INSTALLATION OF ELECTRICAL MATERIALS AND EQUIPMENT ABOVE AND BELOW CEILINGS WITH SUSPENSION SYSTEM, MECHANICAL EQUIPMENT, AND OTHER BUILDING COMPONENTS. ALL COMPONENTS SHALL BE LOCATED AS TIGHT TO STRUCTURE AS POSSIBLE. COORDINATE CEILING CAVITY SPACE CAREFULLY WITH ALL TRADES.
24. NEUTRALS, RACEWAYS, AND NON-CURRENT CARRYING PARTS OF ELECTRICAL EQUIPMENT AND ASSOCIATED ENCLOSURES SHALL BE GROUNDED IN FULL ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE. PROVIDE HARD WIRE GROUND CONNECTIONS TO ALL DEVICES AND SEPARATE CONTINUING WIRE IN EACH CIRCUIT (#12 CU MINIMUM "GREEN" TRACER GROUND). COORDINATE EQUIPMENT GROUNDING CONDUCTOR WIRE SIZE WITH MANUFACTURER REQUIREMENTS.
25. CONDUIT JOINTS SHALL BE CUT SQUARE, THREADED, REAMED SMOOTH, AND DRAWN UP TIGHT. BENDS OR OFFSETS SHALL BE MADE WITH AN APPROVED BENDER OR HICKEY, OR HUB-TYPE CONDUIT FITTINGS. THE NUMBER OF BENDS PER RUN SHALL CONFORM TO THOSE STATED IN CURRENT NEC.
26. WHERE POSSIBLE ALL WIRING SHALL BE RUN CONCEALED. ALL HOME RUNS SHALL BE EMT, CONCEALED CONDUIT SYSTEMS SHALL BE RUN IN A DIRECT LINE WITH LONG SWEEP BENDS AND AN OFFSETS. EXPOSED CONDUIT RUNS SHALL BE PARALLEL TO, AND AT RIGHT ANGLES TO BUILDING LINES, USING CONDUIT FITTINGS FOR ALL TURNS AND OFFSETS. ALL EMPTY CONDUITS SHALL BE SUPPLIED WITH PULL WIRES AND BUSHINGS.
27. "MC" AND "AC" TYPE CABLE WITH INTERNAL GROUND WIRES SHALL BE PERMITTED FOR BRANCH CIRCUIT WIRING WHERE APPROVED IN WRITING BY BUILDING MANAGEMENT AND THE LOCAL AHJ ONLY AND INSTALLED PER NATIONAL ELECTRICAL CODE AND LOCAL BUILDING DEPARTMENT REQUIREMENTS. USE LISTED AND APPROVED TYPE COUPLINGS AND CONNECTORS. PROVIDE CONDUIT SUPPORTS AS REQUIRED BY THE NATIONAL ELECTRICAL CODE AS A MINIMUM.
28. ELECTRICAL CONTRACTOR SHALL FURNISH AND INSTALL JUNCTION AND PULL BOXES TO PROVIDE ACCESS POINTS FOR PULING AND FOR CONDUCTORS INTO A RACEWAY SYSTEM. JUNCTION AND PULL BOXES AND THEIR COVERS SHALL BE FORMED FROM SHEET STEEL AND SHALL BE FINISHED IN GRAY ENAMEL PAINT. BOXES SHALL BE IN INDUSTRY STANDARD SIZES. OUTLET BOXES WITH THE CORRECT FITTING FOR THE APPLICATION SHALL BE LOCATED AT EACH CONDUIT TRIP POINT, AT EACH OUTLET, SWITCH POINT, OR JUNCTION POINT, AND AT EACH PULL POINT FOR THE CONNECTION OF CONDUIT AND OTHER RACEWAYS. OUTLET BOXES FOR CONCEALED WIRING SHALL BE MADE FROM GALVANIZED OR CADMIUM-PLATED SHEET STEEL, AND THEY SHALL HAVE A DEPTH OF AT LEAST 1.5 INCHES, WHETHER SINGLE OR DOUBLED. THE BOXES SHALL BE LARGE ENOUGH SIZE TO ACCOMMODATE THE NUMBER OF WIRING DEVICES AND CONDUCTORS AS SPECIFIED IN THE FILL SCHEDULE OF THE CURRENT NEC. SECURE BOXES WITH MOUNTING BRACKET, BRACES, HANGER OR BOX MOUNTING SUPPORT.
29. ALL NEW SWITCHES, POWER OUTLETS, TELEPHONE OUTLETS, FIRE ALARM DEVICES, AND COMMUNICATIONS OUTLETS SHALL MEET THE REQUIREMENTS FOR AMERICANS WITH DISABILITIES (A.D.A.) MOUNTING HEIGHTS AND ORIENTATIONS, TYPE UNLESS OTHERWISE NOTED. RECEPTACLES SHALL BE A MINIMUM OF 18" A.F.F. AND SWITCHES A MAXIMUM OF 48" A.F.F. TO CENTERLINE, TYPICAL UNLESS OTHERWISE NOTED.
30. ALL WALL MOUNTED OUTLETS SHALL BE OFFSET SO THEY ARE NOT BACK TO BACK, FOR SOUND TRANSMISSION PURPOSES. IN THE ABSENCE OF AT LEAST 6 INCHES SPACE, SEPARATE OUTLET BOXES ON OPPOSITE SIDES OF WALLS AND PARTITIONS. MOUNT ELECTRICAL AND COMMUNICATIONS OUTLETS ON WALLS AS CLOSE TOGETHER AS POSSIBLE.
31. WIRING DEVICES SHALL BE SPECIFICATION GRADE. MINIMUM DEVICE RATING SHALL BE 20 AMPS FOR ALL WIRING DEVICES UNLESS SPECIFICALLY NOTED OTHERWISE. DEVICES WITH DEDICATED CIRCUITS SHALL BE RATED AS REQUIRED BY CIRCUIT LOAD. ISOLATED GROUND RECEPTACLES SHALL BE ORANGE. ALL COLOR AND TYPE TO EXISTING BUILDING STANDARD. PROVIDE MATCHING NYLON COVER PLATES FOR ALL OUTLETS. ELECTRICAL CONTRACTOR SHALL VERIFY ALL OUTLETS WITH ARCHITECTURAL PLANS AND TENANT BEFORE ORDERING AND PURCHASING OF MATERIALS.
32. FIRE RESISTIVE WALLS AND PARTITIONS MAY HAVE OPENINGS FOR STEEL ELECTRICAL OUTLET BOXES NOT EXCEEDING 16 SQUARE INCHES IN AREA. PROVIDE THE AGGREGATE AREA OF SUCH OPENINGS IS NOT MORE THAN 100 SQUARE INCHES FOR ANY 100 SQUARE FEET OF WALL. A HORIZONTAL DISTANCE OF AT LEAST 24 INCHES SHALL SEPARATE OUTLET BOXES ON OPPOSITE SIDES OF FIRE RESISTIVE WALLS AND PARTITIONS.
33. ALL JUNCTION BOX COVERS SHALL BE INDELIBLY LABELED WITH PANEL DESIGNATION AND BRANCH CIRCUIT NUMBER OF EACH WIRE WITHIN THE JUNCTION BOX.
34. ALL WIRING SHALL BE COPPER, TYPE THIN OR THHN INSULATION, UNLESS SPECIFICALLY NOTED OTHERWISE. MINIMUM SIZE SHALL BE #12 AWG. CONDUCTORS SHALL BE FACTORY COLOR-CODED WITH WIRE COLOR CODING AS REQUIRED BY THE NATIONAL ELECTRICAL CODE AND USING STANDARD CONDUCTOR COLOR CODES:
- | | |
|-----------------------------|----------------|
| 120/208 VOLTS: | 277/480 VOLTS: |
| A: BLACK | A: BROWN |
| B: RED | B: ORANGE |
| C: BLUE | C: YELLOW |
| NEU: WHITE | NEU: GRAY |
| GND: GREEN | GND: GREEN |
| ISO: G: GREEN YELLOW STRIPE | |
35. ALL JOINTS OR SPLICES FOR 10 AWG. CONDUCTORS OR SMALLER SHALL BE MADE WITH UL-APPROVED WIRE NUTS, OR COMPRESSION-TYPE CONNECTORS.
36. ALL JOINTS OR SPLICES FOR CONDUCTORS 8 AWG AND LARGER SHALL BE MADE WITH A MECHANICAL COMPRESSION OR BOLTED CONNECTOR. AFTER THE CONDUCTORS HAVE BEEN MADE MECHANICALLY AND ELECTRICALLY SECURE, THE ENTIRE JOINT OR SPLICE SHALL BE COVERED WITH 3M SCOTCH BRAND NO. 33 TAPE OR APPROVED EQUAL, TO MAKE THE INSULATION VALUE AT THE JOINT OR SPLICE EQUAL TO THE VALUE OF THE CONDUCTOR INSULATION. ALL CONNECTORS SHALL BE UL APPROVED.
37. ALL NEW MULTI-WIRE BRANCH CIRCUITS SHALL INCLUDE SEPARATE NEUTRAL CONDUCTORS OR BREAKER TIES AS REQUIRED BY CURRENT NEC SECTION 210.4 (B).
38. VOLTAGE DROP: THE ELECTRICAL CONTRACTOR SHALL ENSURE THAT VOLTAGE DROP FOR FEEDERS TO DISTRIBUTION EQUIPMENT DOES NOT EXCEED 2% AND VOLTAGE DROP IN BRANCH CIRCUITING DOES NOT EXCEED 3% FOR OVERALL VOLTAGE DROP OF 5% (MAXIMUM). FEEDERS LISTED ON SCHEDULES AND THE ELECTRICAL ONE-LINE DIAGRAM ARE A BASE FEEDER-BRANCH CIRCUIT SIZE AND SHALL BE ADJUSTED AS NEEDED BASED ON ACTUAL LENGTHS OF CONDUCTORS.
39. ALL LIGHT FIXTURES SHALL BE SUPPORTED INDEPENDENTLY FROM STRUCTURE. REFER TO ARCHITECTURAL PLANS FOR EXACT LOCATIONS OF LIGHT FIXTURES AND ELECTRICAL DEVICES.
40. FOR ALUMINUM CONDUCTOR TERMINATIONS, ALUMINUM BI-METALLIC PIN CONNECTORS ARE REQUIRED UNLESS CONDUIT CONNECTORS ARE USED. THESE CONNECTORS SHALL BE UL LISTED PER UL 486B AND RATED FOR USE UP TO 90V AND TEMPERATURE UP TO 90°C. CONNECTORS SHALL BE INSTALLED WITH MANUFACTURER'S SPECIFIED CRIMPING TOOLS AND DIES.
41. INSTALLATION IN AREAS OF DRYWALL, CEILING SHALL BE COORDINATED SUCH THAT ACCESS PANELS ARE NOT REQUIRED. ELEMENTS REQUIRING ACCESS SHALL BE LOCATED IN THE AREAS OF ACCESSIBLE CEILING OR IN THE LOCATIONS COORDINATED WITH ARCHITECT. ACCESS PANELS REQUIRED WITHIN DRYWALL CEILINGS SHALL BE INSTALLED SYMMETRICALLY WITH OTHER PANELS OR DEVICES AND SHALL BE MINIMUM SIZE REQUIRED, "MUD-IN" TYPE, AND FIRE RATED, IF REQUIRED. ACCESS PANELS IN FIRE-RATED WALLS AND CEILINGS SHALL HAVE PROPER UL LABEL AND FIRE RATING LISTING.
42. WALL AND CEILING ROUGH-IN INSTALLATIONS FOR LOW-VOLTAGE CONTROL WIRING OF ANY TYPE SUCH AS DATA/TELECOMMUNICATIONS WIRING, FIRE ALARM WIRING, HVAC CONTROL WIRING, SECURITY SYSTEMS WIRING, TV CABLING, OPTICAL FIBER CABLING, ETC. SHALL BE COMPLETE AND READY FOR INSPECTION AT THE TIME ELECTRICAL ROUGH-IN INSPECTIONS ARE REQUESTED. ALL SHARP EDGES, CONDUIT ENDS AND METAL STUDS, ETC. FOR


- LOW-VOLTAGE CABLING SHALL BE PROTECTED BY INSULATED BUSHINGS OR GROMMETS AND SECURELY FASTENED TO THE OPENINGS FOR THE WALL ROUGH-IN INSPECTIONS. WORK SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER (GROUPED CABLES ROUTED WITH CONDUIT PARALLEL TO BUILDING LINES). CABLES SHALL BE INSTALLED PER NEC REQUIRED SEPARATIONS AND SUPPORTED FROM THE BUILDING STRUCTURE. CABLE TIES USED IN DUCTS, PLENUMS, AND OTHER AIR-HANDLING SPACES ARE REQUIRED TO HAVE A TESTING LABORATORY LISTING NUMBER AND LABEL ON EACH UNLabeled PACKAGE AS BEING APPROVED FOR USE IN THESE LOCATIONS.
43. COORDINATE MOUNTING HEIGHTS AND LOCATIONS OF ALL ELECTRICAL DEVICES LOCATED WITHIN, ABOVE, OR NEAR MILLWORK WITH ARCHITECTURAL DRAWINGS, APPROVED "SHOP DRAWINGS" AND MILLWORK CONTRACTOR. MAINTAIN CONSISTENT MOUNTING PRACTICES FOR A UNIFORM APPEARANCE. VERIFY ALL OUTLET REQUIREMENTS PRIOR TO ROUGH-IN.
44. ELECTRICAL CONTRACTOR SHALL COORDINATE EXACT LOCATIONS OF LIGHTING FIXTURES WITH THE MECHANICAL CONTRACTOR. ALL OTHER WIRING, INCLUDING LOW VOLTAGE REQUIRED FOR PROPER OPERATION OF THE AUTOMATIC TEMPERATURE CONTROL SYSTEM, SHALL BE PERFORMED BY THE MECHANICAL CONTRACTOR.
45. ELECTRICAL CONTRACTOR SHALL COMPLY WITH NEC AND LOCAL CODES FOR CONDUIT FILL REQUIREMENTS DEPENDING ON WIRE SIZES, QUANTITY, AND CORRECTION FACTORS. COORDINATE WITH LOCAL AUTHORITY HAVING JURISDICTION IF UPGRADE OF THE EXISTING ELECTRICAL INSTALLATION IS REQUIRED. THIS UPGRADE MAY INCLUDE REPLACEMENT OF THE EXISTING CONDUITS AND WIRING AFFECTED BY SCOPE OF THIS PROJECT TO ACCOMMODATE CURRENT CODE CONDUIT FILL AND CORRECTION REQUIREMENTS. INCLUDE COST ASSOCIATED WITH THIS UPGRADE IN THE BID.
46. ELECTRICAL CABINETS AND ENCLOSURES LOCATED IN PUBLIC AREAS SHALL BE LOCKABLE TYPE.
47. PENETRATIONS THROUGH STRUCTURAL MEMBERS SHALL NOT BE PERMITTED WITHOUT SPECIFIC WRITTEN PERMISSION FROM STRUCTURAL ENGINEER AND ARCHITECT. SUBMIT REQUESTS FOR PENETRATIONS TO ARCHITECT FOR REVIEW AND DISPOSITION. PRIOR TO CORE, DRILLING THROUGH FLOORS, VERIFY CLEARANCE OF BEAMS, DUCTWORK, ETC IN CEILING SPACE BELOW, AND X-RAY FOR CONDUIT AND/OR REBAR IN SLAB. COORDINATE ANGLES TO OWNER TO INFORM TENANT BELOW FOR SCHEDULING OF CORE DRILLING AND TO ADVISE CONCERNING PROTECTION FOR ANY SENSITIVE EQUIPMENT PRIOR TO COMMENCEMENT OF WORK. ALL X-RAYS AND CORE DRILLS MUST BE SCHEDULED FOR AFTER HOURS UNLESS BUILDING MANAGEMENT/OWNER AUTHORIZES OTHERWISE.
48. RACEWAYS SHALL BE PROVIDED WITH EXPANSION FITTINGS WHERE NECESSARY TO COMPENSATE FOR THERMAL EXPANSION AND CONTRACTION, AND TO ALLOW FOR MINOR MOVEMENT OF THE STRUCTURAL ELEMENTS OF THE BUILDING EXPANSION FITTINGS FOR METAL RACEWAYS SHALL BE MADE ELECTRICALLY CONTINUOUS BY EQUIPMENT BONDING JUMPERS OR OTHER MEANS.
49. PROVIDE TYPEWRITTEN, UPDATED PANELBOARD BOARD DIRECTORIES FOR ALL AFFECTED PANELS PER NEC 408.4, REFLECTING ACCURATE BRANCH CIRCUIT DESTINATIONS. CLEARLY MARK JUNCTION BOXES IN CEILING SPACE WITH PANEL DESIGNATIONS AND CIRCUIT NUMBERS. PROVIDE NEW ENGRAVED PLATE LABELS TO REPLACE ANY DAMAGED MISLABELED TEMPORARY OR OTHERWISE ILLEGIBLE EXISTING IDENTIFICATION LABELS FOR DISTRIBUTION EQUIPMENT AFFECTED BY THIS CONTRACT. ATTACH THESE LABELS PERMANENTLY TO EQUIPMENT WITH RIVETS OR SCREWS. ALL PANEL SCHEDULES SHALL INDICATE THE NAME OF THE UPSTREAM PANEL OR SWITCHBOARD PROVIDING POWER.
50. CLEAN EXPOSED PANEL BOARD SURFACES AND CHECK TIGHTNESS OF ELECTRICAL CONNECTIONS. REPLACE DAMAGED CIRCUIT BREAKERS AS REQUIRED AND PROVIDE CLOSURE PLATES FOR VACANT SPACES. ALL NEW PANELS PROVIDED UNDER THIS CONTRACT SHALL BE DOOR-IN-DOOR CONSTRUCTION TYPE, WITH BOLTED CIRCUIT BREAKERS AND COPPER BUSSING, UNLESS SPECIFICALLY NOTED OTHERWISE.
51. PROVIDE FIRE STOPPING MATERIAL AND SYSTEMS AS LISTED IN THE UL FIRE RESISTANCE DIRECTORY EQUAL TO THE FIRE RESISTANCE RATING OF THE RESPECTIVE WALL OR FLOOR ASSEMBLY FOR ALL PENETRATIONS OF CONDUIT, SLEEVES, WIRING CABLES AND OTHER ELECTRICAL ITEMS THROUGH FIRE-RATED CORRIDOR WALLS, FIRE RESISTIVE WALLS, FIRE RESISTIVE SHAFTS, AND FLOOR PENETRATIONS.

MECHANICAL SYSTEM

1. ELECTRICAL CONTRACTOR SHALL REVIEW MECHANICAL AND PLUMBING DRAWINGS AND SCHEDULES FOR VERIFICATION OF THE EQUIPMENT USED, WIRING AND ADDITIONAL INSTALLATION REQUIREMENTS PRIOR TO PROVIDING REQUIRED ROUGH-INS. STARTERS DISCONNECT SWITCHES, WHEN EQUIPMENT BELONGS TO JOB SITE, ELECTRICAL CONTRACTOR SHALL VERIFY THIS DATA WITH EQUIPMENT NAMEPLATES OR MANUALS. IF SIGNIFICANT DISCREPANCIES OCCUR CONTACT ELECTRICAL ENGINEER FOR REVISION OF THE CONSTRUCTION DOCUMENTS.
2. PROVIDE ALL REQUIRED OUTLETS, HEAVY-DUTY SAFETY DISCONNECT SWITCHES, FUSES AND CONNECTIONS FOR ALL MECHANICAL EQUIPMENT UNLESS PROVIDED BY MECHANICAL CONTRACTOR AS SPECIFICALLY DIRECTED ON MECHANICAL DRAWING OR SPECIFICATION REQUIREMENTS.
3. ELECTRICAL POWER WIRING IN CONNECTION WITH THE AUTOMATIC TEMPERATURE CONTROL SYSTEM, WHERE SHOWN ON THE ELECTRICAL DIVISION DRAWINGS, SHALL BE PERFORMED BY THE ELECTRICAL CONTRACTOR. ALL OTHER WIRING, INCLUDING LOW VOLTAGE REQUIRED FOR PROPER OPERATION OF THE AUTOMATIC TEMPERATURE CONTROL SYSTEM, SHALL BE PERFORMED BY THE MECHANICAL CONTRACTOR.

RECORD DOCUMENTS

1. RECORD DOCUMENTS: THE ELECTRICAL CONTRACTOR SHALL MAINTAIN ACCURATE RECORDS OF ALL DEVIATIONS IN WORK AS INSTALLED FROM WORK SPECIFIED ON THE DRAWINGS OR IN THE SPECIFICATIONS AND IDENTIFY ORIGIN OF CHANGE.
2. KEEP A COMPLETE SET OF RECORD DOCUMENT PRINTS IN CUSTODY DURING ENTIRE PERIOD OF CONSTRUCTION AT THE CONSTRUCTION SITE. ON COMPLETION OF THE PROJECT, TWO COMPLETE SETS OF MARKED-UP PRINTS SHOWING THESE DEVIATIONS SHALL BE DELIVERED TO GENERAL CONTRACTOR AND ARCHITECT/ENGINEER. THIS CONTRACT WILL NOT BE CONSIDERED COMPLETED UNTIL THESE RECORD DRAWINGS HAVE BEEN RECEIVED AND REVIEWED BY THE ENGINEER.



TYPICAL DETAIL FOR DEVICES AT DOOR LOCATION

SCALE: NONE

DEMOLITION

1. DURING THE DEMOLITION PHASE OF THIS CONTRACT, IT IS THE RESPONSIBILITY OF THIS CONTRACTOR TO VERIFY DEMOLITION SCOPE AND ITEMS WITH ARCHITECTURAL AND ELECTRICAL DRAWINGS. EXISTING LIGHT FIXTURES, ELECTRICAL DEVICES, EQUIPMENT AND RELATED ITEMS SHALL BE CAREFULLY REMOVED EITHER AS SHOWN ON THE DEMOLITION DRAWINGS AS BEING REMOVED, OR AS REQUIRED FOR THE WORK UNDER THIS CONTRACT. THESE ITEMS SHALL BE TAGGED, PROTECTED FROM DAMAGE, AND STORED AS DIRECTED BY THE BUILDING MANAGEMENT/OWNER, ARCHITECT OR ENGINEER.
2. DEMOLITION OR ABANDONING ANY ELECTRICAL AND COMMUNICATIONS CONDUIT, WIRING, CABLING, OR DEVICE MEANS TO REMOVE IN ITS ENTIRETY. REMOVE UNUSED CONDUITS FROM CEILING SPACES IN AREAS OF WORK. ABANDONED OUTLET JUNCTION BOXES ARE TO BE CAPPED AND COVERED WITH AN NEW PLASTIC BOARD. ABANDONED POLE TYPE OUTLETS SHALL HAVE COVER PLATES AND BE FILLED WITH FIRE RATED FOAM SEALANT TO MAINTAIN FIRE RATING OF FLOOR.
3. CONTRACTOR SHALL REMOVE SWITCHES, DATA/TELEPHONE OUTLETS, AND ELECTRICAL OUTLETS SCHEDULED FOR DEMOLITION. ALL UNUSED POWER WIRING SHALL BE REMOVED BACK TO JUNCTION BOX IN CEILING SPACE OR TO THE ELECTRICAL PANEL, FEEDING THE CIRCUIT. THE SPARE CIRCUIT BREAKER SHALL BE SWITCHED TO THE "OFF" POSITION AND NOTED ON PANEL DIRECTORY AS SPARE WITH THE JUNCTION BOX LOCATION IF APPLICABLE.
4. ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR RINGING OUT ALL CIRCUITS WHICH ARE OR MAY BE AFFECTED BY THIS PROJECT TO ENSURE CIRCUIT CONTINUITY AND TO PREVENT OVERLOADING OF ANY SINGLE CIRCUIT. CONTRACTOR SHALL ENSURE THAT CIRCUITS SHARED BETWEEN PROJECT AREA AND EXISTING TENANT SPACES REMAIN INTACT PER ORIGINAL DESIGN INTENT. CORRECT ANY MISLABELED J-BOX COVERS WITH ACCURATE PANEL BRANCH CIRCUIT IDENTIFICATION. REFER TO DETAIL NOTES ON PLANS THAT APPLY TO WORK TO BE PERFORMED UNDER THIS CONTRACT. CIRCUIT BREAKERS FOR ALL UNUSED CIRCUITS SHALL BE TURNED TO THE "OFF" POSITION AND LABELED AS SPARE ON REVISED PANEL DIRECTORIES.
5. PROVIDE NEW JUNCTION BOXES, NEW CONDUIT AND WIRING AS REQUIRED TO REPAIR, REROUTE AND RECONNECT CONDUITS THAT ARE DAMAGED, DISTURBED OR OTHERWISE ADVERSELY AFFECTED BY THE DEMOLITION AND REMODEL WORK.
6. THE LOCATIONS OF EXISTING LIGHTING FIXTURES, POWER DEVICES AND WIRING, ETC. SHOWN ON THE DRAWINGS HAS BEEN TAKEN FROM EXISTING DRAWINGS AND ARE, THEREFORE, ONLY AS ACCURATE AS THAT INFORMATION. ALL EXISTING CONDITIONS SHALL BE VERIFIED AT THE FIELD WITH NECESSARY ADJUSTMENT BEING MADE TO THE DRAWING INFORMATION.
7. ALL FLOOR AND WALL PENETRATIONS WHERE ELECTRICAL DEVICES AND RACEWAY HAVE BEEN REMOVED MUST BE REPAIRED AND SEALED TO MAINTAIN THE REQUIRED FIRE RATING. ALL LUMINAIRES PENETRATING A ONE HOUR FIRE RESISTIVE ENCLOSURE SHALL BE PROPERLY TESTED TO MAINTAIN FIRE RATING OF THE ENCLOSURE. ALL CONDUITS PENETRATING A ONE HOUR FIRE RATED WALL OR CEILING SHALL BE FIRE STOPPED WITH A U.L. LISTED FIRE STOPPING COMPOUND SEALANT.
8. MAINTAIN LIGHTING CIRCUIT AND SWITCHING CONTROL CONTINUITY IN VACANT AND NON-VACANT AREAS THAT ARE ADJACENT TO PROJECT.
9. MAINTAIN RECEPTACLE CIRCUIT CONTINUITY THROUGH WALLS WHICH ARE TO BE DEMOLISHED AND THROUGH RECEPTACLES WHICH ARE TO BE REMOVED.
10. OWNER HAS RIGHT OF FIRST REFUSAL FOR ALL REMOVED EQUIPMENT, FIXTURES, DEVICES, AND CONDUCTORS. THE ELECTRICAL CONTRACTOR SHALL COORDINATE STORAGE AND DISPOSAL OF ALL SUCH ITEMS WITH OWNER/PROPERTY MANAGEMENT PRIOR TO REMOVAL FROM SITE.

WARRANTY

1. PROVIDE COMPLETE WARRANTY INFORMATION FOR EACH ITEM, WHICH SHALL INCLUDE NAME OF PRODUCT OR EQUIPMENT; DATE OF BEGINNING OF WARRANTY OR BOND; DURATION OF WARRANTY OR BOND; AND NAMES, ADDRESSES, AND TELEPHONE NUMBERS OF MANUFACTURING/SERVICING PERSONNEL AS WELL AS PROCEDURES FOR FILING A CLAIM AND OBTAINING WARRANTY SERVICES.
2. THE CONTRACTOR SHALL WARRANT ALL MATERIALS, WORKMANSHIP AND THE SUCCESSFUL OPERATION OF ALL EQUIPMENT AND APPARATUS INSTALLED FOR A PERIOD OF ONE (1) YEAR FROM THE DATE OF FINAL ACCEPTANCE OF THE ENTIRE WORK AS IDENTIFIED IN THE GENERAL CONDITIONS.

ELECTRICAL SYMBOLS LEGEND

LIGHTING			
SYMBOL	DESCRIPTION		
	SURFACE		
	RECESSED		
	SHADING INDICATES CONNECTION TO EMERGENCY CIRCUIT OR 90-MINUTE BATTERY BACKUP		
	2x4' FLUORESCENT LIGHT FIXTURE		
	2x2' FLUORESCENT LIGHT FIXTURE		
	1x4' FLUORESCENT LIGHT FIXTURE		
	EXIT SIGN		
	EMERGENCY BATTERY PACK FIXTURE		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
	PENDANT FLUORESCENT FIXTURE		FLUORESCENT STRIP FIXTURE
	UNDER CABINET FLUORESCENT FIXTURE		PENDANT FLUORESCENT FIXTURE
	DOWNLIGHT FIXTURE		WALL WASH FIXTURE
	WALL MOUNTED FIXTURE		POLE MOUNTED OUTDOOR FIXTURE
	TRACK LIGHTING		REMOTE EMERGENCY LIGHT HEAD
	COMBINATION LIGHT AND EXHAUST FAN		
	PHOTOCELL		

SWITCHING			
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
	SINGLE POLE SWITCH		DIMMER SWITCH
	DOUBLE POLE SWITCH		KEYED SWITCH
	THREE WAY SWITCH		THERMAL OVERLOAD SWITCH
	FOUR WAY SWITCH		GANGED SWITCHES

WALL	CEILING	FLOOR
OCCUPANCY SENSOR FOR LIGHTING CONTROLS		
CRT OR DATA OUTLET		
TELEPHONE OUTLET		
TV OUTLET		

ABBR.	DESCRIPTION
AFF	ABOVE FINISHED FLOOR
AC	ABOVE COUNTER
GFI	GROUND FAULT CIRCUIT INTERRUPTER
GD	GROUND
IG	ISOLATED GROUND
NL	NIGHT LIGHT
RL	RELOCATED DEVICE OR EQUIPMENT
WP	WEATHER PROOF
EM	EMERGENCY
HD	HEAVY DUTY
TR	TAMPER RESISTANT

POWER		
SYMBOL	DESCRIPTION	
	JUNCTION BOX	
	DUPLEX RECEPTACLE	
	DEDICATED DUPLEX RECEPTACLE	
	DOUBLE DUPLEX RECEPTACLE	
	DEDICATED DOUBLE RECEPTACLE	
	SPECIAL PURPOSE RECEPTACLE	
	COVER PLATE	
	CONTACTOR	
	SIMPLEX RECEPTACLE	
SYMBOL	DESCRIPTION	
	NEW ELECTRICAL PANEL	
	EXISTING ELECTRICAL PANEL	
	DEMO ELECTRICAL PANEL	

SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
	DISCONNECT, NON FUSED		DISCONNECT, FUSED
	GROUND BAR		PULLBOX
	MOTOR		TRANSFORMER
	TIMECLOCK		METER
	WATER HEATER		SWITCHBOARD
	POWER POLE		COMBINATION POWER COMM. FLOOR BOX
	PLUGMOLD		
	WIREMOLD		

COMMUNICATION










SYMBOL	DESCRIPTION
	COMBINATION DATA/TELEPHONE OUTLET
	CRT OR DATA OUTLET
	TELEPHONE OUTLET
	TV OUTLET

CIRCUITING

SYMBOL	DESCRIPTION
	HOMERUN, SOLID 120/208 V. OPEN 277/480 V.
	CIRCUIT: RUN CONCEALED IN WALL OR CEILING
	CIRCUIT: RUN CONCEALED IN FLOOR OR GRADE
	CONDUIT RISER, TURNED UP, TURNED DOWN

FIRE ALARM AND SECURITY			
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
	THERMOSTAT		MANUAL PULL STATION
	DUCT DETECTOR		REMOTE LAMP
	MOTION SENSOR		FIRE SMOKE DAMPER
	HEAT DETECTOR		ANNUNCIATOR PANEL
	FIRE ALARM CONTROL PANEL		CARD READER
	SECURITY CAMERA		DOOR HOLDER
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
	SMOKE DETECTOR		
	FIRE HORN STROBE LIGHT		
	FIRE ALARM STROBE LIGHT		
	PAGER OR MUSIC SPEAKER		
	FIRE ALARM SPEAKER		

SYMBOL	DESCRIPTION
	EXTERIOR PAD-MOUNTED TRANSFORMER
	INTERIOR TRANSFORMER
	CURRENT TRANSFORMER
	PULL BOX
	SPACE WITHIN SWITCHBOARD

OCCUPANCY SENSOR SCHEDULE			
SYMBOL	MANUFACTURER	CATALOG #	
	WATTS/TOPPER SENSORSWITCH COOPER/GREENGATE	DW-100 WSX-PTD OW-D-1001-MV	DW SW
	WATTS/TOPPER SENSORSWITCH COOPER/GREENGATE	PW-100 WSX OW-D-1001-MV	PA SW
	WATTS/TOPPER SENSORSWITCH COOPER/GREENGATE	DW-200 WSX-PTD-2P OW-D-1001-DMV	DW SW IN
	WATTS/TOPPER SENSORSWITCH COOPER/GREENGATE	DT-355 CMR-PTD-9 OAC-PT-2000-MV	DW SW
	WATTS/TOPPER SENSORSWITCH COOPER/GREENGATE	DT-305 / BZ-50 CM-PTD-9 / PP20 OAC-PT-1000 / SP20-MV	DW CO
	WATTS/TOPPER SENSORSWITCH COOPER/GREENGATE	WT-2200 / BZ-50 CM-PTD-10 / PP20 OAC-PT-2000 / SP20-MV	EX OF OF
	WATTS/TOPPER SENSORSWITCH COOPER/GREENGATE	CB-100 / BZ-50 SBR-10-ODP OXC-P-1500-R / SP20-MV	WI PA
	AS SPECIFIED ON PLAN	AS SPECIFIED ON PLAN	OT SC
	AS SPECIFIED ON PLAN	AS SPECIFIED ON PLAN	OT AN

CONSULTANT:



PROJECT:

CS AUDITORIUM RESTROOM RENOVATION

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

COLORADO SPRINGS CITY AUDITORIUM

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/15 ISSUED FOR BIDDING AND
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 15380

DRAWN BY: LEE

PROJECT ENGINEER: AW

APPROVED BY: SLS



SHEET TITLE:

ELECTRICAL PLANS

E100

SHEET 2

OF 2





Level 1 Demolition Lighting Plan

1/8" = 1'-0"

GENERAL NOTES:

A. REMOVED ITEMS SHOWN AS DASHED AND LIGHT





Level 1 Power Plan

1/8" = 1'-0"

GENERAL NOTES:

A. NEW AND RELOCATED ITEMS SHOWN AS BOLD
EXISTING ITEMS SHOWN AS LIGHT



Level 1 Lighting Plan

1/8" = 1'-0"

GENERAL NOTES:

A. NEW AND RELOCATED ITEMS SHOWN AS BOLD
EXISTING ITEMS SHOWN AS LIGHT
B. TOTAL LIGHTING LOAD REDUCED.



COMcheck Software Version 3.9.4

Interior Lighting and Power Compliance Certificate

2012 IECC

Section 1: Project Information

Project Type: Alteration
Project Title: CO Springs Auditorium

Construction Site:

Owner/Agent:

Designer/Contractor:
Alex Wolke
Corey EE

Section 2: Interior Lighting and Power Calculation

A Area Category	B Floor Area (ft ²)	C Allowed Watts / ft ²	D Allowed Watts (B x C)
Common Space Types: Restroom	870	1	870
Total Allowed Watts =			870

Section 3: Interior Lighting Fixture Schedule

A Fixture ID : Description / Lamp / Wattage Per Lamp / Ballast	B Lamps/ Fixture	C # of Fixtures	D Fixture Watt.	E (C X D)
Common Space Types: Restroom (870 sq.ft.)				
Incandescent 1: Incandescent 35W:	1	1	35	35
LED 1: Other:	3	12	39	468
LED 2: Other:				
Total Proposed Watts =			468	

Interior Lighting PASSES

Section 4: Compliance Statement

Compliance Statement: The proposed lighting design represented in this document is consistent with the building plans, specifications and other calculations submitted with this permit application. The proposed lighting system has been designed to meet the 2012 IECC requirements in COMcheck Version 3.9.4 and to comply with the mandatory requirements in the Requirements Checklist.

Name - Title

Signature

Date

Section 5: Post Construction Compliance Statement

Record Drawings and Operating and Maintenance Manuals:

1. Construction documents with record drawings and operating and maintenance manuals provided to the owner.

ALEX WOLKE - PROJECT MANAGER

Lighting Designer or Contractor Name

Signature

10/2/15

Date

Project Title: CO Springs Auditorium

Report date: 10/02/15

Data filename: F:\DATA\ACAD\15 Archives\15300-15399\15380 Colorado Springs Auditorium\Design\IECC-Comcheck\IECC.cck Page 1 of 1

3PH FAULT CALCULATION

POINT #1, AT THE UTILITY TRANSFORMER:

$$I_{sc} = \frac{100,000}{1} A$$

(WORST CASE)

POINT #4, AT PANEL LC:

$$f = 1.73 \times \frac{\text{Length}}{20} \times \frac{I_{sc}(\text{source})}{100,000} A / \frac{L-L \text{ Volts}}{208} \times \frac{\text{Wire Factor}}{8924}$$
$$f = \frac{1.86}{1.86}$$

$$M = 1 / \frac{1+f}{1+1.86} = 0.35$$


$$I_{sc} = M \times I_{sc}(\text{source}) = 0.35 \times 100,000 A = 34,916 A$$

POINT #5, AT PANEL WC:

$$f = 1.73 \times \frac{\text{Length}}{150} \times \frac{I_{sc}(\text{source})}{34,916} A / \frac{L-L \text{ Volts}}{208} \times \frac{\text{Wire Factor}}{5906}$$
$$f = \frac{7.38}{7.38}$$

$$M = 1 / \frac{1+f}{1+7.38} = 0.12$$

$$I_{sc} = M \times I_{sc}(\text{source}) = 0.12 \times 34,916 A = 4,169 A$$




PARTIAL ONE-LINE DIAGRAM (NO NEW WORK)

1/8" = 1'-0"

DETAIL NOTES

- PRESERVE HAND DRYER CIRCUIT FOR NEW LOCATION PER POWER PLAN.
- PRESERVE RECEPTACLE CIRCUIT FOR RE-USE IN NEW LOCATION PER POWER PLAN.
- E.C. TO REMOVE ALL ABANDONED CONDUIT/CABLING/WIRING FROM SPACE INCLUDING ABOVE THE CEILING BACK TO SOURCE. ANY CIRCUITS MADE SPARE TO BE TURNED OFF AND LABELED AS SUCH WITH VEW TYPED PANEL SCHEDULES.
- RETURN LIGHTING NOT RE-USED TO BUILDING MANAGEMENT.
- EXHAUST FAN 7A/120V. CONNECT FAN THROUGH THERMAL SWITCH USING 2-#12 CU AND #12 GND IN 3/4"C. COORDINATE CONTROL WITH M.C.
- RE-USE EXISTING OPENING FOR NEW KEYED SWITCH.
- 6" DOWNLIGHT FOR PLASTER CEILING. 17W/120V. HALO #PD6-15-ED010-PDM6A-##-61V-C. MATCH VANITY COLOR TEMPERATURE.
- LED VANITY FIXTURE, 120V/POLISHED NICKEL. FEISS #VS21903PN-LA. (3) 13W LED. COORDINATE HEIGHT WITH ARCHITECT. SURFACE MOUNT ON PLASTER PROVIDING SURFACE CONDUIT FROM NEW PENETRATION THROUGH CEILING.
- PROVIDE FIXTURE WITH 90-MIN BATTERY BACKUP AND TEST SWITCH AND CIRCUIT TO LOCAL LIGHTING CIRCUIT AHEAD OF CONTROL.
- CONNECT TO LOCAL LIGHTING CIRCUIT. E.C. TO VERIFY NO MORE THAN 70% LOAD ON A SINGLE 120V LIGHTING CIRCUIT.



KEYPLAN

1" = 50'-0"

* NEW CIRCUIT BREAKER TO MATCH EXISTING MANUFACTURER AND AIC RATING.

DIVISION 230000 - MECHANICAL SPECIFICATIONS

BASIC MECHANICAL REQUIREMENTS

QUALITY ASSURANCE:

- IF MANUFACTURER'S MATERIAL OR EQUIPMENT IS LISTED IN SCHEDULES OR ON DRAWINGS, THEY ARE TYPES TO BE PROVIDED FOR ESTABLISHMENT OF SIZE, CAPACITY, GRADE, AND QUALITY. IF OTHER ACCEPTABLE MANUFACTURERS ARE USED, COST OF ANY CHANGE IN CONSTRUCTION REQUIRED BY THEIR USE SHALL BE BORNE BY CONTRACTOR.
- EQUIPMENT SHALL CONFORM TO STATE AND/OR LOCAL ENERGY CONSERVATION STANDARDS.

INTENT AND INTERPRETATIONS:

- IT IS THE INTENT OF THESE DRAWINGS AND SPECIFICATIONS TO RESULT IN A COMPLETE MECHANICAL INSTALLATION IN COMPLETE ACCORDANCE WITH ALL APPLICABLE LOCAL CODES AND ORDINANCES.
- DRAWINGS ARE DIAGRAMMATIC IN CHARACTER AND DO NOT NECESSARILY INDICATE EVERY REQUIRED PIPE, OFFSET, TRANSITION, ETC. ITEMS NOT SPECIFICALLY MENTIONED IN THE SPECIFICATION OR NOTED ON THE DRAWINGS, BUT WHICH ARE NECESSARY TO MAKE A COMPLETE WORKING INSTALLATION, SHALL BE INCLUDED.
- DRAWINGS AND SPECIFICATIONS ARE COMPLEMENTARY. WHATEVER IS CALLED FOR IN EITHER IS BINDING AS THOUGH CALLED FOR IN BOTH. IF THERE IS A CONFLICT IN THE CONTRACT DOCUMENTS, THE MORE DEMANDING AND COSTLY DESIGN SHALL BE SELECTED FOR BIDDING PURPOSES. THE CONTRACTOR SHALL IMMEDIATELY PRESENT THE CONFLICT FOUND IN THE CONTRACT DOCUMENTS TO THE ARCHITECT/ENGINEER FOR RESOLUTION. IF THE RESOLUTION FAVORS A LESS COSTLY DESIGN, THE CONTRACTOR WILL BE REQUIRED TO REIMBURSE THE DIFFERENCE IN COST.
- DRAWINGS SHALL NOT BE SCALED FOR ROUGH-IN MEASUREMENTS OR USED AS SHOP DRAWINGS. WHEN DRAWINGS ARE REQUIRED FOR THESE PURPOSES OR HAVE TO BE MADE FROM FIELD MEASUREMENTS, TAKE THE NECESSARY MEASUREMENTS AND PREPARE THE DRAWINGS.
- BEFORE ANY WORK IS INSTALLED, DETERMINE THAT EQUIPMENT WILL PROPERLY FIT THE SPACE. THAT REQUIRED CLEARANCES CAN BE MAINTAINED AND THAT EQUIPMENT CAN BE LOCATED WITHOUT INTERFERENCES BETWEEN SYSTEMS, WITH STRUCTURAL ELEMENTS, OR WITH THE WORK OF OTHER TRADES.
- IF CONFLICTS ARE DISCOVERED IN CONTRACT DOCUMENTS AS WORK PROGRESSES, SUBMIT A SET OF DRAWINGS MARKED WITH RED PENCIL SHOWING RECOMMENDED MODIFICATIONS TO THE ARCHITECT FOR APPROVAL PRIOR TO INSTALLATION.

JOB CONDITIONS:

- CONFIR, COOPERATE, AND COORDINATE WORK WITH OTHER TRADES. COORDINATE CEILING CAVITY SPACE CAREFULLY WITH ALL TRADES. IN EVENT OF CONFLICT, INSTALL MECHANICAL AND ELECTRICAL SYSTEMS WITHIN CAVITY SPACE IN FOLLOWING ORDER OF PRIORITY.
 - PUMPING WASTE AND VENT PIPING.
 - ROOF DRAIN PIPING.
 - DUCTWORK.
 - ELECTRICAL CONDUIT AND LIGHTING.
 - DOMESTIC HOT AND COLD WATER PIPING.
 - FIRE SPRINKLER PIPING.

PERMITS AND FEES:

- ARRANGE AND PAY FOR ALL INSPECTIONS, PERMITS, LICENSES, CERTIFICATES, AND FEES REQUIRED IN CONNECTION WITH WORK.

SUBMITTALS AND SHOP DRAWINGS:

- CONFORM TO REQUIREMENTS OF DIVISION 1 AND FOLLOWING PARAGRAPHS.
- SUBMITTALS SHALL INCLUDE CATALOG, CUT-SHEETS AND MANUFACTURER'S DATA SHEETS.
- PRIOR TO ORDERING EQUIPMENT OR BEGINNING INSTALLATION WORK, ASSEMBLE, PREPARE, AND FURNISH SUBMITTALS AND SHOP DRAWINGS REQUIRED FOR PROJECT. FURNISH SUBMITTALS AND SHOP DRAWINGS AS REQUIRED BY INDIVIDUAL SECTIONS OF SPECIFICATIONS.
- CONTRACTOR SHALL THOROUGHLY CHECK SUBCONTRACTORS' OR VENDORS' SUBMITTALS AND SHOP DRAWINGS AND, AFTER APPROVING THEM, SUBMIT THEM FOR REVIEW. SUBMITTALS AND SHOP DRAWINGS THAT DO NOT BEAR CONTRACTOR'S REVIEW STAMP WILL BE RETURNED NOT REVIEWED.
- IF DISCREPANCIES BETWEEN SUBMITTALS, SHOP DRAWINGS, AND CONTRACT DOCUMENTS ARE DISCOVERED EITHER PRIOR TO OR AFTER SUBMITTALS AND SHOP DRAWINGS ARE REVIEWED, REQUIREMENTS OF CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE. SUBMITTALS AND SHOP DRAWINGS WHICH ARE SUBMITTED, BUT WHICH ARE NOT REQUIRED BY CONTRACT DOCUMENTS, WILL BE RETURNED NOT REVIEWED.
- SUBMITTALS AND SHOP DRAWINGS SHALL IDENTIFY SPECIFIC EQUIPMENT WITH NUMBERS OR LETTERS IDENTICAL TO THOSE LISTED OR SCHEDULED ON THE DRAWINGS OR SPECIFICATIONS.

RECORD DOCUMENTS:

- KEEP IN CUSTODY DURING ENTIRE PERIOD OF CONSTRUCTION, A CURRENT SET OF DOCUMENTS INDICATING CHANGES THAT HAVE BEEN MADE TO THE CONTRACT DOCUMENTS.
- UPON COMPLETION OF WORK, SUBMIT THE COMPLETE SET OF RECORD DOCUMENTS TO THE ARCHITECT.

PROTECTION OF EQUIPMENT:

- PROTECT MATERIALS AND EQUIPMENT FROM PHYSICAL DAMAGE, CONSTRUCTION DIRT, AND THE ELEMENTS FROM TIME OF SHIPMENT TO TIME INSTALLATION IS ACCEPTED BY OWNER.

GUARANTEE:

- GUARANTEE MATERIALS, WORKMANSHIP, AND OPERATION OF EQUIPMENT INSTALLED FOR PERIOD OF ONE YEAR FROM DATE OF ACCEPTANCE OF ENTIRE WORK. REPAIR OR REPLACE ANY PART OF WORK WHICH SHOWS DEFECT DURING THAT TIME.
- BE RESPONSIBLE FOR DAMAGE TO PROPERTY OF OWNER OR TO WORK OF OTHER CONTRACTORS DURING CONSTRUCTION AND GUARANTEE PERIOD.
- FURNISH EQUIPMENT WARRANTIES TO OWNER.

MECHANICAL EQUIPMENT WIRING AND CONNECTIONS:

- VOLTAGE CHARACTERISTICS SHALL BE AS IN ELECTRICAL DIVISION OF SPECIFICATIONS AND ON ELECTRICAL DRAWINGS.

TEMPORARY FACILITIES:

- USE OF EXISTING EQUIPMENT FOR TEMPORARY HEATING OR COOLING: DO NOT USE NEW OR EXISTING BUILDING EQUIPMENT WITHOUT WRITTEN PERMISSION FROM OWNER.

INSPECTIONS:

- DO NOT COVER UP OR ENCLOSE WORK UNTIL INSPECTED, TESTED, AND APPROVED. ANY WORK ENCLOSED OR COVERED UP BEFORE SUCH APPROVAL SHALL BE UNCOVERED, TESTED, AND APPROVED.

ACCESS DOORS:

- FURNISH HINGED STEEL ACCESS DOORS WITH CONCEALED LATCH, WHETHER SHOWN OR NOT, IN WALLS AND PLASTER OR GYPSUM BOARD CEILINGS FOR ACCESS TO CONCEALED VALVES, SHOCK ARRESTERS, AIR VENTS, MOTORS, FANS, BALANCING VALVES, OR OTHER OPERATING DEVICES REQUIRING ADJUSTMENT OR SERVICING.
- ACCESS DOOR SHALL BE SIZE OF EQUIPMENT TO BE REMOVED OR 24" B X 24" IF USED FOR SERVICE ONLY.

SUPERVISION:

- SUPERVISE WORK TO PROCEED IN PROPER SEQUENCE WITHOUT DELAY TO OTHER CONTRACTORS. KEEP SUPERVISOR ON PREMISES AT ALL TIMES TO ENSURE THAT INTENT OF DRAWINGS AND SPECIFICATIONS IS BEING FOLLOWED.

INSTALLATION:

- WORKMANSHIP SHALL BE FIRST QUALITY. APPEARANCE OF WORK SHALL BE OF EQUAL IMPORTANCE TO ITS MECHANICAL OPERATION. LACK OF QUALITY WORKMANSHIP SHALL BE REASON FOR REJECTION OF SYSTEM IN PART OR IN WHOLE.
- INSTALL SO THAT ALL VALVES AND EQUIPMENT CAN BE EASILY ACCESSED AND SERVICED BY ADEQUATE CLEARANCE, INSTALLATION OF ACCESS DOORS, UNIONS IN PIPING, OR OTHER METHODS.
- COMPLETE INSTALLATION SHALL FUNCTION SMOOTHLY AND NOISELESSLY.
- INSTALL EQUIPMENT AND MATERIALS PER MANUFACTURER'S RECOMMENDATIONS AND LOCAL CODES OR REGULATIONS.
- PLACE OR REPLACE ALL EQUIPMENT NAMEPLATES WHERE THEY CAN BE SEEN AND READ WITHOUT DIFFICULTY.
- FLUSH PIPES FREE OF FOREIGN SUBSTANCES BEFORE INSTALLING VALVES OR MAKING FINAL CONNECTIONS. CLEAN ALL PIPING AND EQUIPMENT.

COMPLETION:

- CLEAN INSULATION COVERING, DUCTS, PIPES, EQUIPMENT, AND ACCESSORIES TO RECEIVE PRIME COAT OF PAINT. CLEAN EQUIPMENT RECEIVED WITH PRIME COAT TO RECEIVE FINAL COAT.
- REPLACE AIR FILTERS IF UNITS WERE OPERATED DURING CONSTRUCTION. CLEAN DUCTS, BLOWERS, AND COILS IF UNITS WERE OPERATED WITHOUT FILTERS DURING CONSTRUCTION.
- INSTRUCT OWNER IN OPERATION AND MAINTENANCE OF MECHANICAL SYSTEMS. MINIMUM PARTICIPANTS SHALL INCLUDE MECHANICAL CONTRACTOR AND CONTROLS CONTRACTOR REPRESENTATIVES.
- AFTER TESTS AND ADJUSTMENTS HAVE BEEN MADE AND SYSTEMS PRONOUNCED SATISFACTORY FOR PERMANENT OPERATION, REFINISH DAMAGED FINISH AND LEAVE EVERYTHING IN PROPER WORKING ORDER AND APPEARANCE.
- ON COMPLETION OF WORK, REMOVE TOOLS, SCAFFOLDING, DEBRIS, ETC., FROM GROUNDS AND LEAVE PREMISES CLEAN.

BASIC MECHANICAL REQUIREMENTS (CONTINUED)

OPERATION AND MAINTENANCE MANUALS:

- PRIOR TO COMPLETION OF PROJECT SUBMIT OPERATION AND MAINTENANCE MANUALS FOR MECHANICAL EQUIPMENT WITH MOVING OR MOVABLE PARTS, INCLUDING PUMPING SYSTEMS, PER EEC. INSTRUCTIONS SHALL BE IN PAMPHLET, TYPEWRITTEN OR PDF FORM. INSTRUCTIONS FOR EACH PIECE OF EQUIPMENT SHALL BE INDICATED BY A SEPARATE TAB.
- INCLUDE TEST AND BALANCE REPORT.
- INCLUDE STARTING, STOPPING, LUBRICATION, PREVENTATIVE MAINTENANCE SCHEDULE, AND ADJUSTMENT INFORMATION FOR EACH PIECE OF EQUIPMENT.
- INCLUDE GUARANTEES AND WARRANTIES OF ALL EQUIPMENT.

PIPE AND PIPE FITTINGS

PIPE AND TUBE

- COPPER REFRIGERANT TUBE: ASTM B280-03, SEAMLESS.
- COPPER DRAINAGE TUBE (DWV): ASTM B308-88.

PIPE AND TUBE JOINTS AND FITTINGS

- COPPER AND BRASS PIPE FITTINGS: ASME B16.23, PRESSURE FITTINGS; ASME B16.29, DRAINAGE FITTINGS.

GENERAL

- COOLING COIL, CONDENSATE DRAIN PIPING: MAINTAIN PIPE SLOPE 1/8" DOWN PER LINEAR FOOT IN THE DIRECTION OF FLOW UNLESS OTHERWISE NOTED ON DRAWINGS.
- MAKE CONNECTIONS TO EQUIPMENT WITH UNIONS OR FLANGES.
- COOLING COIL, CONDENSATE DRAIN PIPING SHALL BE EQUAL TO OR LARGER THAN THE EXIT DIAMETER OF THE DRAIN PAN DRAIN CONNECTION.
- FLUSH EACH PIPING SYSTEM AND PROVE CLEAN.

COPPER PIPE CONNECTIONS

- USE 15% SILVER BRAZING ALLOY AND SILVER BRAZING FLUX ON CONCEALED JOINTS.

REFRIGERANT COPPER PIPE CONNECTIONS

- 2-5/8" O.D. AND SMALLER: 95% TIN, 5% ANTIMONY LEAD-FREE SOLDER.
- 3-1/8" O.D. AND LARGER, HOT GAS PIPING, BURIED PIPING: 15% SILVER BRAZING ALLOY.
- CONTINUOUSLY PURGE PIPING WITH DRY NITROGEN DURING SILVER BRAZING PROCESS.

PIPE TESTING

- TEST ALL PIPING SYSTEMS. CORRECT LEAKS BY REMAKING JOINTS. REMOVE EQUIPMENT NOT ABLE TO WITHSTAND TEST PRESSURE FROM SYSTEM DURING TEST. CONSULT GOVERNING CODES FOR SPECIAL SYSTEM REQUIREMENTS.
- TEST PIPING BEFORE BEING PERMANENTLY ENCLOSED.
- OBTAIN CERTIFICATES OF APPROVAL, ACCEPTANCE, COMPLIANCE WITH REGULATIONS OF AGENCIES HAVING JURISDICTION. SUBMIT TO OWNER.
- REFRIGERANT PIPING SYSTEM TEST: TEST WITH NITROGEN AT 300 PSIG ON HIGH SIDE OF SYSTEM AND AT 150 PSIG ON LOW SIDE. MAINTAIN PRESSURE FOR 24 HOURS. AFTER TEST, EVALUATE PIPING WITH VACUUM PUMP FOR MINIMUM 24 HOURS OR UNTIL SYSTEM HAS BEEN COMPLETELY EVACUATED.

SUPPORTS, ANCHORS, SEALS

WORK INCLUDED:

- DUCT HANGERS AND SUPPORTS.
- EQUIPMENT BASES AND SUPPORTS.
- FLASHING FOR MECHANICAL EQUIPMENT.
- SLEEVING FOR MECHANICAL EQUIPMENT.

REFERENCE STANDARDS:

- PIPE SUPPORTS: ANSI B31.1, POWER PIPING.
- DUCT HANGERS AND REINFORCEMENT: SMACNA DUCT MANUALS.
- FIRE BARRIER PRODUCTS: ASTM E119-00a; ASTM E814-02; ASTM 84-04, AND UL 1479.

SUBMITTALS:

- FURNISH MANUFACTURER'S SUBMITTAL DATA FOR PREFABRICATED EQUIPMENT SUPPORTS.

DUCT HANGERS AND SUPPORTS:

- HANGERS: GALVANIZED STEEL BAND, ROLLED ANGLE, OR UNISTRUT TYPE MEMBERS WITH THREADED RODS.
- WALL SUPPORTS: GALVANIZED STEEL BAND IRON OR FABRICATED ANGLE BRACKET.
- VERTICAL SUPPORT AT FLOOR: ROLLED ANGLE.
- RIGID ROUND DUCTWORK: 1" WIDE GALVANIZED STEEL STRAPS, QUANTITY, SPACING, AND GAUGE PER SMACNA STANDARDS.
- FLEXIBLE DUCTWORK: 1" WIDE GALVANIZED STEEL STRAPS. MAXIMUM ALLOWABLE SAG 1/2" PER FOOT.
- FLEXIBLE DUCTWORK: 1" WIDE GALVANIZED STEEL STRAPS. MAXIMUM ALLOWABLE SAG 1/2" PER FOOT.
- SPACING AND GAUGE OF HANGERS PER UNIFORM MECHANICAL CODE, SMACNA STANDARDS, AND DUCT MANUFACTURER'S RECOMMENDATIONS.
- PROVIDE A MINIMUM OF TWO FASTENERS INTO DUCT AND INTO TOP ATTACHMENT FOR ALL DUCTS WITH LONG SIDE EXCEEDING 18".

PREFABRICATED EQUIPMENT SUPPORTS:

- EQUIPMENT BASES
 - SOLID TOP EQUIPMENT BASE WITH INTEGRAL DUCT CURB AND) STEPPED CANT TO MATCH ROOF INSULATION. PITCH BASE TO MATCH ROOF PITCH; PROVIDE LEVEL INSTALLATION.

EXECUTION/INSTALLATION:

- INSERTS
 - USE INSERTS FOR SUSPENDING HANGERS FROM REINFORCED CONCRETE SLABS AND SIDES OF REINFORCED CONCRETE BEAMS.
 - SET INSERTS IN POSITION IN ADVANCE OF CONCRETE WORK. PROVIDE REINFORCEMENT ROD IN CONCRETE FOR INSERTS CARRYING PIPE OVER 4" OR DUCTS OVER 60" WIDE.
 - WHERE CONCRETE SLABS FORM FINISHED CEILING, FINISH INSERTS FLUSH WITH SLAB SURFACE.
 - WHERE INSERTS ARE OMITTED, DRILL THROUGH CONCRETE SLAB FROM BELOW AND PROVIDE ROD WITH RECESSED SQUARE STEEL PLATE AND NUT ABOVE SLAB. OBTAIN WRITTEN PERMISSION OF LOCATION AND PROCEDURE FROM STRUCTURAL ENGINEER PRIOR TO COMMENCING WORK.
- ANCHORS
 - USE ANCHORS FOR SUSPENDING HANGERS FROM REINFORCED CONCRETE SLABS, AND SIDES OF REINFORCED CONCRETE BEAMS.
 - REVIEW ANCHOR LOCATIONS, DEPTHS WITH ARCHITECT AND STRUCTURAL ENGINEER BEFORE INSTALLATION.
 - INSTALL PER MANUFACTURER'S DESIGN CRITERIA, INSTALLATION INSTRUCTIONS.

DUCT HANGERS AND SUPPORTS:

- SUPPORT DUCTWORK IN ACCORDANCE WITH INTERNATIONAL MECHANICAL CODE, SMACNA, AND ASHRAE REQUIREMENTS AND RECOMMENDATIONS.

EQUIPMENT BASES:

- CONCRETE BASES FOR EQUIPMENT WILL BE PROVIDED BY OTHERS ONLY IF SHOWN ON ARCHITECTURAL OR STRUCTURAL DRAWINGS. ALL OTHER BASES SHALL BE PROVIDED BY THIS CONTRACTOR.
- BASES SHALL BE 4" THICK MINIMUM, EXTENDED 8" BEYOND MACHINERY BEDPLATES. THICKEN CONCRETE AT ANCHOR BOLTS IF IMBEDMENT EXCEEDS 2".
- SIZE AND LOCATE ALL BASES. FURNISH ALL REQUIRED ANCHOR BOLTS AND SLEEVES.
- SECURE EQUIPMENT OR VIBRATION ISOLATION DEVICES FOR EQUIPMENT TO BASES WITH ANCHOR BOLTS. ANCHOR BOLTS SHALL BE PROVIDED BY EQUIPMENT MANUFACTURER OR SPECIFIED BY EQUIPMENT MANUFACTURER AND SUPPLIED BY CONTRACTOR. BOLTS SHALL BE SECURELY IMBEDDED IN THE CONCRETE BASE. GROUT HANGERS UNDER ENTIRE BEARING SURFACE UNLESS ISOLATED FOR VIBRATION. AFTER GROUT HAS SET, REMOVE ALL WEDGES, SHIMS, JACK BOLTS. FILL SPACE WITH NONSHRINKING GROUT. PROVIDE LEAD WASHERS AT EQUIPMENT ANCHOR BOLTS.
- FABRICATE EQUIPMENT SUPPORTS OF STRUCTURAL STEEL MEMBERS OR STEEL PIPE AND FITTINGS. BRACE AND FASTEN WITH FLANGES BOLTED TO STRUCTURE.

FLASHING AND SAVING:

- WHERE EXPOSED PIPING AND DUCTWORK PASSES THROUGH WALLS, FLOORS, ROOFS, PROVIDE CHROME PLATED OR STAINLESS STEEL ESCUTCHEON FOR PIPING AND A MINIMUM 26 GAUGE GALVANIZED ANGLE FRAME FOR DUCTWORK. ROLL FRAME TO MATCH THE DIAMETER OF ROUND DUCT.
- PROVIDE SOUND RATED FLASHING AROUND DUCTS AND PIPES PASSING THROUGH EQUIPMENT ROOMS. INSTALLED PER MANUFACTURER'S DATA FOR SOUND CONTROL. TO MEET THE ATTENUATION SPECIFIED ON ARCHITECTURAL DRAWINGS FOR THE DESIGNATED WALL.
- FLASH AND COUNTERFLASH WHERE MECHANICAL EQUIPMENT PASSES THROUGH WEATHER- OR WATER-PROOFED WALLS, FLOORS, ROOFS.

SUPPORTS, ANCHORS, SEALS (CONTINUED)

SLEEVES:

- PROVIDE FRAMED 18 GAUGE GALVANIZED SHEET METAL SLEEVES FOR DUCTWORK. UNLESS OTHERWISE INDICATED, SLEEVES SHALL BE OF SIZE TO PROVIDE FROM 1/4" TO 1" CLEARANCE BETWEEN BARE PIPE OR DUCT AND SLEEVE OR BETWEEN INSULATION JACKET AND SLEEVE. WHERE PIPE OR DUCT PASSES THROUGH CONCRETE FLOOR, EXTEND SLEEVE MINIMUM 1" ABOVE FINISHED FLOOR.
- SLEEVES IN BEARING WALLS, WATERPROOF MEMBRANE FLOORS, WET AREAS SHALL BE STEEL PIPE OR CAST IRON PIPE FOR SMALL ROUND DUCTS AND PIPES. 16 GAUGE GALVANIZED SHEET METAL FOR DUCTS. SLEEVES IN NON-BEARING WALLS, FLOORS, CEILINGS SHALL BE STEEL PIPE, CAST IRON PIPE, OR GALVANIZED SHEET METAL WITH LOCK-TYPE LONGITUDINAL SEAM.
- WHERE DUCTS PENETRATE BEARING WALLS (EXCLUDING FOUNDATIONS), FIRE RATED WALLS, PARTITIONS, FLOORS, PACK AND SEAL ENTIRE SPACE BETWEEN DUCT AND SLEEVE WITH DOW CORNING 3454B SILICONE RTV SEAL OR 1" MINIMUM THICKNESS OF 3M FIRE BARRIER, 07-25 CAULK, OR 303 PUTTY ON EACH SIDE OF OPENING.
- WHERE DUCT PENETRATIONS OCCUR IN NON-FIRE RATED FLOORS OR WALLS, PACK SPACE BETWEEN DUCT AND SLEEVE OR INSULATION INSERT AND SLEEVE ON EACH END WITH MINERAL WOOL OR OTHER NON-COMBUSTIBLE MATERIAL.

MECHANICAL IDENTIFICATION

DUCT IDENTIFICATION

- WHERE IT WILL ASSIST IN IDENTIFYING OR CORRELATING ZONE SUPPLY AIR DUCTS WITH TEMPERATURE CONTROLS OR OTHERWISE ASSIST IDENTIFICATION, MARK DUCTS AT EQUIPMENT OR IN EQUIPMENT ROOMS WITH DECALS, STENCILS, OR PRESSURE-SENSITIVE LABELS APPROPRIATE FOR SURFACE OF APPLICATION AND OF SIZE EASILY READ FROM FLOOR LEVEL.

EQUIPMENT IDENTIFICATION

- IDENTIFY EQUIPMENT WITH LAMINATED BLACK PLASTIC TAG WITH ENGRAVED WHITE CORE LETTERING. TAG SHALL INDICATE EQUIPMENT DUTY SUCH AS "FURNACE," "CONDENSING UNIT," AND EQUIPMENT DESIGNATION AS SHOWN ON DRAWINGS. TAGS SHALL HAVE MINIMUM THICKNESS OF 1/16", MINIMUM SIZE OF 1-1/2" X 4", WITH MOUNTING HOLES. SECURE TAGS TO EQUIPMENT BY MEANS OF SCREWS, BOLTS, CHAIN.
- IDENTIFY EACH THERMOSTAT BY MEANS OF GUN TAG INDICATING CORRESPONDING UNIT WHICH IT CONTROLS. LOCATE TAG INSIDE THE INSTRUMENT COVER.

INSULATION

- FURNISH AND INSTALL INSULATION FOR ALL DUCTWORK SYSTEMS. LOW PRESSURE DUCTWORK INSULATION: 1" DUCT LINER, MEDIUM PRESSURE DUCTWORK INSULATION: 1-1/2" EXTERIOR DUCT WRAP. ALL EQUIPMENT INSULATION SHALL INCLUDE A VAPOR BARRIER.
- FURNISH AND INSTALL INSULATION FOR ALL REFRIGERANT PIPING SYSTEMS. REFRIGERANT LIQUID AND INDOOR REFRIGERATED SUCTION PIPING, ALL SIZES: 1" THICKNESS. REFRIGERANT PIPING OUTDOORS, ALL SIZES: 3/4" THICKNESS.

DUCTWORK

- FLEXIBLE AIR DUCT
 - LISTED UNDER UL-181 STANDARDS AS CLASS I AIR DUCT MATERIAL. MAXIMUM OPERATING PRESSURE 4" W.C. MAXIMUM WORKING VELOCITY 4,000 FPM. MATERIAL SHALL BE APPROVED BY AUTHORITY HAVING JURISDICTION.
 - INSULATED: METAL OR ALUMINUM LAMINATE INNER CORE. 1" THICK 34 LB. DENSITY FIBERGLASS INSULATION MINIMUM 1/4" VALUE (0.25) METAL OR APPROVED METALLIZED POLYESTER OR SCUF-RESISTANT FOL. SCRIU OUTER JACKET (MAXIMUM VAPOR TRANSMISSION RATE 0.05 PERMS).
 - NON-INSULATED: DEAD SOFT SPIRAL CORRUGATED ALUMINUM SHEET OR ALUMINUM OVER A TIE SPRING HELIX.
- SPIN-IN FITTING: FLARED INLET, MANUAL VOLUME DAMPER AND REGULATOR WHERE NOTED.
- FABRICATION
 - DUCT PRESSURE AND LEAKAGE CLASSIFICATIONS
 - FABRICATE ALL DUCTWORK PER THE REQUIREMENTS OF THE FOLLOWING PRESSURE CLASSIFICATIONS TABLE.

DUCTWORK PRESSURE CHART			
DUCTWORK		MIN. DUCT PRESSURE CLASSIFICATION (W.C.)	MIN. LEAKAGE CLASSIFICATION
VARIABLE AIR VOLUME SUPPLY DUCTWORK	FROM FAN OUTLET TO TERMINAL UNIT		
	RECTANGULAR	4"	6
	ROUND OR OVAL	4"	3
VARIABLE AIR VOLUME SUPPLY DUCTWORK	FROM TERMINAL UNIT TO AIR DEVICES	1"	12
RETURN DUCTWORK		-1"	12
EXHAUST DUCTWORK	FROM AIR DEVICES TO DISCHARGE POINT	-1"	6
	FROM FAN OUTLET TO DISCHARGE POINT	1/2"	6

- MINIMUM LEAKAGE CLASSIFICATION IS AS DEFINED IN THE LATEST EDITION OF THE ASHRAE FUNDAMENTALS HANDBOOK, DESIGN CHAPTER.
- MAKE EQUIVALENT DUCT SIZE CHANGES FROM ASHRAE TABLE OF EQUIVALENT RECTANGULAR AND ROUND DUCTS. NO VARIATION OF DUCT CONFIGURATION OR SIZES PERMITTED EXCEPT BY WRITTEN PERMISSION.
- CROSS BREAK OR BEAD ALL DUCTS IN EXCESS OF 18".

- LAP METAL DUCTS IN DIRECTION OF AIR FLOW. HAMMER DOWN EDGES AND SLIPS TO LEAVE SMOOTH DUCT INTERIOR. PROVIDE CORNER CLOSURES.

- BRANCH CONNECTIONS IN RECTANGULAR DUCTWORK SHALL BE 45 DEGREE ENTRY TYPE WITH 4" MINIMUM CONECTOR LENGTH.

- CONSTRUCT TEES, BENDS, ELBOWS WITH MINIMUM CENTER LINE RADIUS 1-1/2 TIMES WIDTH OF DUCT. WHERE NOT POSSIBLE AND WHERE RECTANGULAR ELBOWS USED, PROVIDE TURNING VANES.

- INCREASE DUCT SIZES MAXIMUM 15 DEGREE DIVERGENCE WHEREVER POSSIBLE. MAXIMUM DIVERGENCE: 20 DEGREE UPSTREAM OF EQUIPMENT, 30 DEGREE DOWNSTREAM.

- RIGIDLY CONSTRUCT METAL DUCTS WITH JOINTS MECHANICALLY TIGHT, AIRTIGHT, BRACED AND STIFFENED.

- SEAL ALL DUCTWORK (USING LIQUIDS, MASTICS, OR GASKETS, AS APPLICABLE) PER THE FOLLOWING TABLE.

DUCTWORK SEALING CHART	
STATIC PRESSURE CLASSIFICATION (W.C.)	REQUIRED SEALING
GREATER THAN 2"	ALL TRAVERSE JOINTS, LONGITUDINAL SEAMS AND DUCT WALL PENETRATIONS
2" AND LESS	TRAVERSE AND LONGITUDINAL JOINTS

- JOINTS IN RECTANGULAR DUCTWORK MAY BE MADE WITH DUCTMATE SYSTEM, NEXUS 4 BOLT DUCT CONNECTION SYSTEM, OR TDC.

- WORK INCLUDES ACCESS DOOR, BALANCING DAMPER, FLEXIBLE CONNECTION AND TURNING VANES.

- ACCESS DOORS SHALL BE UL LABELED. FABRICATE PER ASHRAE AND SMACNA. FURNISH MANUFACTURER'S SUBMITTAL DATA FOR THE ACCESS DOORS, BALANCING DAMPERS, FLEXIBLE CONNECTIONS AND TURNING VANES.

- ACCESS DOOR SHALL RATED FOR SAME STATIC PRESSURE AS DUCTWORK AND SHALL BE FRAMED, HINGED, GASKETED TYPE WITH SASH LOCKS, FULLY INSULATED.

- PROVIDE ACCESS DOORS FOR INSPECTION AND CLEANING BEFORE AND AFTER FILTERS, COILS, FANS, AUTOMATIC DAMPERS, FIRE OR COMBINATION FIRE/SMOKE DAMPERS, AND ELSEWHERE AS INDICATED. REVIEW LOCATIONS WITH ARCHITECT PRIOR TO FABRICATION. PROVIDE 6" X 8" QUICK OPENING ACCESS DOORS FOR INSPECTION AT BALANCING DAMPERS AND TURNING VANES.

- VOLUME DAMPER SHALL BE MULTIPLE OPPOSED BLADE TYPE, CLOSE FITTED IN DUCTS, SUITABLE FOR STATIC PRESSURE IN DUCTWORK AT INSTALLED LOCATION. DAMPERS 12" OR LESS IN HEIGHT SHALL HAVE SINGLE BLADE. DAMPER BLADES SHALL BE: STAMPED 16 GAUGE GALVANIZED STEEL. MAXIMUM LENGTH 48", SHAFT SPACING SHALL NOT EXCEED 9". BEARINGS SHALL BE MOLDED SYNTHETIC. POSITIONING DEVICE SHALL BE LOOKING LEVER AND QUADRANT TYPE, LEVER PARALLEL TO BLADE, LOCKED TO QUADRANT WITH THUMBSCREW OR WING NUT, END OF SHAFT NOTCHED PARALLEL TO DAMPER POSITION. CONSTRUCT DAMPER BLADES FOR MEDIUM AND HIGH PRESSURE. SYSTEMS WITH END BEARINGS OR OTHER SEALING DEVICE. SUPPLY LOCKING TYPE HANDLES.

- NOT ALL BALANCING DAMPERS REQUIRED FOR THE BALANCING WORK ARE SHOWN ON THE DRAWINGS. PROVIDE BALANCING DAMPERS AT POINTS ON LOW PRESSURE SUPPLY, RETURN, EXHAUST SYSTEMS WHERE BRANCHES ARE TAKEN FROM LARGER DUCTS AND AS REQUIRED FOR AIR BALANCING. COORDINATE WITH BALANCING CONTRACTOR AND PROVIDE ANY ADDITIONAL BALANCING DAMPERS REQUIRED. INSTALL DAMPERS IN ACCESSIBLE LOCATION.

- FLEXIBLE CONNECTION SHALL BE NEOPRENE COATED, 30 OZ. FIBERGLASS FABRIC, 8" WIDE, TIGHTLY COMBED INTO METAL EDGING STRIP. ATTACH DUCTING AND EQUIPMENT BY SCREWS OR BOLTS AT 6" INTERVALS. PLENUM RATED WHERE REQUIRED. FLEXIBLE CONNECTIONS EXPOSED TO WEATHER SHALL BE COATED WITH DOWPOINT HYPOLOK.

DUCTWORK (CONTINUED)

- TURNING VANES SHALL BE INSTALLED IN SUPPLY, RETURN, AND EXHAUST MITERED ELBOWS. THEY SHALL BE FORMED SINGLE WALL 38" MAXIMUM LENGTH) OR DOUBLE WALL (GREATER THAN 38" LENGTH) GALVANIZED STEEL BLADES. FOR MITERED DUCTWORK OTHER THAN STEEL, USE SAME TYPE MATERIAL AS DUCT. TURNING VANES INSTALLED IN UNEQUAL ELBOWS. ADJUSTABLE TYPE THAT REMAINS ALIGNED TO AIRSTREAM IN ALL POSITIONS.

- ALL DUCTWORK SHALL BE GALVANIZED SHEET METAL WITH INSULATION PER SPECIFICATIONS. FLEX DUCTS SHALL BE UL-181 LISTED, CLASS 1, FACTORY PRE-INSULATED 1-1/2", WITH INNER LINER AND STEEL HELIX. FLEX DUCTS SHALL NOT BE MORE THAN 5'-0" LONG.
- PAINT ALL DUCTWORK ABOVE CEILING RETURN GRILLES FLAT BLACK.

X. STATIC FIRE DAMPER

- STATIC FIRE DAMPERS WITH CURTAIN STYLE BLADES MEETING REQUIREMENTS OF UL STANDARD 555, SIXTH EDITION. GALVANIZED STEEL OR PRIME COATED STEEL. PROVIDE REINFORCEMENT IN CORNERS TO PROVIDE MAXIMUM RESISTANCE TO RACKING.

- FIRE RESISTANCE: DAMPERS SHALL HAVE A UL 555 FIRE RESISTANCE RATING OF 1-1/2 HOURS.

- FIRE CLOSURE TEMPERATURE: EACH FIRE DAMPER SHALL BE EQUIPPED WITH A FACTORY INSTALLED HEAT RESPONSIVE DEVICE (FUSIBLE LINK) RATED TO CLOSE THE DAMPER WHEN TEMPERATURE AT THE DAMPER REACHES 165 F.

- FIRE DAMPERS SHALL HAVE BLADES RETAINED IN A RECESS SO FREE AREA OF CONNECTING DUCTWORK IS NOT REDUCED (TYPE B).

Y. DYNAMIC FIRE DAMPERS

- DYNAMIC FIRE DAMPERS WITH STEEL 3-V BLADES MEETING REQUIREMENTS OF UL STANDARD 555, SIXTH EDITION. GALVANIZED STEEL OR PRIME COATED BLACK STEEL. PROVIDE REINFORCEMENT TO CORNERS TO PROVIDE MAXIMUM RESISTANCE TO RACKING.

- FIRE RESISTANCE: DAMPERS SHALL HAVE UL 555 FIRE RESISTANCE RATING OF 1-1/2 HOURS.

- FIRE CLOSURE TEMPERATURE: EACH FIRE DAMPER SHALL BE EQUIPPED WITH A FACTORY INSTALLED HEAT RESPONSE DEVICE (FUSIBLE LINK) RATED TO CLOSE THE DAMPER WHEN TEMPERATURE AT THE DAMPER REACHES 165 F.

- DIFFERENTIAL PRESSURE: DAMPERS SHALL HAVE A MINIMUM UL 555 DIFFERENTIAL PRESSURE RATING OF 4 INCHES W.G.

- VELOCITY: DAMPERS SHALL HAVE A MINIMUM UL 555 VELOCITY RATING OF 3000 FPM.

- COMBINATION SMOKE AND FIRE DAMPER
 - COMBINATION FIRE SMOKE DAMPERS WITH STEEL 3-V BLADES MEETING REQUIREMENTS OF UL STANDARD 555, SIXTH EDITION AND UL STANDARD 555, FOURTH EDITION, ACTUATED BY FUSIBLE LINK AND SMOKE DETECTOR, 6" MAXIMUM BLADE WIDTH. GALVANIZED STEEL OR PRIME COATED BLACK STEEL. REINFORCE CORNERS TO MAXIMIZE RESISTANCE TO RACKING.

- LEAKAGE RATING: CLASS 1 (DUCT STATIC PRESSURE EXCEEDS 2" W.C.) OR CLASS II (DUCT STATIC PRESSURE LESS THAN 2" W.C.)

- FIRE RESISTANCE: DAMPERS SHALL HAVE A UL 555 FIRE RESISTANCE RATING OF 1-1/2 HOURS.

- FIRE CLOSURE TEMPERATURE: EACH COMBINATION FIRE SMOKE DAMPER SHALL BE EQUIPPED WITH A THERMOSTAT TO CLOSE THE DAMPER AT 165 F.

- DIFFERENTIAL PRESSURE: DAMPERS SHALL HAVE A MINIMUM UL 555 DIFFERENTIAL PRESSURE RATING OF 4 INCHES W.G.

- VELOCITY: DAMPERS SHALL HAVE A MINIMUM UL 555 VELOCITY RATING OF 3000 FPM.

- OPERATING SHAFT: 90 DEGREES BETWEEN CLOSED AND OPEN, SUITABLE FOR LINKING TO AND OPERATION BY DAMPER OPERATOR, WITH END SWITCH TO SIGNAL, FULL OPEN POSITION.

- ACTUATORS: TYPE: ELECTRIC, 120 VOLT AC, 60 HZ, 2-POSITION, FAIL CLOSE, EXTERNAL MOUNTED.


- PROVIDE ACCESS DOORS FOR INSPECTION AND CLEANING BEFORE AND AFTER FILTERS, COILS, FANS, AUTOMATIC DAMPERS, FIRE OR COMBINATION FIRE/SMOKE DAMPERS, AND ELSEWHERE AS INDICATED. REVIEW LOCATIONS WITH ARCHITECT PRIOR TO FABRICATION.

D

C


B

A



IN-LINE EXHAUST FAN DIAGRAM

NOT TO SCALE



DUCT TAKE-OFF DIAGRAM

NOT TO SCALE

FAN SCHEDULE

SYMBOL	MANUFACTURER	MODEL	FAN TYPE	SERVICE	CFM @ 5000'	S.P. IN W.C. @ S.L.	ELECTRICAL DATA			DRIVE TYPE	DAMPER TYPE	SONES	WEIGHT (LBS)	REMARKS
							VOLT/ PHASE	RPM	WATTS					
EF-1	GREENHECK	CSP-A1410	INLINE	EXHAUST	1200	0.5	120/1	120	822	DIRECT	BACKDRAFT	2.5	60	1, 2, 3, 4

- REMARKS:
1. ACCEPTABLE MANUFACTURERS INCLUDE: ACME, CARNES, COOK, PENN, AND SOLER & PALAU.
 2. PROVIDE FAN WITH UNIT MOUNTED SPEED CONTROL SWITCH.
 3. PROVIDE WITH DISCHARGE DUCT COLLAR.
 4. FAN CONTROLLED VIA LIGHT OCCUPANCY SENSOR. FAN SHALL RUN FOR 15 MINUTES AFTER LIGHTS SHUT-OFF.

SPECIFICATION (INLINE – MOTOR INSIDE):

- A. HOUSING: ACOUSTICALLY INSULATED STEEL.
B. FAN WHEEL: CENTRIFUGAL TYPE.
C. FAN WHEEL AND MOTOR ASSEMBLY: MOUNT ON VIBRATION ISOLATORS, TOTALLY REMOVABLE FROM HOUSING.

AIR DEVICE SCHEDULE

SYMBOL	TYPE	MANUFACTURER	MODEL	FRAME	MATERIAL	FINISH	DAMPER TYPE	ACCESSORIES	REMARKS
EG-1	EXHAUST GRILLE	PRICE	S30	LAY-IN	STEEL	WHITE POWDER COAT	NONE	NONE	45° DEFLECTION, 3/4" SPACING, 8x8
TG-1	TRANSFER GRILLE	PRICE	PDDR	LAY-IN	STEEL	WHITE POWDER COAT	NONE	NONE	24x24 FACE, 14" NECK

- NOTES:
1. EQUIPMENT SCHEDULE BASED ON PRICE. ACCEPTABLE MANUFACTURERS: CARNES, KRUGER, METAL-AIRE, PRICE, TITUS
 2. MAX NC RATING 30. PROVIDE NECESSARY FRAME AND TRIM FOR CEILING APPLICATION.

SLATERPAULL

hord | coplan | macht

1331 Nineteenth Street
Denver, CO. 80202

P 303.607.0977
www.slaterpaul.com

CONSULTANT:



M.E.P. ENGINEERING
6402 S. Troy Circle
Centennial, CO 80111
info@mep-eng.com

(W) 303.936.1633
(F) 303.934.3299
www.mep-eng.com



PROJECT:

CS AUDITORIUM
RESTROOM
RENOVATION

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

COLORADO SPRINGS
CITY AUDITORIUM

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/2015 BIDDING AND ISSUE FOR
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 15242

DRAWN BY: MBJ

CHECKED BY: MAB

APPROVED BY: MCS


SHEET TITLE:

MECHANICAL
SCHEDULES AND
DIAGRAMS

M-101

SHEET OF

C:\Users\RSchutz\Documents\15242_MEP_RSchutz.rvt
10/20/2015 1:05:06 PM



GENERAL NOTES:

1. CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS BEFORE COMMENCING WORK AND NOTIFY ARCHITECT AND ENGINEER IN WRITING OF DISCREPANCIES FROM THE CONTRACT DRAWINGS. COMMENCEMENT OF WORK WITHOUT NOTIFICATION CONSTITUTES ACCEPTANCE OF EXISTING CONDITIONS.
2. COORDINATE ALL DEMOLITION AND NEW WORK WITH ALL OTHER DIVISIONS AS REQUIRED TO PROVIDE A COMPLETE INSTALLATION.

DRAWING NOTES:

1. REMOVE EXISTING EXHAUST DUCTWORK ASSOCIATED WITH TOILET ROOM ABOVE. TOILET ROOM ABOVE WILL BE REMODELED. RE: M-111. CAP DUCTWORK.
2. REMOVE EXISTING EXHAUST DUCT UP TO REMODELED TOILET ROOM ABOVE. RE: M-111.
3. EXISTING EXHAUST DUCT AND FAN SYSTEM FOR BASEMENT TOILET ROOMS TO REMAIN.

SLATERPAULL
hord | coplan | macht

1331 Nineteenth Street | P 303.607.0977
Denver, CO. 80202 | www.slaterpaul.com

CONSULTANT:



PROJECT:

**CS AUDITORIUM
RESTROOM
RENOVATION**

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

**COLORADO SPRINGS
CITY AUDITORIUM**

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/2015 BIDDING AND ISSUE FOR
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 15242

DRAWN BY: MBJ

CHECKED BY: MAB

APPROVED BY: MCS



SHEET TITLE:

**ENLARGED
BASEMENT
MECHANICAL PLAN**

M-110

SHEET OF

C:\Users\RSStutz\Documents\15242_MEP_RSStutz.rvt
10/20/2015 1:05:08 PM



LEVEL 1 ENLARGED RESTROOM MECHANICAL DEMO PLAN

SCALE: 1/4" = 1'-0"

DRAWING NOTES:



1. REMOVE EXISTING EXHAUST GRILLE AND ASSOCIATED DUCTWORK.
2. REMOVE EXISTING EXHAUST DUCTWORK.
3. REMOVE EXISTING EXHAUST DUCTWORK DOWN TO BASEMENT. RE: M-110.
4. EXISTING RADIANT HEATERS TO REMAIN. CONTRACTOR TO INSPECT FOR PROPER WORKING ORDER AND REPORT.

GENERAL NOTES:

1. CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS BEFORE COMMENCING WORK AND NOTIFY ARCHITECT AND ENGINEER IN WRITING OF DISCREPANCIES FROM THE CONTRACT DRAWINGS. COMMENCEMENT OF WORK WITHOUT NOTIFICATION CONSTITUTES ACCEPTANCE OF EXISTING CONDITIONS.
2. COORDINATE ALL DEMOLITION AND NEW WORK WITH ALL OTHER DIVISIONS AS REQUIRED TO PROVIDE A COMPLETE INSTALLATION.


DRAWING NOTES:

1. LOUVER PROVIDED BY DIVISION 8. PROVIDE MINIMUM 1.5 SQUARE FEET FREE AREA.
2. SUSPEND FAN FROM STRUCTURE ABOVE ACCESSIBLE CEILING. LOCATE FAN IN LOCATION FOR EASE OF MAINTENANCE. FIELD VERIFY.
3. PROVIDE DUCT TAKE-OFF, TYPICAL.
4. PLENUM ON BACK OF LOUVER.



LEVEL 1 ENLARGED RESTROOM MECHANICAL PLAN

SCALE: 1/4" = 1'-0"



Key Plan

SLATERPAULL

hord | coplan | macht

1331 Nineteenth Street
Denver, CO. 80202

P 303.607.0977

www.slaterpaul.com

CONSULTANT:



M.E.P. ENGINEERING

6402 S. Troy Circle
Centennial, CO 80111
info@mep-eng.com

(W) 303.936.1633

(F) 303.934.3299

www.mep-eng.com



PROJECT:

**CS AUDITORIUM
RESTROOM
RENOVATION**

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

**COLORADO SPRINGS
CITY AUDITORIUM**

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/2015 BIDDING AND ISSUE FOR
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 15242

DRAWN BY: MBJ

CHECKED BY: MAB

APPROVED BY: MCS

SHEET TITLE:

**ENLARGED FIRST
LEVEL MECHANICAL
PLANS**

M-111

SHEET OF

DIVISION 220000 - PLUMBING SPECIFICATIONS

BASIC MECHANICAL REQUIREMENTS

- QUALITY ASSURANCE:
- IF MANUFACTURER'S MATERIAL OR EQUIPMENT IS LISTED IN SCHEDULES OR ON DRAWINGS, THEY ARE TYPES TO BE PROVIDED FOR ESTABLISHMENT OF SIZE, CAPACITY, GRADE, AND QUALITY. IF OTHER ACCEPTABLE MANUFACTURERS ARE USED, COST OF ANY CHANGE IN CONSTRUCTION REQUIRED BY THEIR USE SHALL BE BORNE BY CONTRACTOR.
 - EQUIPMENT SHALL CONFORM TO STATE AND/OR LOCAL ENERGY CONSERVATION STANDARDS.
 - COMPLY WITH RULES AND REGULATIONS OF LOCAL UTILITY COMPANIES. INCLUDE COST OF VALVES, VALVE BOXES, METER BOXES, METERS, ACCESSORY EQUIPMENT REQUIRED FOR PROJECT.
- INTENT AND INTERPRETATIONS:
- IT IS THE INTENT OF THESE DRAWINGS AND SPECIFICATIONS TO RESULT IN A COMPLETE MECHANICAL INSTALLATION IN COMPLETE ACCORDANCE WITH ALL APPLICABLE LOCAL CODES AND ORDINANCES.
 - DRAWINGS ARE DIAGRAMMATIC IN CHARACTER AND DO NOT NECESSARILY INDICATE EVERY REQUIRED PIPE, OFFSET, TRANSITION, ETC. ITEMS NOT SPECIFICALLY MENTIONED IN THE SPECIFICATION OR NOTED ON THE DRAWINGS, BUT WHICH ARE NECESSARY TO MAKE A COMPLETE WORKING INSTALLATION, SHALL BE INCLUDED.
 - DRAWINGS AND SPECIFICATIONS ARE COMPLEMENTARY. WHATEVER IS CALLED FOR IN EITHER IS BINDING AS THOUGH CALLED FOR IN BOTH. IF THERE IS A CONFLICT IN THE CONTRACT DOCUMENTS, THE MORE DEMANDING AND COSTLY DESIGN SHALL BE SELECTED FOR BIDDING PURPOSES. THE CONTRACTOR SHALL IMMEDIATELY PRESENT THE CONFLICT FOUND IN THE CONTRACT DOCUMENTS TO THE ARCHITECT/ENGINEER FOR RESOLUTION. IF THE RESOLUTION FAVORS A LESS COSTLY DESIGN, THE CONTRACTOR WILL BE REQUIRED TO REIMBURSE THE DIFFERENCE IN COST.
 - DRAWINGS SHALL NOT BE SCALED FOR ROUGH-IN MEASUREMENTS OR USED AS SHOP DRAWINGS. WHERE DRAWINGS ARE REQUIRED FOR THESE PURPOSES OR HAVE TO BE MADE FROM FIELD MEASUREMENTS, TAKE THE NECESSARY MEASUREMENTS AND PREPARE THE DRAWINGS.
 - BEFORE ANY WORK IS INSTALLED, DETERMINE THAT EQUIPMENT WILL PROPERLY FIT THE SPACE, THAT REQUIRED CLEARANCES CAN BE MAINTAINED AND THAT EQUIPMENT CAN BE LOCATED WITHOUT INTERFERENCE BETWEEN SYSTEMS, WITH STRUCTURAL ELEMENTS, OR WITH THE WORK OF OTHER TRADES.
 - IF CONFLICTS ARE DISCOVERED IN CONTRACT DOCUMENTS AS WORK PROGRESSES, SUBMIT A SET OF DRAWINGS MARKED WITH RED PENCIL SHOWING RECOMMENDED MODIFICATIONS TO THE ARCHITECT FOR APPROVAL PRIOR TO INSTALLATION.
 - CONTRACTOR SHALL COORDINATE WITH ALL OWNER SUPPLIED EQUIPMENT PRIOR TO ROUGH-IN. ENSURE ALL EQUIPMENT CONNECTIONS ARE PROVIDED FOR AND THAT THE INSTALLATION WILL MEET ALL LOCAL AND NATIONAL CODE REQUIREMENTS.

JOB CONDITIONS:

OWNER, COOPERATE, AND COORDINATE WORK WITH OTHER TRADES. COORDINATE CEILING CAVITY SPACE CAREFULLY WITH ALL TRADES. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR AND HAVE CONTROL OVER CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AS WELL AS COORDINATING ALL PARTS OF THE WORK UNDER THE CONTRACT. UNLESS THE CONTRACT DOCUMENTS GIVE OTHER SPECIFIC INSTRUCTIONS CONCERNING THESE MATTERS.

PERMITS AND FEES:

- ARRANGE AND PAY FOR ALL INSPECTIONS, PERMITS, LICENSES, CERTIFICATES, AND FEES REQUIRED IN CONNECTION WITH WORK.

SUBMITTALS AND SHOP DRAWINGS:

- CONFORM TO REQUIREMENTS OF DIVISION 1 AND FOLLOWING PARAGRAPHS.
- SUBMITTALS SHALL INCLUDE CATALOG CUT-SHEETS AND MANUFACTURER'S DATA SHEETS.
- PRIOR TO ORDERING EQUIPMENT OR BEGINNING INSTALLATION WORK, ASSEMBLE, PREPARE, AND FURNISH SUBMITTALS AND SHOP DRAWINGS REQUIRED FOR PROJECT. FURNISH SUBMITTALS AND SHOP DRAWINGS AS REQUIRED BY INDIVIDUAL SECTIONS OF SPECIFICATIONS.

CONTRACTOR SHALL THOROUGHLY CHECK SUBCONTRACTORS' OR VENDORS' SUBMITTALS AND SHOP DRAWINGS AND, AFTER APPROVING THEM, SUBMIT THEM FOR REVIEW. SUBMITTALS AND SHOP DRAWINGS THAT DO NOT BEAR CONTRACTOR'S REVIEW STAMP WILL BE RETURNED NOT REVIEWED.

IF DISCREPANCIES BETWEEN SUBMITTALS, SHOP DRAWINGS, AND CONTRACT DOCUMENTS ARE DISCOVERED EITHER PRIOR TO OR AFTER SUBMITTALS AND SHOP DRAWINGS ARE REVIEWED, REQUIREMENTS OF CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE. SUBMITTALS AND SHOP DRAWINGS WHICH ARE SUBMITTED, BUT WHICH ARE NOT REQUIRED BY CONTRACT DOCUMENTS, WILL BE RETURNED NOT REVIEWED.

SUBMITTALS AND SHOP DRAWINGS SHALL IDENTIFY SPECIFIC EQUIPMENT WITH NUMBERS OR LETTERS IDENTICAL TO THOSE LISTED OR SCHEDULED ON THE DRAWINGS OR SPECIFICATIONS.

RECORD DOCUMENTS:

- KEEP IN CUSTODY DURING ENTIRE PERIOD OF CONSTRUCTION, A CURRENT SET OF DOCUMENTS INDICATING CHANGES THAT HAVE BEEN MADE TO THE CONTRACT DOCUMENTS.
- UPON COMPLETION OF WORK, SUBMIT THE COMPLETE SET OF RECORD DOCUMENTS TO THE ARCHITECT.

PROTECTION OF EQUIPMENT:

- PROTECT MATERIALS AND EQUIPMENT FROM PHYSICAL DAMAGE, CONSTRUCTION DIRT, AND THE ELEMENTS FROM TIME OF SHIPMENT TO TIME INSTALLATION IS ACCEPTED BY OWNER.

GUARANTEE:

- GUARANTEE MATERIALS, WORKMANSHIP, AND OPERATION OF EQUIPMENT INSTALLED FOR PERIOD OF ONE YEAR FROM DATE OF ACCEPTANCE OF ENTIRE WORK. REPAIR OR REPLACE ANY PART OF WORK WHICH SHOWS DEFECT DURING THAT TIME.
- BE RESPONSIBLE FOR DAMAGE TO PROPERTY OF OWNER OR TO WORK OF OTHER CONTRACTORS DURING CONSTRUCTION AND GUARANTEE PERIOD.
- FURNISH EQUIPMENT WARRANTIES TO OWNER.

MECHANICAL EQUIPMENT WIRING AND CONNECTIONS:

- VOLTAGE CHARACTERISTICS SHALL BE AS IN ELECTRICAL DIVISION OF SPECIFICATIONS AND ON ELECTRICAL DRAWINGS.

TEMPORARY FACILITIES:

- USE OF EXISTING EQUIPMENT FOR TEMPORARY HEATING OR COOLING. DO NOT USE NEW OR EXISTING BUILDING EQUIPMENT WITHOUT WRITTEN PERMISSION FROM OWNER.

INSPECTIONS:

- DO NOT COVER UP OR ENCLOSE WORK UNTIL INSPECTED, TESTED, AND APPROVED. ANY WORK ENCLOSED OR COVERED UP BEFORE SUCH APPROVAL SHALL BE UNCOVERED, TESTED, AND APPROVED.

ACCESS DOORS:

- FURNISH HINGED STEEL ACCESS DOORS WITH CONCEALED LATCH, WHETHER SHOWN OR NOT, IN WALLS AND PLASTER OR GYPSUM BOARD CEILINGS FOR ACCESS TO CONCEALED VALVES, SHOCK ARRESTERS, AIR VENTS, MOTORS, FANS, BALANCING VALVES, OR OTHER OPERATING DEVICES REQUIRING ADJUSTMENT OR SERVICING.
- ACCESS DOOR SHALL BE SIZE OF EQUIPMENT TO BE REMOVED OR 24" BY 24" IF USED FOR SERVICE ONLY.

INSTALLATION:

- WORKMANSHIP SHALL BE FIRST QUALITY. APPEARANCE OF WORK SHALL BE OF EQUAL IMPORTANCE TO ITS MECHANICAL OPERATION. LACK OF QUALITY WORKMANSHIP SHALL BE REASON FOR REJECTION OF SYSTEM IN PART OR IN WHOLE.
- INSTALL SO THAT ALL VALVES AND EQUIPMENT CAN BE EASILY ACCESSED AND SERVICED BY ADEQUATE CLEARANCE, INSTALLATION OF ACCESS DOORS, UNIONS IN PIPING, OR OTHER METHODS.
- COMPLETE INSTALLATION SHALL FUNCTION SMOOTHLY AND NOISELESSLY.
- INSTALL EQUIPMENT AND MATERIALS PER MANUFACTURER'S RECOMMENDATIONS AND LOCAL CODES OR REGULATIONS.
- PLACE OR REPLACE ALL EQUIPMENT NAMEPLATES WHERE THEY CAN BE SEEN AND READ WITHOUT DIFFICULTY.
- FLUSH PIPES FREE OF FOREIGN SUBSTANCES BEFORE INSTALLING VALVES OR MAKING FINAL CONNECTIONS. CLEAN ALL PIPING AND EQUIPMENT.

COMPLETION:

- CLEAN INSULATION COVERING, PIPES, EQUIPMENT, AND ACCESSORIES TO RECEIVE PRIME COAT OF PAINT. CLEAN EQUIPMENT RECEIVED WITH PRIME COAT TO RECEIVE FINAL COAT.
- INSTRUCT OWNER IN OPERATION AND MAINTENANCE OF PLUMBING SYSTEMS. MINIMUM PARTICIPANTS SHALL INCLUDE PLUMBING CONTRACTOR AND CONTROLS CONTRACTOR REPRESENTATIVES.
- AFTER TESTS AND ADJUSTMENTS HAVE BEEN MADE AND SYSTEMS PROUNOUNCED SATISFACTORY FOR PERMANENT OPERATION, REFINISH DAMAGED FINISH AND LEAVE EVERYTHING IN PROPER WORKING ORDER AND APPEARANCE.
- ON COMPLETION OF WORK, REMOVE TOOLS, SCAFFOLDING, DEBRIS, ETC., FROM GROUNDS AND LEAVE PREMISES CLEAN.

BASIC MECHANICAL REQUIREMENTS (CONTINUED)

- OPERATION AND MAINTENANCE MANUALS:
- PRIOR TO COMPLETION OF PROJECT, SUBMIT OPERATION AND MAINTENANCE MANUALS FOR MECHANICAL EQUIPMENT WITH MOVING OR MOVABLE PARTS, INCLUDING PLUMBING SYSTEMS, PER IECC. INSTRUCTIONS SHALL BE IN PAMPHLET, TYPEWRITTEN OR PDF FORM, INSTRUCTIONS FOR EACH PIECE OF EQUIPMENT SHALL BE INDICATED BY A SEPARATE TAB.
 - INCLUDE STARTING, STOPPING, LUBRICATION, PREVENTATIVE MAINTENANCE SCHEDULE, AND ADJUSTMENT INFORMATION FOR EACH PIECE OF EQUIPMENT.

PIPE AND PIPE FITTINGS

- QUALITY ASSURANCE:
- WELDING MATERIALS AND LABOR SHALL CONFORM TO ASME CODE FOR PRESSURE PIPING AND APPLICABLE STATE LABOR REGULATIONS.
 - USE WELDERS FULLY QUALIFIED AND LICENSED BY STATE AUTHORITIES. FURNISH CERTIFICATION FROM APPROVED TESTING AGENCY OR NATIONAL CERTIFIED PIPE WELDING BUREAU THAT WELDERS PERFORMING WORK ARE CERTIFIED.
 - ALL PIPING MATERIALS SHALL COMPLY WITH LOCAL CODES.
- UNIONS AND COUPLINGS:
- 2" AND SMALLER: 125 PSI CAST IRON FOR THREADED FERROUS PIPING; BRONZE FOR COPPER OR BRASS PIPE, SOLDERED JOINTS.
 - 2-1/2" AND LARGER: 150 PSI FORGED STEEL FLANGES, RAISED FACE WITH WELDING NECK, FOR FERROUS PIPING; BRONZE FLANGES FOR COPPER OR BRASS PIPING; GASKETS FOR WATER PIPING TO 140 F EQUAL TO GARLOCK PREMIUM GRADE STYLE 22 RED RUBBER, 1/16" THICK; GASKETS FOR NATURAL GAS EQUAL TO GARLOCK BLUE-GRAD STYLE 3000 SYNTHETIC FIBER WITH NITRILE BINDER, 1/16" THICK; GASKETS FOR CONDENSATE, AND WATER ABOVE 140 F AS MANUFACTURED BY FLEXITALIC.
 - DIELECTRIC UNIONS AND FLANGES: EPDM OR EQUAL HAVING PROPER GASKET MATERIAL FOR CONNECTION OF DISSIMILAR METALS; UNIONS, 2" AND SMALLER, DIELECTRICALLY GASKETED FLANGES, 2-1/2" AND LARGER, USE DIELECTRIC CONNECTIONS WHEREVER JOINING DISSIMILAR METALS IN OPEN DOMESTIC WATER SYSTEMS.

- EXECUTION:
- VERIFY LOCATION(S) OF ALL AIR PLENUMS. ALL PIPING AND SUPPORT MATERIALS INSTALLED IN AIR PLENUMS SHALL BE PLENUM RATED. DO NOT INSTALL SPECIFIED NON-PLENUM RATED MATERIALS IN AIR PLENUMS. USE PLENUM RATED OPTIONS.
 - ROUTE PIPING IN ORDERLY MANNER AND MAINTAIN PROPER SLOPE.
 - CONCEAL PIPING IN WALLS OR ABOVE CEILING UNLESS OTHERWISE NOTED.
 - MAINTAIN FOLLOWING PIPE SLOPES UNLESS OTHERWISE NOTED ON DRAWINGS:
 - COOLING COIL CONDENSATE DRAIN PIPING: 1/8" DOWN PER LINEAR FOOT IN THE DIRECTION OF FLOW.
 - SANITARY WASTE 2-1/2" AND SMALLER: 1/4" DOWN PER 1'-0" IN DIRECTION OF FLOW.
 - SANITARY WASTE 3" AND LARGER: 1/8" DOWN PER 1'-0" IN DIRECTION OF FLOW.
 - GREASE WASTE: 1/4" DOWN PER 1'-0" IN DIRECTION OF FLOW.
 - SANITARY VENT PIPING, ALL SIZES: GRADED AND CONNECTED AS TO DRIP BACK BY GRAVITY TO THE DRAINAGE PIPE IT SERVES.
 - STORM DRAIN PIPING, ALL SIZES: 1/8" DOWN PER 1'-0" IN DIRECTION OF FLOW.
 - INSTALL PIPING TO ALLOW FOR EXPANSION AND CONTRACTION WITHOUT STRESSING PIPE OR CONNECTED EQUIPMENT.
 - PROVIDE CLEARANCE FOR INSTALLATION OF INSULATION AND FOR ACCESS TO VALVES, AIR VENTS, DRAINS, UNIONS.
 - INSTALL SAME TYPE PIPING MATERIAL SPECIFIED FOR INSIDE BUILDING TO 5'-0" OUTSIDE BUILDING.
 - MAKE CONNECTIONS TO EQUIPMENT WITH UNIONS OR FLANGES.

- STEEL PIPE CONNECTIONS:
- 2" AND SMALLER - THREADED; 2-1/2" AND LARGER - WELDED.
 - DO NOT USE MITERED AND WELDED ELBOWS IN LIEU OF FITTINGS.
 - DIE CUT THREADED JOINTS WITH FULL CUT STANDARD TAPER PIPE THREADS WITH 1/2" WIDE WHITE TEFLON PIPE JOINT SEALANT TAPE APPLIED TO MALE THREADS ONLY.
 - USE ONLY MALLEABLE IRON THREADED PIPE FITTINGS FOR GAS PIPING.
 - USE BUTT WELD FITTINGS FOR WELDED STEEL PIPES. USE OXYACETYLENE OR ELECTRIC ARC PROCESS.

- CAST IRON PIPE CONNECTIONS:
- JOINTS FOR BELL AND SPIGOT PIPES: NEOPRENE GASKETING SYSTEM WITH "TY-SEAL" WATER SOLUBLE LUBRICANT.
 - JOINTS FOR PLAIN END PIPE ABOVE GRADE: STAINLESS STEEL BAND TYPE GASKET AND CLAMP MECHANICAL FASTENER.
 - USE HUBLESS PIPING ABOVE GRADE ONLY.

- COPPER PIPE CONNECTIONS:
- 2-1/2" AND SMALLER: USE 15% SILVER BRAZING ALLOY AND SILVER BRAZING FLUX ON BELOW-GRADE JOINTS. USE 95% TIN, 5% ANTIMONY LEAD-FREE SOLDER AND ASTM B813-91 NON-CORROSIVE STM 1.0 FLUX ON JOINTS. APPLY FLUX ON CLEANED END OF PIPE AND INSIDE FITTINGS WITH SMOOTH EVEN COATS.
 - 3" AND LARGER: USE 15% SILVER BRAZING ALLOY AND SILVER BRAZING FLUX. APPLY FLUX ON CLEANED END OF PIPE AND INSIDE FITTINGS WITH SMOOTH EVEN COATS.

APPLICATION OF PIPING SYSTEMS:

SERVICE	MATERIAL
EQUIPMENT DRAINS AND OVERFLOWS	COPPER, TYPE M OR DWV, HARD DRAWN
SANITARY DRAIN AND VENT ABOVE SLAB-ON-GRADE	COPPER, TYPE DWV, HARD DRAWN; CAST IRON; SCH 40 PVC (PVC NOT ALLOWED IN ANY RETURN AIR PLENUM)
SANITARY DRAIN AND VENT BELOW SLAB-ON-GRADE INSIDE BUILDING	CAST IRON; SCHEDULE 40 PVC (PVC NOT ALLOWED IN ANY RETURN AIR PLENUM)
STORM DRAIN INSIDE BUILDING	CAST IRON; SCHEDULE 40 PVC (PVC NOT ALLOWED IN ANY RETURN AIR PLENUM)
DOMESTIC WATER UNBURIED	COPPER, TYPE L, HARD DRAWN; CROSS-LINKED POLYETHYLENE (PEX); ASTM F877 FOR DOMESTIC HOT AND COLD WATER
DOMESTIC WATER BURIED	COPPER, TYPE K, HARD DRAWN; CROSS-LINKED POLYETHYLENE (PEX); ASTM F877 FOR DOMESTIC HOT AND COLD WATER
DOMESTIC WATER EXPOSED AT FIXTURES	SEAMLESS BRASS PIPE, CHROME PLATED
GAS PIPING	SCHEDULE 40 BLACK STEEL

- CAST IRON PIPING AND FITTINGS:
- CAST IRON PIPING SHALL BEAR THE COLLECTIVE TRADEMARK OF THE CAST IRON SOIL PIPE INSTITUTE (CISPI) AND LISTED BY NSF INTERNATIONAL.
 - HUBLESS STANDARD DUTY CAST IRON PIPE AND FITTINGS SHALL CONFORM TO CISPI 310 AND LISTED BY NSF INTERNATIONAL.

UNDERGROUND PIPE INSTALLATION

- PROJECT STEEL PIPE INSTALLED BELOW GRADE AND TO MINIMUM 6" ABOVE GRADE WITH FACTORY APPLIED COVERING, PRO CO FELT AND PIPE LINE ENAMEL NO. 4 DOUBLE WRAP OR X-TRU-COAT PLASTIC COATING. PROTECT FIELD JOINTS ON STEEL PIPE BY WITH TAPECOAT COMPANY PRIME COAT AND ONE LAYER OF TAPECOAT #20 HEAT APPLIED, 62 MIL TAPE PER MANUFACTURER'S RECOMMENDATIONS.
- PROVIDE TRIBUT BLOCK AT ALL DIRECTION CHANGES ON PRESSURE PIPE.
- BURY ALL OUTSIDE WATER PIPING MINIMUM 5'-0" BELOW GRADE TO TOP OF PIPE.
- BURY ALL OUTSIDE GAS PIPING MINIMUM 1'-6" BELOW GRADE TO TOP OF PIPE.

VALVES

- SUBMITTALS:
- FURNISH MANUFACTURER'S SUBMITTAL DATA FOR VALVES.
 - VALVES SHALL BE OF SAME MANUFACTURER WHERE POSSIBLE. VALVE SEATS AND MATERIALS SHALL BE SUITABLE FOR SERVICE INTENDED.
- ACCEPTABLE MANUFACTURERS:
- BALL VALVE: APOLLO, KITZ, NIBCO.
 - GAS VALVE: DEZURIK.

- RATINGS:
- UNLESS OTHERWISE INDICATED, VALVES SHALL BE SUITABLE FOR 200 PSIG WOG AND 250

- SHUTOFF VALVE:
- BALL VALVE, ALL SIZES: TWO-PIECE BRONZE OR FORGED BRASS BODY WITH PTFE SEATS, PRESSURE RATED TO 150 SW/PSIG WOG, FULL PORT, BLOWOUT PROOF SYSTEM AND POSITIVE SHUT-OFF. PACKING GLAND WITH PTFE PACKING. STEM EXTENSION WHERE INSULATED, LOCKABLE HANDLE.

VALVES (CONTINUED)

- BALANCING VALVE:
- FULL PORTED BALL VALVE WITH BALANCING STOPS.
- CHECK VALVE:
- 2" AND SMALLER: BRONZE, SWING DISC, SOLDER OR THREADED ENDS.
 - 2-1/2" AND LARGER: IRON BODY, BRONZE TRIM, SWING DISC, RENEWABLE DISC AND SEAT, FLANGED ENDS.
 - SPRING LOADED, SILENT TYPE, CAST IRON BODY WITH BUNA-N SEATS SUITABLE FOR 250F. WAFER AND DISCS OF ALUMINUM, BRONZE, OR DUCTILE IRON. SHAFT AND SPRINGS TYPE 316 STAINLESS STEEL.
- GAS VALVE:
- IRON OR FORGED BRASS BODY INDOORS; BRONZE OR FORGED BRASS BODY OUTDOORS.
 - FORGED BRASS BALL VALVE: CERTIFIED TO CSA, ASME B16.33, AND UL FOR GAS PIPING SYSTEMS.
- DRAIN VALVE:
- BALL VALVE WITH NIPPLE, CAP, HOSE THREAD.
- INSTALLATION:
- PROVIDE VALVES SUITABLE TO CONNECT TO ADJOINING PIPING AS SPECIFIED FOR PIPE JOINTS. USE PIPE SIZE VALVES.
 - 2" AND SMALLER: THREADED OR SOLDERED.
 - 2-1/2" AND LARGER: FLANGED.
 - SOLDER OR SCREW TO SOLDER ADAPTERS FOR COPPER TUBING.
 - PROVIDE DRAIN VALVES AT MAIN SHUT-OFF VALVES, LOW POINTS OF PIPING AND APPARATUS.
 - USE SPRING LOADED CHECK VALVES AT PUMPS AND WHERE INSTALLED IN VERTICAL POSITION.

SUPPORTS, ANCHORS, SEALS

- REFERENCE STANDARDS:
- PIPE SUPPORTS: ANSI B31.1, POWER PIPING.
- INSERTS:
- MALLEABLE IRON CASE, GALVANIZED STEEL SHELL, EXPANDER PLUG FOR THREADED CONNECTION WITH LEAVES ADJUSTMENT, TOP SLOT FOR REINFORCING RODS, LUGS FOR ATTACHING TO FORMS. USE INSERTS AND ANCHORS SUITABLE FOR TYPE OF STRUCTURAL CONDITIONS AND COMPONENTS.
- PIPE HANGERS AND SUPPORTS:
- HANGERS, PIPE SIZES TO 1-1/2": ADJUSTABLE STEEL RING (INSULATED PIPE) OR BAND (UNINSULATED PIPE).
 - HANGERS, HOT PIPE SIZES 2" TO 4" AND ALL COLD PIPE SIZES: ADJUSTABLE STEEL CLEVIS.
 - WALL SUPPORT, PIPE SIZES TO 3": CARBON STEEL HOOK.
 - WALL SUPPORT, PIPE SIZES 4" AND OVER: WELDED STEEL BRACKET AND PIPE STRAP. ADJUSTABLE STEEL YOKE PIPE ROLL OR ROLLER CHAIR FOR HOT PIPE SIZES 5" AND OVER.
 - VERTICAL SUPPORT: STEEL RISER CLAMP.
 - FLOOR SUPPORT, HOT PIPE SIZES TO 4" AND ALL COLD PIPE SIZES: CARBON STEEL ADJUSTABLE PIPE SADDLE, LOCKNUT NIPPLE, FLOOR FLANGE, CONCRETE PIER OR STEEL SUPPORT SIZED FOR PIPE ELEVATION.
 - FOR PIPE SIZES 1-1/2" AND SMALLER, PROTECT INSULATED HORIZONTAL PIPE AT POINT OF SUPPORT BY 180 DEGREE, 12" LONG SHEET METAL SHIELD. NO HANGER SHALL PENETRATE OR CRUSH INSULATING MATERIAL.
 - FOR PIPE SIZES 2" AND LARGER, PROTECT INSULATED HORIZONTAL PIPE AT POINT OF SUPPORT BY 180 DEGREE, 12" LONG GALVANIZED METAL SHIELD SURROUNDING 180 DEGREE INSERT OF HIGH DENSITY CALCIUM SILICATE INSULATION OF SAME THICKNESS AS ADJOINING PIPE INSULATION, ON COLD PIPING. EXTEND INSULATION INSERT 1" BEYOND SHEET METAL SHIELD AT EACH END. OVERSIZE HANGERS TO ACCOMMODATE SHIELDED INSERTS. NO HANGER SHALL PENETRATE OR CRUSH INSULATING MATERIAL. AT CONTRACTOR'S OPTION, PRE-MANUFACTURED THERMAL HANGER SHIELDS WITH INTEGRAL VAPOR BARRIER, EQUIVALENT TO VALUE ENGINEERED PRODUCTS PRO-SHIELD OR PRO-SHIELD NT, MAY BE UTILIZED. FOR EXTERIOR INSTALLATIONS USE WEATHER SHIELD WITH ALUMINUM JACKET.
 - PROVIDE COPPER PLATED HANGERS AND SUPPORTS FOR COPPER PIPING WHERE PIPING AND HANGER ARE IN DIRECT CONTACT WITH ONE ANOTHER.

- PIPE HANGER RODS:
- THREADED STEEL.

- PIPE HANGERS AND SUPPORTS:
- SUPPORT HORIZONTAL PIPING AS FOLLOWS:

NOMINAL PIPE SIZE	MAXIMUM HANGER SPACING			HANGER ROD DIAMETER
	STEEL	COPPER	SCHEDULE 40 PVC	
1-1/2" AND SMALLER	6'-0"	6'-0"	4'-0"	3/8"
2" TO 4"	10'-0"	10'-0"	4'-0"	3/8"
5" TO 8"	10'-0"	10'-0"	4'-0"	1/2"

- INSTALL HANGERS TO PROVIDE MINIMUM 12" CLEAR SPACE BETWEEN FINISHED COVERING AND ADJACENT WORK, EXCEPT WHERE UL LISTING FOR FIRE RATED CEILING REQUIRES 4" MINIMUM SEPARATION.
- SUPPORT HORIZONTAL, CAST IRON HUB AND SPIGOT PIPE WITHIN 1'-0" OF EACH HUB AND WITH 5'-0" MAXIMUM SPACING BETWEEN HANGERS, EXCEPT THAT PIPE EXCEEDING 5'-0" IN LENGTH SHALL BE SUPPORTED AT INTERVALS NO GREATER THAN 10'-0". SUPPORT HORIZONTAL NO-HUB CAST IRON PIPE RINGS AT EACH FITTING AND AT 10'-0" MAXIMUM SPACING. SUPPORT HORIZONTAL NO-HUB CAST IRON PIPE, SUPPORT HORIZONTAL NO-HUB PIPES LONGER THAN 4'-0" ON BOTH SIDES OF EACH JOINT.
- PLACE HANGER WITHIN 1'-0" OF EACH ELBOW OR TEE.
- SUPPORT VERTICAL PIPING AT EVERY FLOOR. SUPPORT VERTICAL SOIL PIPE AT EACH FLOOR AT HUB. SUPPORT NO-HUB PIPE 30 WEIGHT IS CARRIED FROM PIPE TO SUPPORT AND NOT FROM JOINT TO SUPPORT. SUPPORT 2" AND SMALLER PIPES MIDWAY BETWEEN FLOORS WITH RESTRAINTS ADEQUATE TO PREVENT PERPENDICULAR AXIAL MOVEMENT.
- SUPPORT EACH BRANCH PIPE TO EQUIPMENT AT TAKE-OFF AND WITHIN 12" OF TERMINATION.
- PROVIDE GALVANIZED STEEL INSULATION PROTECTION SADDLES AT ALL SUPPORT POINTS FOR INSULATED PIPES AT TRAPEZE HANGERS.
- ANCHOR ALL SUPPORTING LUGS OR GUIDES TO BUILDING STRUCTURE.
- ANCHOR AND SUPPORT WATER CONNECTIONS TO PLUMBING FIXTURES, IN PIPE CHASES OR WALLS, TO FIXTURE CARRIERS OR WASTE AND VENT PIPING. SUPPORTS SHALL BE SIMILAR TO ADJUSTO-SPACER SYSTEM AS MANUFACTURED BY THOMAS INDUSTRIES. PLACE ADJUSTO-SPACERS EVERY 10'-0" ON VERTICAL PIPE AND EVERY 5'-0" ON HORIZONTAL PIPE. INSULATE PIPE AREA IN CONTACT WITH ADJUSTO-SPACERS WITH DUCT TAPE, FELT LINER, OR PLASTIC LINER MATERIAL.

- FLASHING AND SAFING:
- WHERE EXPOSED PIPING PASSES THROUGH WALLS, FLOORS, ROOFS, PROVIDE CHROME PLATED OR STAINLESS STEEL ESCUTCHEON FOR PIPING.
 - FLASH AND COUNTERFLASH WHERE MECHANICAL EQUIPMENT PASSES THROUGH WEATHER. OR WATER-PROOFED WALLS, FLOORS, ROOFS.
 - PROVIDE PRE-MANUFACTURED PIPE BOOT FOR VENT AND/OR WASTE STACKS PASSING THROUGH ROOF. SECURE BOOT TO PIPE WITH STAINLESS STEEL BAND CLAMP OR OTHER CLAMPING DEVICE AS APPROVED BY ROOFING MANUFACTURER, RE: ARCHITECT.

SLEEVES

- PROVIDE PIPE SLEEVES TO APPLICABLE TRADES WITH PRECISE ROUGH-IN LOCATIONS FOR PIPES PASSING THROUGH CONCRETE OR MASONRY CONSTRUCTION. UNLESS OTHERWISE INDICATED, SLEEVES SHALL BE OF SIZE TO PROVIDE FROM 1/4" TO 1" CLEARANCE BETWEEN BARE PIPE AND SLEEVE. WHERE PIPE PASSES THROUGH CONCRETE FLOOR, EXTEND SLEEVE MINIMUM 1" ABOVE FINISHED FLOOR.
- SLEEVES IN BEARING WALLS, WATERPROOF MEMBRANE FLOORS, WET AREAS SHALL BE STEEL PIPE OR CAST IRON PIPE.
- WHERE UNINSULATED PIPES PENETRATE BEARING WALLS (EXCLUDING FOUNDATIONS), FIRE RATED WALLS, PARTITIONS, FLOORS, PACK AND SEAL ENTIRE SPACE BETWEEN PIPE AND SLEEVE WITH DOW CORNING 9454H SILICONE PUTTY FOAM OR 1" MINIMUM THICKNESS OF 3M FIRE BARRIER, CP-25 CAULK, OR 303 PUTTY ON EACH SIDE OF OPENING.
- ENCASE ALL INSULATED PIPES PENETRATING FIRE WALLS AND FLOORS IN 360 DEGREE METAL-SHIELDED INSULATION INSERTS AS MANUFACTURED BY VALUE ENGINEERED PRODUCTS. PACK AND SEAL SPACE BETWEEN SHIELD AND SLEEVE PER PRECEDING PARAGRAPH. EXTEND INSULATION INSERT ON ALL DOMESTIC WATER LINER 1" BEYOND SHEET METAL SHIELD.
- PIPE TO SLEEVE CLOSURE FOR PIPES PENETRATING FOUNDATIONS, WATERPROOFING MEMBRANE FLOORS, WET AREAS SHALL BE "LINK-SEAL".

METERS AND GAUGES

- SUBMITTALS:
- FURNISH MANUFACTURER'S SUBMITTAL DATA FOR: THERMOMETERS, PRESSURE GAUGES, FLOW MEASURING DEVICES, TEST PLUGS.
- PORTABLE INSERTION TYPE THERMOMETERS:
- 5" STEMS, ACCURATE WITHIN 1% OVER DIAL RANGE, HERMETICALLY SEALED.
- CONSTANT READ THERMOMETERS:
- MERCURY FREE THERMOMETER: 9" ALUMINUM CASE, NON-TOXIC HEAT TRANSFER MEDIUM-FILLED TUBE, SEPARABLE SOCKET CONNECTION, EXTENSION NECK TO CLEAR INSULATION, SWIVEL ANGLE STEM, FULLY ADJUSTABLE. ACCURATE WITHIN 1% OVER DIAL RANGE.
- PORTABLE INSERTION TYPE PRESSURE GAUGES:
- CRIPICE OR VENTURI TYPE, FACTORY ASSEMBLED WITH 300 PSIG RATED BALL VALVE OR 125 PSIG RATED MULTI-TURN GLOBE VALVE WITH ADJUSTABLE MEMORY STOP. SCHRAEDER TYPE PRESSURE TEST PORTS AND CAPS WITH PORT EXTENSIONS. CHAINED METAL TAG INDICATING LOCATION, GPM, AND METER READING.
- CONSTANT READ PRESSURE GAUGES:
- 4-1/2" OR 5" DIAL, STANDARD BLACK CASE, BRASS PRESSURE SNUBBER AND NEEDLE VALVE. ACCURATE WITHIN 1% OVER MIDDLE HALF OF SCALE RANGE, 2% OVER REMANDER.
- FLOW MEASURING DEVICE:
- CRIPICE OR VENTURI TYPE, FACTORY ASSEMBLED WITH 300 PSIG RATED BALL VALVE OR 125 PSIG RATED MULTI-TURN GLOBE VALVE WITH ADJUSTABLE MEMORY STOP. SCHRAEDER TYPE PRESSURE TEST PORTS AND CAPS WITH PORT EXTENSIONS. CHAINED METAL TAG INDICATING LOCATION, GPM, AND METER READING.
- INSTALLATION:
- MOUNT THERMOMETERS TO BE EASILY READ FROM FLOOR.
 - INSTALL FLOW MEASURING DEVICES PER MANUFACTURER'S RECOMMENDATIONS.
 - FURNISH METERING STATION WITH PERMANENT METAL TAG MARKED WITH STATION DESIGNATION, GPM, METER READING FOR GPM.

MECHANICAL IDENTIFICATION

- PIPE IDENTIFICATION:
- IDENTIFY EACH BRANCH PIPING SYSTEM AND INDICATE DIRECTION OF FLOW WITH BAND-SECURED OR SNAP-ON PRINTED LABELS IN MECHANICAL ROOM AND OTHER EXPOSED AREAS AND PRESSURE SENSITIVE, SELF-ADHESIVE LABELS IN CONCEALED AREAS. APPLY MARKINGS AFTER PAINTING AND CLEANING OF PIPING AND INSULATION IS COMPLETED.
 - APPLY LEGEND AND FLOW ARROWS AT VALVE LOCATIONS, AT POINTS WHERE PIPING ENTERS OR LEAVES VALVE OR METER BOX, AT NOT LESS THAN EVERY 30'-0" OF RUN OR AT LEAST ONCE IN EVERY EXPOSED LOCATION. LOCATE MARKINGS FOR MAXIMUM VISIBILITY.
 - WORKING-COLOR COMBINATIONS SHALL MEET ANSI SPECIFICATIONS UNLESS COLORS ARE SPECIFIED OTHERWISE.
 - SIZES OF LETTERING AND FLOW ARROWS SHALL BE AS FOLLOWS:

OUTSIDE DIAMETER OF PIPE OR COVERING (INCLUSIVE)	SIZE OF LETTER	MINIMUM LENGTH OF FLOW ARROW
5/8" TO 2"	1/2"	2-1/2"
2-1/2" AND LARGER	1"	4"

MECHANICAL INSULATION

- GENERAL:
- ADHESIVES AND INSULATION MATERIALS, COMPOSITE FIRE AND SMOKE HAZARD RATINGS MAXIMUM 25 FOR FLAME SPREAD AND 50 FOR SMOKE DEVELOPED. ADHESIVES SHALL BE WATERPROOF.
- PIPE INSULATION:
- HEAVY DENSITY ONE-PIECE FIBERGLASS, FACTORY APPLIED VAPOR BARRIER JACKET, DOUBLE SURFACE ADHESIVE SELF-SEALING LAP, "K" FACTOR 0.23 AT 75 F MEAN TEMPERATURE. INSULATION EXPOSED TO WEATHER, PROTECT INSULATION WITH WEATHERPROOF METAL JACKET. JACKET SHALL BE FACTORY APPLIED ALUMINUM, 0.016" THICK, WITH LAMINATED VAPOR BARRIER AND "Z" GROOVE WATER/TIGHT SEAL. SEAL EACH JOINT WITH SNAP STRAPS CONTAINING PERMANENT PLASTIC SEALING COMPOUND. SECURE WITH 1/2" WIDE STAINLESS STEEL BANDS. INSULATE FITTINGS WITH MITERED SECTIONS OF SAME MATERIAL. SEAL JOINTS WITH SEALING COMPOUND AND PREFORMED ALUMINUM BANDS.
- INSTALLATION OF PIPE INSULATION:
- SEAL LONGITUDINAL LAPS WITH VAPOR BARRIER ADHESIVE OR WITH FACTORY APPLIED DOUBLE SURFACE PRESSURE SENSITIVE ADHESIVE SYSTEM. SEAL END JOINTS WITH 3" WIDE BUTT STRIPS SECURED WITH VAPOR BARRIER ADHESIVE. SEAL ALL SEAMS ON COLD WATER PIPING WITH BENJAMIN FOSTER 30-35 SEAL FAST MASTIC.
- INSTALLATION OF INSULATION ON FITTINGS AND VALVES:
- INSULATE FITTINGS AND VALVES WITH FIRMLY COMPRESSED FOIL-FACED FIBERGLASS BLANKET AND 25/50 UL RATED PVC FITTING COVERS (ZESTON OR EQUAL).
 - WHERE INSTALLATION OF PVC FITTING COVERS IS PROHIBITED BY LOCAL AUTHORITIES, INSULATE FITTINGS AND VALVES WITH MOLDED FIBERGLASS FITTINGS OR FIRMLY COMPRESSED FOIL-FACED FIBERGLASS BLANKET. SECURE IN PLACE WITH 20 GAUGE CORROSION RESISTANT WIRE AND APPLY SMOOTHING COAT OF INSULATING GEMENT. FINISH WITH LAYER OF GLASS CLOTH EMBEDDED BETWEEN TWO COATS OF VAPOR BARRIER MASTIC. LAP GLASS FABRIC 2" ONTO ADJACENT INSULATION.
 - INSULATION ON FITTINGS AND VALVES SHALL BE SAME THICKNESS AS ON PIPE.
- INSULATION SCHEDULE:

SERVICE	PIPE SIZE	THICKNESS
DOMESTIC COLD WATER	ALL	1"
DOMESTIC HOT WATER	1-1/2" AND SMALLER	1"
DOMESTIC HOT WATER REGRUCLATION	2" AND LARGER	2"
ROOF DRAIN, OVERFLOW DRAIN PIPING (VERTICAL LEADER FROM DRAIN BOWLS, AND ALL HORIZONTAL)	ALL	1/2"
ROOF DRAIN, OVERFLOW DRAIN BOWL	ALL	1"

TESTING AND BALANCING





































- STATUS OF SYSTEMS:
- DO NOT BEGIN TESTING AND BALANCING WORK UNTIL SYSTEM HAS BEEN COMPLETED AND IS IN FULL WORKING ORDER.
 - PUT SYSTEMS AND EQUIPMENT INTO FULL OPERATION AND CONTINUE OPERATION OF SAME DURING EACH WORKING DAY OF TESTING AND BALANCING. ASCERTAIN PRELIMINARY TAB REQUIREMENTS PRIOR TO COMMENCEMENT OF WORK THROUGH REVIEW OF AVAILABLE DRAWINGS AND SPECIFICATIONS. MAKE VISUAL OBSERVATIONS AT SITE DURING CONSTRUCTION TO DETERMINE LOCATION AND SUITABILITY OF REQUIRED BALANCING DEVICES.
- REQUIREMENTS OF WORK:
- DOMESTIC CIRCULATING HOT WATER:
 - ADJUST MANUAL BALANCING VALVES IN SYSTEM SO ALL HOT WATER OUTLETS RECEIVE ADEQUATE SUPPLY OF HOT WATER.
 - WHEN BALANCING IS DONE, MARK VALVES IN BALANCED POSITION, SET LOCKING RINGS.

- GENERAL PIPE TESTING:
- TEST ALL PIPING SYSTEMS, CORRECT LEAKS BY REMAKING JOINTS. REMOVE EQUIPMENT NOT ABLE TO WITHSTAND TEST PRESSURE FROM SYSTEM DURING TEST. CONSULT GOVERNING CODES FOR SPECIAL SYSTEM REQUIREMENTS.
 - TEST PIPING BEFORE BEING PERMANENTLY ENCLOSED.
 - OBTAIN CERTIFICATES OF APPROVAL, ACCEPTANCE, COMPLIANCE WITH REGULATIONS OF AGENCIES HAVING JURISDICTION. SUBMIT TO OWNER.

TESTING AND BALANCING (CONTINUED)

- CHLORINATION OF DOMESTIC WATER LINE:
- STERILIZE DOMESTIC WATER SYSTEM AFTER PRESSURE TESTS HAVE BEEN COMPLETED. FLUSH ENTIRE SYSTEM, INTRODUCE CHLORINE OR HYPOCHLORITE TO NOT LESS THAN 50 PPM RESIDUAL CHLORINE. LET STAND FOR 24 HOURS MINIMUM.
 - FLUSH SYSTEM WITH CLEAN WATER UNTIL CHLORINE CONTENT IS REDUCED TO 1 PPM AT POINT FURTHEST FROM WHERE CHLORINE WAS INTRODUCED.
- SYSTEM TESTS:
- HYDROSTATIC TEST - WATER PIPING (NEW PIPING ONLY): HAND PUMP SYSTEM TO GREATER OF 100 PSIG OR 150% OF OPERATING PRESSURE. MAINTAIN PRESSURE UNTIL SYSTEM HAS BEEN INSPECTED FOR LEAKS BUT NOT LESS THAN FOUR HOURS.
 - COMPRESSED AIR OR NITROGEN TEST FOR NATURAL GAS PIPING: SUBJECT PIPING SYSTEM TO REQUIRED GAS PRESSURE WITH OIL FREE AIR OR NITROGEN. SYSTEM SHALL MAINTAIN PRESSURE FOR DURATION OF SOAPY WATER TEST OF EACH JOINT. TEST PRESSURE OF 100 PSIG FOR 4 HOURS OR TEST PRESSURE OF 80 PSIG OR ABOVE FOR 24 HOURS SHOWING NO PRESSURE DROP EXCEPT THAT CAUSED BY TEMPERATURE CHANGES. DO NOT USE FLAME OR OTHER LIQUID FOR TESTING. DO NOT REPAIR DEFECTS IN GAS PIPING OR FITTINGS. REMOVE AND REPLACE WITH SOUND MATERIAL.
 - WASTE, DRAIN, VENT PIPING: FILL SYSTEM WITH WATER TO POINT OF OVERFLOW BUT NOT LESS THAN 10'-0" HEAD. MAINTAIN WATER LEVEL FOR 4 HOURS.

PLUMBING LEGEND

NOT ALL ITEMS LISTED BELOW ARE USED ON THIS SET OF PLUMBING DRAWINGS					
PLUMBING PIPING		PIPING SYMBOLS			
SYMBOL	ABBV. DESCRIPTION	SYMBOL DESCRIPTION			
---	CW DOMESTIC COLD WATER	 WALL HYDRANT			
---	HW DOMESTIC HOT WATER	 HOSE BIBB			
---	HWC DOMESTIC HOT WATER CIRCULATION	 BALL VALVE			
180	DOMESTIC HOT WATER AT TEMP. SHOWN	 CALIBRATED BALANCING VALVE			
T	T TEMPERED WATER	 GATE VALVE			
TR	TR TEMPERED WATER CIRCULATION	 CHECK VALVE			
W	W SOIL OR WASTE	 SOLENOID VALVE			
GW	GW GREASE WASTE	 PRESSURE REDUCING VALVE			
SOD	SOD SEDIMENT & OIL DRAIN	 GAS VALVE			
BD	BD BUILDING DRAIN	 PUMP			
BS	BS BUILDING SEWER	 ATMOSPHERIC VACUUM BREAKER			
PD	PD PUMP DISCHARGE LINE	 STRAINER			
D	D DRAIN	 RELIEF VALVE			
V	V SANITARY VENT	 DOWNSPOUT NOZZLE			
SD	SD STORM DRAIN	 WATER HAMMER ARRESTER			
OD	OD OVERFLOW DRAIN	 UNION			
SS	SS STORM SEWER	 REDUCER			
F	F FIRE SPRINKLER	 WATER METER			
FDC	FDC FIRE DEPT. CONNECTION	 PRESSURE GAUGE			
G	G NATURAL GAS	 THERMOMETER			
LG	LG LOW PRESSURE NATURAL GAS	 FLOOR SINK			
MPG	MPG MEDIUM PRESSURE	 AREA/FLOOR DRAIN			
LPG	LPG PROPANE GAS	 ROOF DRAIN OR OVERFLOW DRAIN			
CA	CA COMPRESSED AIR	 WALL CLEANOUT AND LINE CLEANOUT			
PLUMBING PIPING SYMBOLS		 FLOOR CLEANOUT			
SYMBOL	DESCRIPTION	 CONNECT NEW TO EXISTING			
	ARROW IN LINE INDICATES DIRECTION OF FLOW	 RISER BUBBLE AND REFERENCE BUBBLE			
	INDICATES PIPE SLOPE DOWN	 EQUIPMENT DESIGNATION			
	REMOVE EXISTING				
	BOTTOM PIPE CONNECTION				
	PIPING UP				
	PIPING DOWN				
	FIXTURE TRAP OR DRAIN TRAP				
	PIPING CAP OR PLUG				
ABBREVIATIONS					
AFF	ABOVE FINISHED FLOOR	FCO	FLOOR CLEAN OUT	NC	NORMALLY CLOSED
AFG	ABOVE FINISHED GRADE	FPC	FIRE PROT. CONTROLLER	NC	NOT IN CONTACT
AP	ACCESS PANEL	GC	GENERAL CONTRACTOR	NO	NORMALLY OPEN
BFP	BACKFLOW PREVENTER	IE	INVERT ELEVATION	NTS	NOT TO SCALE
DNZ	DOWNSPOUT NOZZLE	LOC	LINE CLEAN OUT	SCD	SURFACE CLEANOUT
(E)	EXISTING	MC	MECHANICAL CONTRACTOR	TYP	TYPICAL
EC	ELECTRICAL CONTRACTOR	MH	MANHOLE	VCL	VENT CLEAN OUT
EL	ELEVATION	(N)	NEW	VTR	VENT THROUGH ROOF



DOMESTIC EXPANSION TANK SCHEDULE

WATER HAMMER ARRESTOR SCHEDULE


WASTE AND VENT RISER DIAGRAM

1331 Nineteenth Street
Denver, CO. 80202

CONSULTANT:



M.E.P. ENGINEERING
6402 S. Troy Circle (W) 303.936.1633
Centennial, CO 80111 (F) 303.934.3299
info@mep-eng.com www.mep-eng.com



PROJECT:

CS AUDITORIUM
RESTROOM
RENOVATION

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

COLORADO SPRINGS
CITY AUDITORIUM

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/2015 BIDDING AND ISSUE FOR CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO:	15242
-------------	-------

DRAWN BY: RLS



CHECKED BY:	MAB
-------------	-----

SHEET TITLE:

ENLARGED BASEMENT PLUMBING PLANS

P-110

SHEET OF



ENLARGED BASEMENT PLUMBING DEMO PLAN



SCALE: 1/4" = 1'-0"

○ **DRAWING NOTES:**

1. EXISTING 2" CW TO REMAIN.
2. EXISTING CW PIPING TO BE REMOVED BACK TO 2" CW MAIN. CAP WATER TIGHT.
3. EXISTING HW PIPING TO BE REMOVED IN ITS ENTIRETY BACK TO EXISTING HOT WATER HEATER (FIRST LEVEL).
4. EXISTING BUILDING DRAIN TO BE REMOVED BACK TO THE POINT OF DISCONNECT.
5. EXISTING BUILDING DRAIN TO REMAIN.
6. EXISTING WASTE/VENT STACK TO REMAIN.

GENERAL NOTES:

1. CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS BEFORE COMMENCING WORK AND NOTIFY ARCHITECT AND ENGINEER IN WRITING OF DISCREPANCIES FROM THE CONTRACT DRAWINGS. COMMENCEMENT OF WORK WITHOUT NOTIFICATION CONSTITUTES ACCEPTANCE OF EXISTING CONDITIONS.
2. COORDINATE ALL DEMOLITION AND NEW WORK WITH ALL OTHER DIVISIONS AS REQUIRED TO PROVIDE A COMPLETE INSTALLATION.




ENLARGED BASEMENT PLUMBING PLAN

SCALE: 1/4" = 1'-0"



 DRAWING NOTES:

1. 2"V UP.
2. 3/4"HW & 3/4"CW UP.
3. 1"HW FROM ABOVE, 1"CW UP.
4. 1"CW UP.
5. 3/4"CW UP.



Key Plan

C:\Users\RSStutz\Documents\15242_MEP_RSStutz.rvt
10/20/2015 1:03:42 PM





LEVEL 1 ENLARGED RESTROOM PLUMBING DEMO PLAN
SCALE: 1/4" = 1'-0"

DRAWING NOTES:

- EXISTING 4 KW ELECTRIC WATER HEATER TO REMAIN. CONTRACTOR TO INSPECT FOR PROPER WORKING CONDITION AND REPORT. REMOVE ALL EXISTING HW & CW DISTRIBUTION PIPING, VALVES ASSOCIATED WITH WATER HEATER.
- REMOVE EXISTING PLUMBING FIXTURES AND ASSOCIATED PIPING IN THEIR ENTIRETY.
- REMOVE EXISTING FLOOR DRAIN AND ASSOCIATED PIPING. PATCH FLOOR TO MATCH EXISTING.

GENERAL NOTES:


- CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS BEFORE COMMENCING WORK AND NOTIFY ARCHITECT AND ENGINEER IN WRITING OF DISCREPANCIES FROM THE CONTRACT DRAWINGS. COMMENCEMENT OF WORK WITHOUT NOTIFICATION CONSTITUTES ACCEPTANCE OF EXISTING CONDITIONS.
- COORDINATE ALL DEMOLITION AND NEW WORK WITH ALL OTHER DIVISIONS AS REQUIRED TO PROVIDE A COMPLETE INSTALLATION.



LEVEL 1 ENLARGED RESTROOM PLUMBING PLAN
SCALE: 1/4" = 1'-0"

DRAWING NOTES:

- 1" CW FROM BELOW AND CONNECT TO EXISTING WATER HEATER.
- 1" HW FROM EXISTING WATER HEATER AND DOWN.
- 1" CW FROM BELOW AND CONNECT TO PLUMBING FIXTURE.
- CONNECT NEW 2" CW TO EXISTING 2" CW IN CHASE. HEADER IN CHASE AND PROVIDE A CONNECTION TO EACH PLUMBING FIXTURE.
- 3/4" HW, 3/4" CW FROM BELOW. ROUTE IN FURRED WALL AND PROVIDE A CONNECTION TO EACH PLUMBING FIXTURE.
- 3/4" CW FROM BELOW AND CONNECT TO PLUMBING FIXTURE.



Key Plan

SLATERPAULL
hord | coplan | macht

1331 Nineteenth Street | P 303.607.0977
Denver, CO. 80202 | www.slaterpaul.com

CONSULTANT:



M.E.P. ENGINEERING
6402 S. Troy Circle (W) 303.936.1633
Centennial, CO 80111 (F) 303.934.3299
info@mep-eng.com www.mep-eng.com



PROJECT:

**CS AUDITORIUM
RESTROOM
RENOVATION**

221 E Kiowa St Colorado Springs, CO 80903

OWNER:

**COLORADO SPRINGS
CITY AUDITORIUM**

221 E Kiowa St
Colorado Springs, CO 80903

ISSUE:

10/16/2015 BIDDING AND ISSUE FOR
CONSTRUCTION

DRAWING INFORMATION:

PROJECT NO: 15242

DRAWN BY: RLS

CHECKED BY: MAB

APPROVED BY: MCS

SHEET TITLE:

**ENLARGED FIRST
LEVEL PLUMBING
PLANS**

P-111

SHEET OF