

<b>APPENDIX A1 - PRICE SHEET PATTY JEWETT</b>			
<b>Item #</b>	<b>Equipment</b>	<b>Qty</b>	<b>UI</b>
1	Full circle valve in head with swing joint & wire spaced at 65'	926	EA
2	Part circle valve in head with swing joint and wire spaced at 65'	856	EA
4	Part circle valve in head with tail nozzle, swing joint and wire spaced at 65'	114	EA
5	Full circle valve in head short radius sprinkler with swing joint and wire spaced at 50'	32	EA
6	Part circle valve in head short radius sprinkler with swing joint and wire spaced at 50'	427	EA
7	Part Circle short radius block zone sprinkler with swing joint spaced at 25'	257	EA
8	Quick Coupler	69	EA
9	Winter watering hydrant /QC assembly	31	EA
10	48 station irrigation controller with grounding	1	EA
11	1.5" Electric valve assembly for short radius block zone sprinkler heads	46	EA
12	Lateral Isolation Valve on 6" ML	153	EA
13	Lateral Isolation Valve on 8" ML	73	EA
14	Lateral Isolation Valve on 10" ML	43	EA
15	Lateral Isolation Valve on 12" ML	12	EA
16	Lateral Isolation Valve on 14" ML	12	EA
17	Mainline Gate Valve 6"	24	EA
18	Mainline Gate Valve 8"	11	EA
19	Mainline Gate Valve 10"	7	EA
20	Mainline Gate Valve 12"	3	EA
21	Air release valve assembly on 6" mainline	5	EA
22	2" Drain valve assembly on 6" mainline	2	EA
23	2" Drain valve assembly on 8" mainline	2	EA
24	2" Drain valve assembly on 10" mainline	1	EA
25	2" Winter quick coupler isolation valve on 6" mainline	14	EA
26	2" Winter quick coupler isolation valve on 8" mainline	7	EA
27	2" Winter quick coupler isolation valve on 10" mainline	5	EA
28	2" Winter quick coupler isolation valve on 12" mainline	1	EA
29	2" Winter quick coupler isolation valve on 14" mainline	2	EA
30	Central computer	1	EA
31	Weather Station	3	EA
32	6" Cross connection	4	EA
33	Winterization connection	1	EA
34	Wall Mount Smart Hub	4	EA
35	Grounding Assembly	55	EA
<b>Mainline and Lateral Piping</b>			
36	2" DR11 HDPE Lateral Piping 18" bury	122,000	LF
37	2" DR11 HDPE Pipe for Block Zone Sprinklers 18" bury	5,500	LF
38	2" DR11 HDPE Lateral Piping for winter hydrants 24" bury	2,000	LF
39	6" DR13.5 HDPE Mainline piping	17,000	LF
40	8" DR13.5 HDPE Mainline piping	8,000	LF
41	10" DR13.5 HDPE Mainline piping	5,500	LF
42	12" DR13.5 HDPE Mainline piping	1,550	LF
43	14" DR11 HDPE Mainline piping	1,200	LF
<b>Communication Wire Trunk Line #12 AWG</b>			
44	Path 1	4,000	LF
45	Path 2	3,500	LF
46	Path 3	4,000	LF
47	Path 4	4,000	LF
48	Path 5	4,500	LF
49	Path 6	6,000	LF
50	Path 7	4,000	LF
51	Path 8	5,500	LF
52	Path 9	4,000	LF
53	Path 10	4,000	LF
54	Path 11	3,000	LF
55	Path 12	5,000	LF
56	Path 13	3,500	LF
57	Path 14	3,000	LF
58	Toro Communication cable for Controller	7,000	LF
<b>Communication Wire Branch Line #14 AWG</b>			
59	Path 1	7,000	LF
60	Path 2	7,500	LF
61	Path 3	10,500	LF
62	Path 4	9,000	LF
63	Path 5	7,000	LF
64	Path 6	10,000	LF
65	Path 7	4,500	LF
66	Path 8	10,000	LF
67	Path 9	7,000	LF
68	Path 10	10,000	LF
69	Path 11	12,000	LF
70	Path 12	12,000	LF
71	Path 13	12,000	LF
72	Path 14	10,000	LF