

| APPENDIX A2 - PRICE SHEET VALLEY HI | | | |
|---|--|------------|-----------|
| Item # | Equipment | Qty | UI |
| 1 | Full circle valve in head with swing joint & wire spaced at 65' | 418 | EA |
| 2 | Part circle valve in head with swing joint and wire spaced at 65' | 525 | EA |
| 3 | Part circle valve in head with tail nozzle, swing joint and wire spaced at 65' | 84 | EA |
| 4 | Full circle valve in head short radius sprinkler with swing joint and wire spaced at 50' | 24 | EA |
| 5 | Part circle valve in head short radius sprinkler with swing joint and wire spaced at 50' | 482 | EA |
| 6 | Full or Part Circle short radius block zone sprinkler with swing joint spaced at 25' | 159 | EA |
| 7 | Quick Coupler | 0 | EA |
| 8 | Winter watering hydrant /QC assembly | 19 | EA |
| 9 | 1.5" Electric valve assembly for short radius block zone sprinkler heads | 27 | EA |
| 10 | Lateral Isolation Valve on 6" ML | 103 | EA |
| 11 | Lateral Isolation Valve on 8" ML | 32 | EA |
| 12 | Lateral Isolation Valve on 10" ML | 50 | EA |
| 13 | Mainline Gate Valve 6" | 19 | EA |
| 14 | Mainline Gate Valve 8" | 10 | EA |
| 15 | Mainline Gate Valve 10" | 7 | EA |
| 16 | Air release valve assembly on 6" mainline | 4 | EA |
| 17 | Air release valve assembly on 8" mainline | 1 | EA |
| 18 | Air release valve assembly on 10" mainline | 2 | EA |
| 19 | 2" Drain valve assembly on 6" mainline | 4 | EA |
| 20 | 2" Drain valve assembly on 8" mainline | 1 | EA |
| 21 | 2" Winter quick coupler isolation valve on 6" mainline | 12 | EA |
| 22 | 2" Winter quick coupler isolation valve on 8" mainline | 3 | EA |
| 23 | 2" Winter quick coupler isolation valve on 10" mainline | 3 | EA |
| 24 | Central computer | 1 | EA |
| 25 | Weather Station | 2 | EA |
| 26 | 6" Cross connection | 3 | EA |
| 27 | Winterization connection | 1 | EA |
| 28 | Wall Mount Smart Hub | 3 | EA |
| 29 | Grounding Assembly | 36 | EA |
| Mainline and Lateral Piping | | | |
| 30 | 2" DR11 HDPE Lateral Piping 18" bury | 75,000 | LF |
| 31 | 2" DR11 HDPE Pipe for Block Zone Sprinklers 18" bury | 3,000 | LF |
| 32 | 2" DR11 HDPE Lateral Piping for winter hydrants 24" bury | 500 | LF |
| 33 | 6" DR13.5 HDPE Mainline piping | 13,500 | LF |
| 34 | 8" DR13.5 HDPE Mainline piping | 5,000 | LF |
| 35 | 10" DR13.5 HDPE Mainline piping | 5,000 | LF |
| 36 | 12" DR13.5 HDPE Mainline piping | 80 | LF |
| 37 | 24" DR17 HDPE Intake Pipe | 80 | LF |
| Communication Wire Trunk Line #12 AWG | | | |
| 38 | Path 1 | 4,000 | LF |
| 39 | Path 2 | 6,000 | LF |
| 40 | Path 3 | 6,000 | LF |
| 41 | Path 4 | 4,500 | LF |
| 42 | Path 5 | 2,000 | LF |
| 43 | Path 6 | 3,000 | LF |
| 44 | Path 7 | 5,000 | LF |
| 45 | Path 8 | 5,000 | LF |
| 46 | Path 9 | 4,500 | LF |
| Communication Wire Branch Line #14 AWG | | | |
| 47 | Path 1 | 8,500 | LF |
| 48 | Path 2 | 9,500 | LF |
| 49 | Path 3 | 6,500 | LF |
| 50 | Path 4 | 8,500 | LF |
| 51 | Path 5 | 8,000 | LF |
| 52 | Path 6 | 9,500 | LF |
| 53 | Path 7 | 10,500 | LF |
| 54 | Path 8 | 6,000 | LF |
| 55 | Path 9 | 10,500 | LF |